This item was submitted to [Loughborough's Research Repository](#) by the author.
Items in Figshare are protected by copyright, with all rights reserved, unless otherwise indicated.

Safety risk assessment for vertical concrete formwork activities in civil engineering construction

PLEASE CITE THE PUBLISHED VERSION

<http://dx.doi.org/10.3233/WOR-131724>

PUBLISHER

© IOS Press

VERSION

AM (Accepted Manuscript)

PUBLISHER STATEMENT

This work is made available according to the conditions of the Creative Commons Attribution-NonCommercial-NoDerivatives 4.0 International (CC BY-NC-ND 4.0) licence. Full details of this licence are available at:
<https://creativecommons.org/licenses/by-nc-nd/4.0/>

LICENCE

CC BY-NC-ND 4.0

REPOSITORY RECORD

Lopez-Arquillos, A., Juan C. Rubio-Romero, Alistair G.F. Gibb, and J.A. Gambatese. 2019. "Safety Risk Assessment for Vertical Concrete Formwork Activities in Civil Engineering Construction". figshare.
<https://hdl.handle.net/2134/18081>.

SAFETY RISK ASSESSMENT FOR VERTICAL CONCRETE FORMWORK ACTIVITIES IN CIVIL ENGINEERING CONSTRUCTION.

Lopez-Arquillos, A; Rubio-Romero, JC; Gibb, AGF; Gambatese, JA (2014)

Work: A Journal of Prevention, Assessment & Rehabilitation, 49:2, 183-192,

ISSN 1051-9815, DOI 10.3233/WOR-131724

Abstract:

BACKGROUND: The construction sector has one of the worst occupational health and safety records in Europe. Of all construction tasks, formwork activities are associated with a high frequency of accidents and injuries.

OBJECTIVE: This paper presents an investigation of the activities and related safety risks present in vertical formwork for in-situ concrete construction in the civil engineering sector.

METHODS: Using the methodology of staticized groups, twelve activities and ten safety risks were identified and validated by experts. Every safety risk identified in this manner was quantified for each activity using binary methodology according to the frequency and severity scales developed in prior research. A panel of experts was selected according to the relevant literature on staticized groups.

RESULTS: The results obtained show that the activities with the highest risk in vertical formwork tasks are: Plumbing and leveling of forms, cutting of material, handling materials with cranes, and climbing or descending ladders. The most dangerous health and safety risks detected were falls from height, cutting and overexertion.

CONCLUSIONS The research findings provide construction practitioners with further evidence of the hazardous activities associated with concrete formwork construction and a starting point for targeting worker health and safety programmes.

Keywords: Occupational, expert panel, fall from height,

1. Introduction

According to the European Agency for Safety and Health at Work, the construction sector has one of the worst occupational health and safety records in Europe [1]. In the original 15 European Union (EU) Member States alone, about 1,300 construction workers die every year, another 800,000 are injured, and countless more suffer work-related ill health [2].

In the United States, 751 deaths occurred on construction sites in 2010 [3]. This figure accounts for about 17% of all fatal occupational injuries and is the fourth highest fatality rate for all U.S. industries. A similar problem exists in Spain where the fatality rate on construction sites in 2011 was 11.2 fatalities per 100,000 workers [4], with a total of 120 worker deaths.

Formwork is defined as a temporary structure whose purpose is to provide support and containment for fresh concrete until it can support itself. It molds the concrete to the desired shape and size, and controls its position and alignment [5]. Of all construction tasks, formwork activities are associated with a high frequency of accidents and injuries. Huang and Hinze [6] observed that 5.83% of falls were attributed to the construction of formwork or to the

construction of temporary structures and approximately 21% of all accidents involved wood framing or formwork construction. Many studies on construction safety are focused on topics such as contributing factors in construction accidents [7] or the impact of the different variables on the severity of the accidents [8,9,10,11,12,13,14,15]. Research studies have tried to quantify the safety risks of large-scale processes, such as underground construction projects [16] or buildings [17]. However, only one study was found in which the authors actually quantified the relative health and safety risks of specific construction tasks [18]. The objective of the latter study was to quantify the comprehensive health and safety risk at the activity level for a common construction process, such as formwork activities, using the Delphi method.

The aim of the present study is to quantify the health and safety risks in different vertical formwork activities in civil engineering construction using the binary method and the methodology of staticized groups.

2. Methodology

To achieve the study aim, the researchers used two different methodologies. A general research methodology was used to define the study's structure and a specific methodology inside this structure was used as a tool to elaborate the safety risk assessment.

With regard to the specific methodology, some authors have developed methods of risk quantification with different levels of complexity and application. An example of this is a study where ergonomic risks were analysed using ratings for each risk factor on a three-point scale [*insignificant, moderate and high*] in 65 construction activities to identify the presence of risk factors concerning overexertion injuries [19]. Other studies quantifying safety risk defined it as the product of frequency and severity [20]. A similar methodology with the addition of the exposure factor was used by Jannadi and Almishari [21]. The method we have chosen for this study is the approach known as the binary method [22], where the unit risk is defined as the product of frequency and severity (see Equation 1). Frequency is defined in terms of worker hours per incident, while severity is defined in terms of impact on the worker per incident.

$$\text{UNIT RISK} \left(\frac{\text{severity}}{\text{work-hour}} \right) = \text{Frequency} \left(\frac{\text{incident}}{\text{work-hour}} \right) \times \text{Severity} \left(\frac{\text{severity}}{\text{incident}} \right) (1)$$

Once the method for risk quantification was defined, the next step was to define a suitable research strategy to accomplish our specific goal.

According to a previous civil construction research [23] based on the Delphi method, cited method can be defined as systematic and interactive research technique for obtaining the judgment of a panel of independent experts on a specific topic. Panel members are selected according to predefined guidelines and are asked to participate in two or more rounds of structured surveys. After each round, an anonymous summary of the experts' input from the previous survey is provided as a part of the subsequent survey. In each subsequent round, participants are encouraged to review the anonymous opinion of the other panelists and consider revising their previous response. The goal during this process is to decrease the variability of the responses and achieve group consensus about a correct value. Finally, the process is concluded after a predefined criterion (as number of rounds or the achievement of consensus) is met and a statistical aggregation of the responses in the final round determines the results.

The staticized group technique is very similar to the Delphi method. The only methodological difference is the exclusion of feedback or iterations in the staticized group technique. Several studies have reported different opinions about the accuracy of both methods. Some of these studies have reported a significant increase of the staticized group technique over Delphi rounds as far as accuracy is concerned [24, 25]. By contrast, other studies found no substantial difference in the accuracy records when the Delphi and staticized group approaches were

compared [26, 27]. Meanwhile, two other surveys suggested that the accuracy of the Delphi method is worse when there is a high level of iterations [28, 29].

Authors such as Erffmeyer and Lane [30] are in favour of using the staticized group approach because panel members are not led to achieve a consensus on a value that could be wrong. This is the main reason why the present study was carried out using the method of staticized groups.

2.1 Panel Members

As in the Delphi procedure, in the staticized group approach the selection of experts is a very important factor in determining the quality of the study. Hallowell and Gambatese [23] maintain that the level of expertise is the most important facet in a panel member and propose guidelines for a flexible point system for the selection of an expert panel member. A suitable adaptation of the suggested point system to the specific goals of our research project resulted in the requirements listed in Table 1.

TABLE 1

The authors contacted 15 construction companies and 10 universities. After a review of the background and availability of the possible candidates, 12 experts were selected from 7 large high profile companies from the engineering construction sector, and from 5 Schools of Engineering. In addition to the flexible point system requirements, only one expert per company or per University was selected in order to ensure diversity in the origin of the experts.

According to the guidelines proposed by Hallowell and Gambatese [23], all members of the panel met the minimum level of requirements. As can be seen in Table 2, all of the panellists scored a total of at least 17 points and in at least four different achievement or experience categories. Four other professionals were selected as panel members, but they did not complete the survey and so were excluded from the final list of panel members and also from the results shown in Table 2.

TABLE 2

The qualifications of the selected members of the staticized groups are as follows.

- As a guarantee of expertise in Safety at Work and Occupational Risk, all members of the panel have obtained a Master in Occupational Risk Prevention degree. In our opinion, this is the most valuable requirement for our research, because it shows that the person has completed specific courses on occupational health and safety and, therefore, that he or she has the expertise to evaluate risks in the activities under study.
- Every member has a technical Bachelor's or Master's degree. Formwork activities in construction have a very important technical profile. Consequently, this requirement is considered highly relevant because previous training in technical issues is necessary to be able to form an accurate evaluation.
- Between them, the panellists have 94 years of experience in the construction sector. Experience is another extremely relevant requirement.
- Four of the panellists have contributed to 24 books related to construction safety and health or risk management.

2.2 Study Design

A web-survey used for collecting the expert responses was developed on a specialized site and was made available to the experts. Experts had access to the survey only by using a password supplied by the researchers. The web-survey expired after the collection of data in the above mentioned period of time.

In order to improve the quality of the study, certain strategies for study design and the elimination of bias were adopted. For example:

- The order of the questions and the order of the potential safety risk in the survey were randomized for each panel member to reduce the contrast effect and the primacy effect.
- Independent frequency and severity rates were implemented.
- The anonymity of each expert was ensured.

2.3 Survey Content

Following the guidelines of Hallowell and Gambatese [18], experts were provided with the incident classification descriptions (Table 3) and the formwork construction activity descriptions (Table 4). In line with the above, the selected incidents or health and safety risk classification were based on the Occupational Safety & Health Administration, Bureau of Labour Statistics, and Hinze accident classification systems [31].

The panellists were asked to provide their opinion on frequency rates and severity levels using the frequency and severity scales provided previously (Table 5&Table 6). These scales were created by Hallowell and Gambatese [18], and cover a complete spectrum of frequency and severity levels.

TABLES 3-6

3. Results and Discussion

Although consensus is not a requirement for the methodology of staticized groups, it was also calculated in order to compare the results with the Delphi approach (Table 7).

TABLE 7

To measure the variation in the responses, the absolute deviation was calculated using the following equation:

$$\text{Average Deviation from Median} = \text{Average} (\text{Median } j - \text{Value } ij)(2)$$

After calculating the absolute deviation from the median, and accepting that consensus is achieved with a value less than 1/10 of the possible value for the quantitative study developed, the target consensus was found to be achieved in this case.

Table 8 shows the quantified risk when all formwork activities are included by the following methods. First, the frequency ratings chosen by the expert from a range of values from table 5 with units of worker-hours per incident were converted into a single point value with units of incidents per worker-hour. Then single point values were multiplied by the severity values chosen by the experts according to the severity scale from Table 6.

TABLE 8

For example, if the expert rated the average frequency as 10-100 w-h /incident, the mean value of 55 w-h/incident was identified in order to convert to a single value, and the inverted value 0.018 [1/55] represented the frequency value for the particular risk and activity. The product of this frequency and the severity rating from table 6 represents the unit risk for the activities.

In a further analysis of the data matrix shown in Table 8, two different comparative tables were produced according to the sum values from a row [Activities] and from a column [Safety risks]. Table 9 summarizes the total safety risk score for each activity, and Table 10 shows the quantified risks when all formwork activities are included.

TABLE 9

Table 9 shows that the highest risk scores for the construction activities under study were obtained by the activities plumb/level forms (0.4772 S/w-h) cut material (0.0585 S/w-h), crane

material (0.0194 S/w-h) and ascend/descend ladder (0.0187S/w-h). On the other hand, the lowest risk scores were obtained by lubrication/preparation (0.0008S/w-h), manual transport (0.0006S/w-h) and inspect/plan (0.0002S/w-h). Some of the activities with the highest risk scores such as crane material or ascend and descend ladders, have been dealt with in other papers with a more general approach [32,33,34,35,36]. Our specific results for vertical formwork activities in construction are in line with other general results that are discussed below.

Surprisingly, the first and second highest risk score activities, that is, plumb/level forms and cut material, had not been studied before. This fact could be due to the highly specific activities involved. Consequently, further research concerning these issues is needed. It is especially significant that plumb/level forms accumulated approximately 80% of all of the risk. Therefore, it should be an activity which is the primary focus of safety management on the worksite.

Crane-lifting of material is one of the major causes of fatalities in construction [32]. To reduce the rate of crane fatalities, these authors believe that crane operators and riggers should be qualified and requalification courses should take place every 3 years. Likewise, other researchers [33] highlighted the fact that big contractors and other agents provide insufficient training for crew members. In addition, these authors found difficulties in communication among crew members, including language and a proper understanding of signals. Consequently, to improve the health and safety levels in these tasks, education programmes should be redesigned for all workers engaged in crane operations. Sometimes the risk is caused by deficiencies in the electrical system of the crane [34].

Ascending and descending ladders has been associated with a high percentage (33.5%) of the non-fatal accidents in construction workers in the United States [35]. Ladders were also associated with 11% of all fatal falls over the period 1980-1989 in the US. More recently, ladder-related accidents have been shown to be associated with risk factors that increased the probability of a serious or fatal accident [36]. Hallowell and Gambatese [18] found that this activity is one of the most dangerous. They studied formwork activities following a more general approach, that is, without concentrating on vertical civil works. To improve the safety records at work in this activity, we must make a more accurate risk assessment.

Regarding the health and safety risk values included in Table 10, the highest risk scores were obtained by fall to a lower level (0.5247 S/w-h), cutting (0.0591 S/w-h) and overexertion (0.0079 S/w-h). The lowest risk scores correspond to fall on the same level (0.0001 S/w-h), exposure to harmful substances (0.0000 S/w-h) and others (0.0000 S/w-h). The health and safety risks studied had previously been addressed by many papers on construction activities [18,19,37,38,39,40,41]. The results provided here on specific vertical formwork safety risks are in line with the results of other general studies on the same issue.

Given their fatal consequences, falls to a lower level in the construction industry have been extensively studied by many authors [35, 36, 37, 38, 39]. Although these authors studied falls in the construction industry, their research was not focused on falls related to a formwork task. The most relevant work on falls and formwork is the study carried out by Adam, Pallarés, and Calderon [41]. In this study, falls from a height during floor slab formwork of buildings are dealt with specifically. They compared the fall protection systems commonly used during floor slab formwork construction in buildings and concluded that the suitability of the different systems depends greatly on the willingness of the workers to use the systems. This fact should be taken into account when making the choice. Hallowell and Gambatese [18] found that falls to a lower level is a very important risk, but this result was obtained without distinguishing between the two types of formwork (vertical or horizontal). Unfortunately, no literature about the risk of falls in vertical formwork in civil engineering is available. In a similar way to the studied activities, fall to lower levels accumulated almost 88% of the total risk score. Therefore concentration on this aspect of the work will produce the greatest improvement in health and safety performance.

Overexertion injury is the single largest category of injuries in construction work. They account for about 24% of all injuries [19]. Everett's analysis shows that virtually all construction activities have moderate-to-high ratings for at least one risk factor, and thereby place craft workers at increased risk for overexertion injuries and disorders.

The authors of this paper have found no articles on the safety risk involved in formwork cutting activities.

To sum up, although there are several research papers on common health and safety issues in construction work, there is still a significant shortage of specific investigations on some of the activities and risks relating to tasks such as formwork erection dealt with in this paper.

4. Conclusions

The results of this study can be used as an important tool for making a risk assessment when a vertical formwork task is scheduled. Each construction project involves specific health and safety issues because each has different circumstances and environment. However, the general health and safety topics described in this research can be addressed effectively on each project.

As for preventive measures, resources are always limited and must be managed efficiently. Construction practitioners must first identify the most dangerous activities and their safety risks. This is the first step for prioritizing preventive measures according to a suitable scale of needs. The classification obtained according to the scores provided by expert panel members in this study placed plumb/level forms, cut material, crane-lift material, and ascend/descend ladder at the top of the list of activities with high risk factors. Likewise, fall to a lower level, cutting, and overexertion were the most dangerous safety risks according to the experts. Accordingly, special attention is needed to reduce these safety risks.

4.1 Limitations of the study

This research does not consider the exposure [worker-hours] to the hazards. The total risk will depend on the magnitude of the exposure [see Equation 3]. The exposure can vary significantly depending on the specific construction project.

$$\text{TOTAL RISK (severity)} = \text{Frequency} \left(\frac{\text{accident}}{\text{work-hour}} \right) \times \text{Severity} \left(\frac{\text{severity}}{\text{accident}} \right) \times \text{Exposure (work-hour)} \quad (3)$$

If the exposure is high but the unit risk is low, then the total risk may be high relative to the other activities. Similarly, if the exposure is low, but the unit risk is high, then the total risk may be low compared to the other activities. In spite of this fact, unit risk is a very important tool to quantify health and safety needs.

The results allow us to compare risk values between different activities, and value them in order to prioritize preventive resources. However, as a relative subjective scale, it cannot be said that greater than a specific value the risk is major and under this value the risk is minor.

4.2 Impact on the Industry

The conclusions from this research can be used by construction companies in several ways. Health and Safety managers and supervisors can improve associated risks with specific activities, especially with plumb/level forms activities and risks of falls to lower levels. Project engineers and designers can estimate the exposure time for their specific project and calculate the total risk. This calculation can be made considering the different formwork types and design solutions. Companies can use the results obtained in their occupational safety strategies and in their safety training programmes. The authors encourage further research on the issue and promote future solutions to prevent the risks involved.

ACKNOWLEDGMENTS

[edited for the review process]

REFERENCES

- [1] OSHA Europe. European Agency for Safety and Health at Work. Building in Safety - Prevention of risks in construction - in practice. : Office for Official Publications of the European Communities 2004; 2004.
- [2] OSHA Europe. European Agency for Safety and Health at Work. <http://osha.europa.eu/en/sector/construction>. 2012.
- [3] BLS. Bureau of Labor Statistics. National census of fatal occupational injuries in 2010 [preliminary results]. http://www.bls.gov/news.release/archives/cfoi_08252011.pdf. 2010.
- [4] INSHT. Instituto Nacional de Seguridad e Higiene en el Trabajo. Avance de siniestralidad laboral. Periodo octubre 2010-septiembre 2011. ; 2011.
- [5] Hanna AS. Concrete formwork systems. : CRC; 1998.
- [6] Huang X, Hinze J. Analysis of construction worker fall accidents. J Constr Eng Manage 2003;129[3]:262-271.
- [7] Haslam R, Hide S, Gibb AGF, Gyi DE, Pavitt T, Atkinson S, et al. Contributing factors in construction accidents. Appl Ergon 2005;36[4]:401-415.
- [8] Sawacha E, Naoum S, Fong D. Factors affecting safety performance on construction sites. Int J Project Manage 1999;17[5]:309-315.
- [9] Salminen S. Have young workers more injuries than older ones? An international literature review. J Saf Res 2004;35[5]:513-521.
- [10] Chau N, Gauchard GC, Siegfried C, Benamghar L, Dangelzer JL, Francais M, et al. Relationships of job, age, and life conditions with the causes and severity of occupational injuries in construction workers. Int Arch Occup Environ Health 2004;77[1]:60-66.
- [11] LópezArquillos A, Rubio Romero JC, Gibb A. Analysis of construction accidents in Spain, 2003-2008. J Saf Res 2012.
- [12] Choi SD. Safety and ergonomic considerations for an aging workforce in the US construction industry. Work: A Journal of Prevention, Assessment and Rehabilitation 2009;33(3):307-315.
- [13] Goldsheyder D, Weiner SS, Nordin M, Hiebert R. Musculoskeletal symptom survey among cement and concrete workers. Work: A Journal of Prevention, Assessment and Rehabilitation 2004;23(2):111-121.
- [14] Gillen M, Kools S, Sum J, McCall C, Moulden K. Construction workers' perceptions of management safety practices: A qualitative investigation. Work: A Journal of Prevention, Assessment and Rehabilitation 2004;23(3):245-256.
- [15] Liu M, Wei W, Fergenbaum J, Comper P, Colantonio A. Work-related mild-moderate traumatic brain injury and the construction industry. Work: A Journal of Prevention, Assessment and Rehabilitation 2011;39(3):283-290.
- [16] Choi HH, Cho HN, Seo J. Risk assessment methodology for underground construction projects. J Constr Eng Manage 2004;130[2]:258-272.
- [17] Aneziris O, Topali E, Papazoglou I. Occupational Risk of building construction. Reliab Eng Syst Saf 2011.

327 [18] Hallowell MR, Gambatese JA. Activity-based safety risk quantification for concrete
328 formwork construction. *J Constr Eng Manage* 2009;135[10]:990-998.

329 [19] Everett JG. Overexertion injuries in construction. *J Constr Eng Manage* 1999;125[2]:109-
330 114.

331 [20] Sun Y, Fang D, Wang S, Dai M, Lv X. Safety risk identification and assessment for
332 Beijing Olympic venues construction. *J Manage Eng* 2008;24[1]:40-47.

333 [21] Jannadi OA, Almishari S. Risk assessment in construction. *J Constr Eng Manage*
334 2003;129[5]:492-500.

335 [22] Romero JCR. Métodos de evaluación de riesgos laborales. : Ediciones Díaz de Santos;
336 2004.

337 [23] Hallowell MR, Gambatese JA. Qualitative research: application of the Delphi method to
338 CEM research. *J Constr Eng Manage* 2009;136[1]:99-107.

339 [24] Best RJ. An experiment in Delphi estimation in marketing decision making. *J Market Res*
340 1974;448-452.

341 [25] Rowe G, Wright G. The impact of task characteristics on the performance of structured
342 group forecasting techniques. *Int J Forecast* 1996;12[1]:73-89.

343 [26] Fischer GW. When oracles fail -A comparison of four procedures for aggregating
344 subjective probability forecasts. *Organ Behav Hum Perform* 1981;28[1]:96-110.

345 [27] Snizek JA. A comparison of techniques for judgmental forecasting by groups with
346 common information. *Group & Organization Management* 1990;15[1]:5-19.

347 [28] Gustafson DH, Shukla RK, Delbecq A, Walster GW. A comparative study of differences in
348 subjective likelihood estimates made by individuals, interacting groups, Delphi groups, and
349 nominal groups. *Organ Behav Hum Perform* 1973;9[2]:280-291.

350 [29] Boje DM, Murnighan JK. Group confidence pressures in iterative decisions. *Management*
351 *Science* 1982;28[10]:1187-1196.

352 [30] Erffmeyer RC, Lane IM. Quality and acceptance of an evaluative task: The effects of four
353 group decision-making formats. *Group & Organization Management* 1984;9[4]:509-529.

354 [31] Hinze J. Construction safety. : Prentice-Hall Upper Saddle River, NJ; 1997.

355 [32] Beavers J, Moore J, Rinehart R, Schriver W. Crane-related fatalities in the construction
356 industry. *J Constr Eng Manage* 2006;132[9]:901-910.

357 [33] Tam VWY, Fung IWH. Tower crane safety in the construction industry: A Hong Kong
358 study. *Saf Sci* 2011;49[2]:208-215.

359 [34] Rubio-Romero JC, Simón-Donaire JM. Principales defectos en las instalaciones eléctricas
360 de las grúas torre desmontables para obra. *Dyna*, 2009; 84[4]:321-326.

361 [35] Cattledge GH, Hendricks S, Stanevich R. Fatal occupational falls in the US construction
362 industry, 1980–1989. *Accident Analysis & Prevention* 1996;28[5]:647-654.

363 [36] Camino López MA, Ritzel DO, Fontaneda González I, González Alcántara OJ.
364 Occupational accidents with ladders in Spain: Risk factors. *J Saf Res* 2011.

365 [37] Derr J, Forst L, Chen HY, Conroy L. Fatal falls in the US construction industry, 1990 to
366 1999. *Journal of occupational and environmental medicine* 2001;43[10]:853-860.

367 [38] Dong XS, Fujimoto A, Ringen K, Men Y. Fatal falls among Hispanic construction workers.
368 *Accident Analysis & Prevention* 2009;41[5]:1047-1052.

369 [39] Gillen M. Injuries from construction falls. Functional limitations and return to work.
370 *AAOHN journal: official journal of the American Association of Occupational Health Nurses*
371 1999;47[2]:65.

[40] Cattledge GH, Schneiderman A, Stanevich R, Hendricks S, Greenwood J. Nonfatal occupational fall injuries in the West Virginia construction industry. *Accident Analysis & Prevention* 1996;28[5]:655-663.

[41] Adam JM, Pallarés FJ, Calderón PA. Falls from height during the floor slab formwork of buildings: Current situation in Spain. *J Saf Res* 2009;40[4]:293-299.

TABLES.

Table 1.Flexible point system for the selection of panel members.

Achievements or experience	Points
Master of Science in Occupational Risk Prevention	5
Technical Degree [Architect or Engineer]	4
Years of professional experience	1 per year
Professional registration	2
Author of a book on safety	2 per book
Author of an article on safety in a learned journal	2 per article
Faculty member at an accredited university	3
Ph.D.	4

383 Table 2. Panel members' scores

Panel Member	Master of Science in Occupational Risk Prevention	Technical Degree	Years of experience	Professional registration	Author of a book on safety	Author of an article on safety in a learned journal	Faculty member at and accredited university	PhD	Total Points	Number of achievement categories
Expert 1	5	4	18	2	32	22	3	4	90	8
Expert 2	5	4	23	0	0	4	3	0	39	5
Expert 3	5	4	12	0	4	12	0	0	37	5
Expert 4	5	4	10	2	4	0	0	0	25	5
Expert 5	5	4	13	2	0	0	0	0	24	5
Expert 6	5	4	0	0	8	0	3	4	24	5
Expert 7	5	4	12	2	0	0	0	0	23	4
Expert 8	5	4	6	2	0	0	0	0	17	4
TOTAL	40	32	94	10	48	38	9	8	279	41
Average	5.0	4.0	11.8	1.3	6.0	4.8	1.1	1.0	34.9	5.1

384

385

386 Table 3.Incident classification

Exposure to harmful substances
Fall to lower level
Fall onthe same level
Cutting
Overexertion
Struck against objects in motion
Struck against objects
Caught in or compressed
Repetitive motion
Others

387

388

389 Table 4. Activities

Activity name	Description
Ascend /descend ladder	Ascending or descending ladders to reach the workface at different levels from the ground.
Lift /lower materials	Lifting or lowering materials or equipment from/to ground level.
Nail/screw/drill	Nailing, screwing or drilling formwork components using hammer, nail gun or similar.
Hammer materials	Hammer or drive large objects with tools such as a sledgehammer.
Crane materials and motorized transport	Materials or formwork components are transported by cranes or by vehicles such as trucks, skid steers or scissor lifts. Including loading operations.
Cut materials	Formwork operations where plywood or aluminium is cut on-site.
Inspect/plan	Workers, supervisors and managers of construction planning and inspecting the works.
Manual transport	Transporting equipment and materials.
Static lift	Supporting a portion of formwork while other workers connect components or materials.
Plumb/level forms	Levelling and plumbing forms to shift and adjust a form.
Excavation	Dig or move soil to prepare the ground.
Lubrication/preparation	Formwork lubrication and preparation involving spraying form with oil and/or curing compound and setting and wetting curing blankets and expansion materials.

390

391

392

393

394 Table 5. Frequency Scale.

Worker hours per incident	Frequency score
>100 million	1
10-100 million	2
1-10 million	3
100,000-1 million	4
10,000-100,000	5
1000-10,000	6
100-1000	7
10-100	8
1-10	9
0.1-1	10

395

396

397 Table 6. Severity Scale

Subjective severity level	Severity score
Negligible	1
Temporary discomfort	2
Persistent discomfort	4
Temporary pain	8
Persistent pain	16
Minor first aid	32
Major first aid	64
Medical case	128
Lost work time	256
Permanent disablement	1,024
Fatality	26,214

398

399

400 Table 7. Consensus of experts

Absolute deviation from the median	
Frequency ratings	Severity ratings
0.89	0.91

401

402

403 Table 8. Risk Scores

	Exposure to harmful substances	Fall to lower level	Fall on same level	Cutting	Overexertion	Struck against object in motion	Struck against objects	Caught-in	Repetitive motion	Others
Ascend /descend ladder	$2.73 \cdot 10^{-8}$	$1.86 \cdot 10^{-2}$	$1.45 \cdot 10^{-7}$	$2.91 \cdot 10^{-6}$	$2.91 \cdot 10^{-5}$	$2.91 \cdot 10^{-7}$	$2.91 \cdot 10^{-5}$	$5.82 \cdot 10^{-7}$	$2.91 \cdot 10^{-5}$	$1.00 \cdot 10^{-8}$
Lift /lower materials	$1.50 \cdot 10^{-8}$	$1.86 \cdot 10^{-4}$	$2.91 \cdot 10^{-6}$	$1.45 \cdot 10^{-5}$	$2.91 \cdot 10^{-5}$	$7.27 \cdot 10^{-8}$	$1.45 \cdot 10^{-5}$	1.16E-03	$7.27 \cdot 10^{-6}$	$1.00 \cdot 10^{-8}$
Nail/screw/drill	$2.00 \cdot 10^{-8}$	$4.65 \cdot 10^{-3}$	$1.45 \cdot 10^{-6}$	$5.82 \cdot 10^{-4}$	$2.91 \cdot 10^{-3}$	$3.20 \cdot 10^{-7}$	$1.45 \cdot 10^{-5}$	$5.82 \cdot 10^{-6}$	$1.45 \cdot 10^{-3}$	$1.00 \cdot 10^{-8}$
Hammer materials	$1.50 \cdot 10^{-8}$	$4.65 \cdot 10^{-4}$	$2.91 \cdot 10^{-6}$	$2.91 \cdot 10^{-4}$	$2.91 \cdot 10^{-4}$	$3.20 \cdot 10^{-7}$	$1.45 \cdot 10^{-4}$	$5.82 \cdot 10^{-6}$	$1.45 \cdot 10^{-3}$	$1.00 \cdot 10^{-8}$
Crane materials and motorized transport	$1.50 \cdot 10^{-8}$	$1.86 \cdot 10^{-2}$	$2.91 \cdot 10^{-5}$	$2.91 \cdot 10^{-5}$	$7.27 \cdot 10^{-8}$	$5.82 \cdot 10^{-4}$	$7.27 \cdot 10^{-8}$	$1.16 \cdot 10^{-4}$	$7.27 \cdot 10^{-7}$	$1.00 \cdot 10^{-8}$
Cut materials	$1.00 \cdot 10^{-8}$	$1.16 \cdot 10^{-5}$	$2.91 \cdot 10^{-6}$	$5.82 \cdot 10^{-2}$	$2.91 \cdot 10^{-4}$	$3.20 \cdot 10^{-7}$	$1.45 \cdot 10^{-6}$	$2.91 \cdot 10^{-7}$	$7.27 \cdot 10^{-7}$	$1.00 \cdot 10^{-8}$
Inspect/plan	$1.00 \cdot 10^{-8}$	$1.86 \cdot 10^{-4}$	$1.45 \cdot 10^{-6}$	$2.00 \cdot 10^{-8}$	$3.64 \cdot 10^{-8}$	$2.91 \cdot 10^{-7}$	$7.27 \cdot 10^{-7}$	$4.00 \cdot 10^{-8}$	$7.27 \cdot 10^{-8}$	$1.00 \cdot 10^{-8}$
Manual transport	$1.00 \cdot 10^{-8}$	$4.65 \cdot 10^{-4}$	$7.27 \cdot 10^{-8}$	$2.91 \cdot 10^{-7}$	$2.91 \cdot 10^{-3}$	$5.82 \cdot 10^{-7}$	$2.91 \cdot 10^{-5}$	$2.91 \cdot 10^{-7}$	$2.91 \cdot 10^{-4}$	$1.00 \cdot 10^{-8}$
Static lift	$1.00 \cdot 10^{-8}$	$1.86 \cdot 10^{-5}$	$7.27 \cdot 10^{-8}$	$2.91 \cdot 10^{-5}$	$2.91 \cdot 10^{-4}$	$1.45 \cdot 10^{-7}$	$1.45 \cdot 10^{-5}$	$2.91 \cdot 10^{-7}$	$2.91 \cdot 10^{-4}$	$1.00 \cdot 10^{-8}$
Plumb/level forms	$1.82 \cdot 10^{-8}$	$4.77 \cdot 10^{-1}$	$2.91 \cdot 10^{-7}$	$2.91 \cdot 10^{-6}$	$5.82 \cdot 10^{-4}$	$5.82 \cdot 10^{-6}$	$1.45 \cdot 10^{-5}$	$5.82 \cdot 10^{-7}$	$2.91 \cdot 10^{-6}$	$1.00 \cdot 10^{-8}$
Excavation	$1.00 \cdot 10^{-8}$	$4.65 \cdot 10^{-3}$	$5.82 \cdot 10^{-6}$	$1.45 \cdot 10^{-7}$	$2.91 \cdot 10^{-6}$	$2.91 \cdot 10^{-6}$	$1.45 \cdot 10^{-6}$	$2.33 \cdot 10^{-5}$	$7.27 \cdot 10^{-7}$	$1.00 \cdot 10^{-8}$
Lubrication/preparement	$3.64 \cdot 10^{-8}$	$1.86 \cdot 10^{-4}$	$2.91 \cdot 10^{-6}$	$2.91 \cdot 10^{-6}$	$5.82 \cdot 10^{-4}$	$5.82 \cdot 10^{-6}$	$1.45 \cdot 10^{-5}$	$1.16 \cdot 10^{-6}$	$2.91 \cdot 10^{-5}$	$1.00 \cdot 10^{-8}$

404

405

406

407

408

409 Table 9. Comparison of activity risk values

Vertical Formwork civil construction activities	Risk score [S/w-h]
Plumb/level forms	0.4772
Cut material	0.0585
Crane-lift material	0.0194
Ascend/descend ladder	0.0187
Nail/screw/drill	0.0096
Excavation	0.0047
Lift/lowe rmaterials	0.0037
Hammer materials	0.0027
Staticlift	0.0014
Lubrication/preparation	0.0008
Manual transport	0.0006
Inspect/plan	0.0002
TOTAL	0.5976

410

411

412

413

414

415

416

417

418

419 Table 10.Comparison of safety risk values.

Safety risk	Risk Score [S/w-h]
Fall to lower level	0.5247
Cutting	0.0591
Overexertion	0.0079
Repetitivemotion	0.0036
Caught-in	0.0013
Struck against object in motion	0.0006
Struckagainstobjects	0.0003
Fall on the same level	0.0001
Exposure to harmful substances	0.0000
Others	0.0000
TOTAL	0.5976

420

421

422

423

424

425

426

427

428

429 Table 11. Activities description by images.

Activity name	Image
Ascend /descend ladder
Lift /lower materials
Nail/screw/drill
Hammer materials

Crane materials and motorized transport	<p>A 3D diagram showing a crane lifting a platform. The platform is a rectangular structure with a green base and a brown top. It is suspended by four red cables that converge at a single point above it. A worker in a blue uniform and orange helmet is standing on the ground, holding a purple rope that is attached to the platform. The background is white.</p>
Cut materials	<p>A photograph of a construction site. In the foreground, there is a large, circular concrete structure with a grid of rebar (reinforcing bars) embedded in it. Two workers in yellow safety vests and hard hats are standing near the structure. The background shows a dirt area and some construction equipment.</p>
Inspect/plan	<p>A photograph of a tall, red, spiral staircase structure. The structure is made of metal and has a complex, multi-level design. It is situated on a concrete base. Several workers in yellow safety vests and hard hats are visible on different levels of the structure, appearing to be inspecting or planning the construction. The background is a clear blue sky.</p>
Manual transport	<p>A 3D diagram showing two workers in blue uniforms and orange helmets moving a long, green, rectangular beam. The beam is supported by two green sawhorses. The workers are positioned on either side of the beam, and one is lifting it. The background is white.</p>

Static lift
Plumb/level forms
Excavation
Lubrication/preparation

430

431

432