NOTE TO USERS

This reproduction is the best copy available.

UMI[®]

HYDROLOGIC MODELLING OF CONSTRUCTION SITE SEDIMENT
CONTROL POND USING SWMM

by

Renata Krasnova
Hydrogeologist and Geological Engineer
Odessa Mechnikov State University
Odessa, Ukraine
June 1991

A thesis
presented to Ryerson University
in partial fulfillment of the
requirements for the degree of
Master of Applied Science
in the Program of
Environmental Applied Science and Management

Toronto, Ontario, Canada, 2004

© Renata Krasnova 2004

RECEIVED
Ryerson University
2004-12-17

UMI Number: EC52959

INFORMATION TO USERS

The quality of this reproduction is dependent upon the quality of the copy submitted. Broken or indistinct print, colored or poor quality illustrations and photographs, print bleed-through, substandard margins, and improper alignment can adversely affect reproduction.

In the unlikely event that the author did not send a complete manuscript and there are missing pages, these will be noted. Also, if unauthorized copyright material had to be removed, a note will indicate the deletion.

UMI[®]

UMI Microform EC52959

Copyright 2008 by ProQuest LLC.

All rights reserved. This microform edition is protected against unauthorized copying under Title 17, United States Code.

ProQuest LLC
789 E. Eisenhower Parkway
PO Box 1346
Ann Arbor, MI 48106-1346

Ryerson University requires the signatures of all persons using or photocopying this thesis. Please sign below, and give address and date.

ABSTRACT

Hydrologic Modelling of Construction Site Sediment Control Pond Using SWMM
Renata Krasnova, MASc,
Environmental Applied Science and Management,
Ryerson University, Toronto, 2004

Construction activities have been identified as one of the major sources of pollution to receiving waters. Although Erosion and Sediment Control (ESC) measures reduce the amount of sediment exported from construction sites, there are still significant concerns regarding the sufficiency of current control measures to protect receiving waters. This study documents the work completed to monitor and model the performance of a typical stormwater management facility used for erosion and sediment control in suburban construction site. The main objective of this study is to provide background information regarding the performance of storm water management facilities for treating urban construction runoff prior to discharging to receiving water bodies. The RUNOFF and STORAGE/TREATMENT blocks of EPA's stormwater management model (PCSWMM4.4) were used to simulate the quantity and quality of stormwater runoff from the area under construction and assess the performance of stormwater treatment facility (Ballymore Pond) located in Richmond Hill, Ontario. The performance of the construction site sediment control pond was found to be unsatisfactory due to the high outflow concentration of suspended solids. Some specific recommendations to improve its effectiveness have been made.

ACKNOWLEDGEMENTS

My special thanks to people who participated in the planning and implementation of this thesis. These include my thesis supervisor Dr. James Li and my research advisor Dr. Pradeep Behera. I would like to thank Derek Smith and Lindsay Pyatt who shared with me their field work experience and Joanna Domarad for her dedication in assisting in the field work. I also would like to thank Rob James for his assistance with the SWMM.

This research study would not have been undertaken without the generous support of the following organizations:

- The Toronto and Region Conservation Authority,
- The Department of Fisheries and Oceans, Canada,
- The Government of Canada's Great Lake Sustainability Fund,
- Environmental Canada,
- The Ontario Ministry of Environment,
- The City of Toronto,
- The Town of Richmond Hill,
- The National Science and Engineering Research Council,
- The National Water Research Institute, and
- Clarifica Inc., Toronto.

DEDICATION

To Lloyd and Margarita for their love, support and understanding.

TABLE OF CONTENTS

Author's Declaration	iii
Borrower's page	v
Abstract	vii
Acknowledgements	ix
Dedication	xi
Table of Contents	xiii
List of Tables	xvii
List of Figures	xxi

Chapter 1 - Introduction

1.1	Background	1
1.2	Study Objectives	4

Chapter 2 - Literature Review

2.1	Description of Urban Runoff Pollution	7
2.1.1	General	7
2.1.2	Construction Site as a Major Stormwater Polluter	14
2.1.3	The Effect of Construction on Receiving Waters	16
2.2	Management of Runoff from Construction Sites	18
2.2.1	Management of Runoff Pollution using BMP's	18
2.2.2	Sedimentation basins as an Effective BMP's	23
2.2.3	Managing Fine Sediments	29
2.3	Hydrologic Modelling of Urban Runoff	30
2.3.1	Modelling Concepts	30
2.3.2	SWMM Description	34
2.3.3	Modelling Studies	37

Chapter 3 - Study Site

3.1	Study Site and Stormwater Catchment Area Description	39
3.1.1	Soils and Drainage	43
3.2	Pond Design Features	43

Chapter 4 - Methodology

4.1	Monitoring	49
4.1.1	Rainfall and Runoff	50
4.1.2	Water Quality	52
4.1.3	Monitoring of Construction Activities	54

4.1.4	Bottom Sediments Accumulation vs. Construction Activities	57
4.2	Analysis of Monitored Data	58
4.2.1	Water Quantity Data Analysis	58
4.2.2	Water Quality Data Analysis	60
4.2.2.1	Discrete Data Analysis	63
4.2.2.2	Composite Data Analysis	64
4.3	Application of SWMM	65
4.3.1	RUNOFF and STORAGE/TREATMENT Blocks	65
4.3.2	Sensitivity Analysis and Model Calibration	67
4.3.3	Continuous Simulation	70
4.4	Assessment of Pond's Performance	70

Chapter 5 - Water Quantity Analysis

5.1	Rainfall-Runoff	71
5.2	Runoff Coefficient	72
5.3	Peak Flow Attenuation	75
5.4	Hydraulic Detention Times and Drawdown Times	79

Chapter 6 - Water Quality Analysis

6.1	Discrete analysis	83
6.1.1	Suspended Solids	83
6.2	Composite Analysis	92
6.2.1	General Water Chemistry	95
6.2.1.1	Suspended Solids	97
6.2.1.2	pH and Alkalinity	98
6.2.1.3	Turbidity	98
6.2.2	Nutrients	100
6.2.3	Metals	101
6.3	Particle Size Distribution	103

Chapter 7- SWMM Application

7.1	Modelling Objectives and Methodology	111
7.2	Data Input	112
7.3	SWMM Water Quantity	115
7.3.1	RUNOFF Block Parameter Development and Calibration	115
7.3.2	STORAGE/TREATMENT Block Parameter Development and Calibration	122
7.4	SWMM Water Quality	123
7.4.1	RUNOFF Block Parameter Development and Calibration	123
7.4.2	STORAGE/TREATMENT Block Parameter Development and Calibration	130

Chapter 8 - Modelling Results

8.1	Water Quantity Results	133
8.2	Water Quality Results	147

Chapter 9 - Continuous Simulation and Bottom Sediment Accumulation		
9.1	Bottom Sediment Accumulation	165
9.2	Continuous Simulation	166
9.2.1	Assessment of Sediment Load, Concentration and Removal Efficiency	166
9.2.2	Long-Term Pond's Performance	169
Chapter 10 - Receiving Water Analysis		173
Chapter 11 - Discussion		177
Chapter 12 - Summary of Results. Conclusions and Recommendations		
12.1	Summary of Results	187
12.1.1	Water Quantity	187
12.1.2	Water Quality	188
12.1.3	Continuous Simulation and Receiving Water Analysis	189
12.2	Conclusions and Recommendations	190
References		195
Appendices		203

LIST OF TABLES

Table 1.1: Multi-phase approach of TRCA towards improving erosion and control practices	2
Table 1.2: ESC pond storage volume requirements	3
Table 2.1: Sources of non-point urban runoff pollutants	10
Table 2.2: Typical pollutants concentrations found in urban stormwater	13
Table 2.3: The Performance of sediment basins and traps. A summary of field, laboratory and modeling results	26
Table 2.4: Characteristics and capabilities of selected NPS models	34
Table 3.1: Comparison pond design features	45
Table 4.1: Installation location and description of measuring devices	51
Table 4.2: Water Quality Analysis	62
Table 5.1: Rainfall event characteristics	72
Table 5.2: Rainfall-runoff coefficient	73
Table 5.3: Peak attenuation and flow mass balance summary	76
Table 5.4: Hydraulic detention and drawdown times	81
Table 6.1: Concentrations from inlets and outlet of Ballymore Pond	84
Table 6.2: Observed SS loads from inlets and outlet and removal efficiency	91
Table 6.3: Total performance of the Ballymore Pond throughout the study period	93
Table 6.4: Average Event Mean Concentrations (AEMC's) and Provincial Water Quality Objectives (PWQO's) for general chemistry	96
Table 6.5: Average Event Mean Concentrations (AEMC's) and Provincial Water Quality Objectives (PWQO's) for nutrients during the study period	100
Table 6.6: Average Event Mean Concentrations (AEMC's) and Provincial Water Quality Objectives (PWQO's) for metals	102

Table 6.7: D ₁₀ and D ₅₀ particle size	105
Table 6.8: Particle size class and distribution	108
Table 6.9: Average particle size, mass proportion and performance	109
Table 7.1: PCSWMM RUNOFF block control input parameters	114
Table 7.2: Storage/Treatment block control input parameters	115
Table 7.3: RUNOFF block quantity calibration parameters summary	120
Table 7.4: Common RUNOFF block water-quantity input parameters	122
Table 7.5: S/T block line H3 input parameters	123
Table 7.6: Input values for ERODAR SWMM parameter	127
Table 7.7: Water quality calibration on event basis	128
Table 7.8: Common RUNOFF block water-quality input parameters	130
Table 7.9: Calibrated water-quality parameters for S/T block	131
Table 8.1: Comparison of observed and simulated water quantity results for the construction catchment	134
Table 8.2: Comparison of observed and simulated water quantity results for the combined catchment	139
Table 8.3: Comparison of observed and simulated outlet runoff volume and peak flow for the outlet	142
Table 8.4: Comparison of observed and simulated mass loads for the construction catchment	148
Table 8.5: Comparison of observed and simulated SS concentrations for the construction catchment	150
Table 8.6: Simulated EMC and mass load and EMC for the combined catchment	156
Table 8.7: Comparison of observed and simulated SS loads for the outlet	158
Table 8.8: Comparison of observed and simulated SS concentrations for the outlet	160
Table 8.9: Load-based removal efficiency	164

Table 8.10: Concentration-based removal efficiency	164
Table 9.1: Sediment Accumulation during Fall 2002-Fall 2003	166
Table 9.2: Summary of long-term simulated, event-based simulated, and observed instantaneous removal efficiencies	169
Table 9.3: Long-term simulation of water quantity	170
Table 9.4: Long-term simulation water quality	170
Table 10.1: Receiving water impacts due to increases in TSS concentration	174
Table 11.1: Rainfall characteristics vs. median concentration	183
Table 11.2: Relation between detention/drawdown times and removal efficiency	184

LIST OF FIGURES

Fig. 2.1: Pre- and postdevelopment hydraulics	9
Fig. 2.2: Administrator's Performance Ratings-Percent Indicating Satisfactory Performance	24
Fig. 2.3: Urban watershed modelling process	33
Fig. 3.1: Ballymore Study Area	40
Fig. 3.2: Key Plan	41
Fig.3.3: Ballymore Pond bank erosion, September 2002	42
Fig.3.4: Ballymore Pond banks vegetation, September 2003	42
Fig. 3.5: Ballymore Construction Sediment Control Pond	45
Fig.3.6: Ballymore Pond's cross-section	47
Figure 4.1: Water quality samples of each monitoring station	55
Figure 4.2: Road Conditions in Catchment-1070 during construction 2002	56
Figure 4.3: Road Conditions in Catchment-1070 during construction 2003	56
Fig. 4.4: Schematic of hyetograph and hydrograph	59
Fig. 4.5: A flow chart depicting the calibration process of each model data	68
Fig. 5.1: Rainfall-runoff relationship	74
Fig. 5.2 (a-d): Samples observed hydrographs at the inlets and the outlet	78
Fig. 5.3: Drawdown time estimation for May 5 th 2003 event	82
Fig. 6.1 (a-c): Suspended solids concentrations	88
Fig. 6.2: Observed average EMC of SS	89
Fig. 6.3: Total load –based removal efficiencies for the Fall 2002 period	94
Fig. 6.4: Total load –based removal efficiencies for the May-July 2003 period	94

Fig. 6.5: Total load –based removal efficiencies for the August-November 2003 period	95
Fig. 6.6: Outflow turbidity vs. EMC	99
Fig. 6.7: Average cumulative particle size distribution for Fall 2002	106
Fig. 6.8: Average cumulative particle size distribution for May-July 2003	107
Fig 6.9: Average cumulative particle size distribution for August-November 2003	108
Fig. 8.1: Relation between observed and simulated runoff volume for the construction catchment	135
Fig. 8.2: Relation between observed and simulated peak flows for the construction catchment	136
Fig. 8.3: Comparison of observed and simulated hydrographs for the construction catchment	138
Fig. 8.4: Relation between observed and simulated runoff volume for the combined catchment	140
Fig. 8.5: Relation between observed and simulated peak flows for the combined catchment	141
Fig. 8.6: Relation between observed and simulated runoff volume for the outlet	143
Fig. 8.7: Relation between observed and simulated peak flows for the outlet	144
Fig. 8.8: Comparison of observed and simulated hydrographs for the combined inlet and the outlet	146
Fig. 8.9: Relation between observed and simulated mass load for the construction catchment	149
Fig. 8.10: Relation between observed and simulated SS concentrations for the construction catchment	151
Fig. 8.11: Comparison of observed and simulated SS pollutographs for 4 events	154
Fig 8.12: Evolution of EMC for the construction catchment	155
Fig 8.13: Evolution of EMC for combined catchment	157
Fig. 8.14: Relation between observed and simulated mass load for the outlet	159

Fig.8.15: Relation between observed and simulated SS concentrations for the outlet	160
Fig. 8.16: Evolution of EMC for the outlet	161
Fig. 8.17: Comparison of observed and simulated SS pollutographs for 3 events for the outlet	163
Fig. 9.1: Long-term continuous simulation for the period of September 2002-November 2003	168
Fig. 9.2: Sample long-term continuous simulation results for May 2003	171
Fig. 9.3: Comparison of observed and simulated flow for May 2003	172
Fig. 10.1: Receiving water impacts assessment approach	173
Fig. 10.2: Preliminary evaluation of severity of impacts by suspended sediments	175
Fig.11.1: Hydrograph and pollutograph for September 14, 2002 event	178
Fig.11.2: Hydrograph and pollutograph for May 2, 2003 event	179
Fig. 11.3: Hydrographs and rainfall for May 11-12, 2003 event	180
Fig. 11.4: Relationship between rainfall intensity and SS concentration	182
Fig. 11.5: Relation between detention time and RE based on simulation data	184
Fig. 11.6: Relation between drawdown time and RE based on simulated data	185
Fig. 11.7: Relation between detention time and instantaneous RE	185
Fig. 11.8: Relation between drawdown time and instantaneous RE	186

CHAPTER 1

INTRODUCTION

1.1 Background

Urban development is on the rise in and around most Canadian cities. As this rapid expansion takes place, it affects a significant portion of watersheds that are subjected to runoff discharges from construction sites. In many cases, limited water quality controls, particularly during large events, have lead to widespread water quality concerns resulting from sediment loading associated with construction activities. For instance, the Ministry of Natural Resources in Ontario has determined that during construction, when soil is disturbed and often left partially exposed or unprotected, the erosion process can increase at a rate up to 40,000 times that of undeveloped lands or forests (Li, 1998).

In urban stormwater runoff, suspended solids are considered the dominant pollutant. Evidently, suspended solids have continuously been found to have the greatest concentration in stormwater runoff (Randall et al., 1982). In addition, suspended solids are associated with many pollutants such as nutrients, heavy metals and petroleum-based organics that sorb to their surfaces.

The Ministry of the Environment (MOE, 1993) has stated that soil erosion at construction sites is a major cause of the degradation of rivers and streams in urban areas. According to these government agencies, tons of sediments from construction activities are entering Ontario watercourses each year. This in combination with ineffective erosion control measures is responsible for the degradation of water quality and fish habitats, reduction in navigation in waterways, and increases in flooding (MOE & MTRCA, 1992). According to Great Lakes Science Advisory Board Workshop (2000), construction sites are significant sources of sediments to urban streams. Although sediment control measures have been a requirement at construction sites for almost two decades, these have not proven to be adequate to protect receiving waters and meet the desired water quality and stream habitat targets.

Over the years, several studies have been conducted that aimed to improve existing erosion and sediment control practices (ESC). The TRCA has led several of these studies

due to the development activities that occur within its jurisdiction, and the concern associated with projected future developments. Table 1.1 outlines the TRCA's multi-phase approach of past studies, current projects in the process of completion, and future studies aimed at improving erosion and sediment control practices.

Table 1.1: Multi-phase approach of TRCA towards improving erosion and control practices (Clarifica, 2003).

Phase I	Urban Construction Sediment Control Study	1999
Phase II	Investigation to Develop an Improved Sizing Approach for Construction Sediment Control Facilities	April 2001 – March 2002
Phase III	Development and implementation of ESC Model by-law	August 2001-April 2002
Phase IV	Monitoring of Construction Sediment Pond	March 2002 – November 2003
Phases V – VI	Setting up model for runoff and erosion generation. Calibration of hydrologic and water quality models using field monitored data	AUG 2002 – MARCH 2004
Phase VII	Preliminary receiving water impact analysis	April 2004-March 2005

The intention of this thesis is to evaluate the performance of a construction sediment pond using a hydrologic modeling approach. Thus, it contributes to the outlined research in phases V-VI.

Previous studies have indicated the need to implement ESC storage ponds at the on-set of urban development. The current design criteria for ESC ponds being considered is as follows:

- Case 1: Use a temporary ESC pond for the period of construction only.
- Case 2: Use the ultimate SWM pond for ESC during construction.

In case 1, the sizing criteria would be as follows: (i) the permanent pool volume must be sized for a minimum of 125 m³/ha or the volume required under the latest MOE Stormwater Management Planning and Design (SMPD) manual, whichever is greater; (ii) the active storage must be sized for a minimum of 125 m³/ha, released over a minimum of 24 hours.

In case 2, when the ultimate facility is used for ESC, the sizing must meet the criteria specified in the MOE SMPD Manual (2003). As per TRCA requirements, an 'Enhanced Protection Level' will be required for sizing the permanent pool volume. In addition, the TRCA requires extended detention storage for the runoff from a 25 mm storm released over minimum 24 hours. The applicable design criteria for wet ponds is summarized in Table 1.2.

Table 1.2: ESC pond storage volume requirements (m³/ha)

Protection Level	Catchment Imperviousness			
	35%	55%	70%	85%
Permanent Pool Volume ¹	100	150	185	210
Extended Detention Volume ²	25 mm	25 mm	25 mm	25 mm

Note:

(1) MOE Enhanced Level of Protection sizing criteria – permanent pool only.

(2) Extended Detention Volume is the runoff from a 25 mm storm released over a minimum of 24 hours.

The implementation of either the ultimate pond or an interim pond designed according to the Enhanced Protection Level will provide better runoff treatment than the previous design criteria of 125 m³/ha for active storage only. However, the question still remains as to whether the Enhanced Protection Level is sufficient to control the runoff from construction sites given the significantly different sediment characteristics and extreme suspended sediment concentrations and loads as compared to stable urban areas. Furthermore, although new ponds may provide better treatment, there is still no data to indicate the effectiveness for meeting the specific environmental quality objectives (e.g., targets for fish habitats). For example, the sizing does not relate the aquatic system sensitivity to suspended solids concentration and duration of exposures so as to limit the effects.

Therefore the TRCA recognized the need to evaluate the adequacy of SWM ponds designed according to the MOE SMPD manual for construction sites and the performance of the ponds in meeting receiving water targets. This evaluation has been divided into two phases:

- Phase I: Monitor a typical construction site and corresponding sediment control pond designed as per MOE SMPD manual and evaluate the pond performance; and
- Phase II: Monitor a typical construction site, sediment control pond and receiving water to evaluate the integrated performance.

The present study documents the findings of the recently completed first phase. This phase included a field monitoring and modelling program conducted from 2002 to 2003 at Ballymore Pond in Richmond Hill, Ontario. The study characterizes the hydrologic conditions within typical construction sites and sediment control ponds designed according to the MOE manual. In addition, the study documents construction sediment characteristics, and the evaluation of pond performance and theoretical receiving water impact assessment.

1.2 Study Objectives

The main objective of this study is to evaluate the performance of storm water management facilities designed according to the MOE SWMP manual for treating urban construction runoff prior to discharging to receiving water bodies. The study provides input for further improvement of construction stormwater treatment and will lead to future revisions of TRCA's ESC guidelines.

Specific objectives include:

- Monitor runoff from a typical construction site and construction sediment control pond to obtain runoff quantity and quality data, sediment characteristics and sediment removal efficiency;
- Develop calibrated hydrologic and water quality model using monitored data to supplement measured data and assess sediment removal performance during monitoring period and long-term simulation;

- Preliminary evaluation of receiving water quality impacts from pond outlet effluents by comparing sediment concentrations and durations with receiving water habitat targets.

This thesis is the next step towards linking stormwater runoff quality control best management practices and receiving water protection goals.

CHAPTER 2

LITERATURE REVIEW

This chapter provides an overview of urban runoff pollution issues including types of pollutants, their origins and modes of transport, and their effects on receiving waters. Special emphasis is placed on stormwater runoff pollution coming from construction sites and management of construction sites runoff using best management practices (BMP's). This chapter also reviews current water quality models, particularly SWMM model, and modelling studies related to SWMM.

2.1 Description of Urban Runoff Pollution

2.1.1 General

It is estimated that in the year 2000, half of the world's population will be living in urban areas (Zoppou, 2001). In many countries the land occupied by the urban population is often less than 5% of the total area. This concentration of human activities intensifies local competition for all types of resources, with water amongst the most vital. Water is essential for human existence and human settlement and it is employed extensively in urban areas for the disposal of wastes. Water can also have a negative impact on human activity. This includes flooding, drainage, erosion and sedimentation. These problems are exacerbated in urban catchments by altering natural watercourses and increasing impervious areas. Urban runoff is typically highly polluted with pathogenic and organic substances that are a public health threat.

Urban runoff pollution results from numerous sources. The impact of rainfall dislodges particles on the surface of the ground. Many pollutants adhere to these particles and are conveyed along with soluble pollutants by the runoff. The momentum associated with the runoff dislodges other contaminant-laden particles. These are transported to a watercourse by the flowing water and progress through the urban watershed. Depending on the type of activity on the land, the volume of runoff and the amount and types of pollutants carried with it will vary. The intensity and duration of precipitation and the time

since the last precipitation event also affects the quantity and transport of pollutants generated (Viessman and Lewis, 2002).

Rain falling over a watershed will fall on either an impervious or a pervious area. On a pervious area, some rainfall may infiltrate the sub-surface and the remainder is surface runoff. Surface runoff and perhaps infiltration will eventually flow into a watercourse or a receiving water body. This is not the case for an impervious area, where nearly all the rainfall becomes runoff (Schueler, 2000). An urban area is by definition an area of concentrated human activity, which is characterized by extensive impervious areas and man-made watercourses (Zoppou, 2001). The result is an increase in runoff volume and flow that can result in flooding, watercourse and habitat destruction.

Urbanization replaces permeable surfaces with impervious surfaces (e.g., roof tops, roads, sidewalks, and parking lots), which typically are designed to remove rainfall as quickly as possible. Increasing the proportion of paved areas decreases the infiltration and evapotranspiration paths of precipitation, thus increasing the amount of precipitation leaving an area as runoff. In addition to magnifying the volume of runoff, urban development increases the peak runoff rate and decreases travel time of the runoff. When mechanisms that delay entry of runoff into receiving waters (i.e., vegetation) are replaced with systems designed to remove and convey storm water from the surface, the storm water's travel time to the receiving waters is greatly reduced, as is the time required to discharge the storm water generated by a storm. Figure 2.1 shows an urban area's typical predevelopment and postdevelopment discharge rates over time.

The U.S. EPA summarizes changes to hydrology that might be expected for a developing watershed: (i) increased peak discharges (by a factor of 2 to 5); (ii) increased volume of storm runoff; (iii) decreased time for runoff to reach stream; (iv) increased frequency and severity of flooding; (v) reduced streamflow during periods of prolonged dry weather (loss of base flow); (vi) greater runoff and stream velocity during storm events (EPA, 1993). Each of these hydrologic changes can lead to increased pollutant transport and loading to receiving waters.

Fig. 2.1: Pre- and postdevelopment hydraulics

(Source: EPA, Handbook, Urban Runoff Pollution Prevention and Control Planning, 1993).

When discharge of pollutants into receiving water bodies exceed the assimilation capacity of these bodies, problems can result. Types of biological effects that these water quality problems may cause include: infection of organisms by bacteria and viruses, death from chronic toxicity exposure and alteration to natural habitat cycles and breeding. Pollution and water quality degradation can also interfere with the range of legitimate human water uses.

The most common pollutants that can be expected from various non-point sources in an urban environment and their typical concentrations are presented in Tables 2.1 and 2.2.

Table 2.1: Sources of non-point urban runoff pollutants
(modified from Whipple et al., 1983).

Pollutant	Source					
	Soil Erosion	Vehicles	Industrial Wastes	Fossil Fuels	Lawn and Garden Chemicals	Animal Wastes
Suspended solids	M*	M		M		
Nutrients						
Nitrogen	m**	M			M	M
Phosphorus	M	m	m		M	M
Heavy metals						
Iron						
Manganese						
Zinc		M			M	
Lead		M	m			
Copper	M	M	M			
Chromium	M	M	M		M	
Nickel	m	M	M			
Mercury		M	M			
Cadmium		M	M			
Pesticides					M	

*M, major source; **m, minor source

Urban runoff quantity and quality depends on several factors that determine flow magnitude and time distribution, as well as pollutant concentrations. These include rainfall patterns, volume, intensity, and antecedent number of dry days; traffic volume; land use; geographic and geologic characteristics of the region; maintenance practices; and drainage system configuration.

Water quality parameters for stormwater comprise a long list and are classified in many ways. Wanielista and Yousef (1993) classified water quality parameters as follows: (1) sediment, nutrients, and metals; (2) oxygen-demanding and inert material; (3) particulate and dissolved; (4) chemical, biological, and physical; (5) toxic and nontoxic; (6) organic and inorganic; and (7) others.

Receiving waters can assimilate a limited quantity of each, but there are thresholds beyond which the measured amount becomes a pollutant and results in an undesirable impact. Brief explanation of some pollutants, their sources and impacts is as follows.

Sediments. These are made up of particulate matter that settles and fills in the bottoms of ditches, streams, lakes, rivers, and wetlands. Sources of sediment include washoff of particles that are deposited on impervious surfaces and erosion from streambanks and construction sites. Both suspended and deposited sediments can have adverse effects on environment. Sediments also transport other attached pollutants. Some sediment is tolerated in streams; however, too much sediment produces highly turbid waters and adverse consequences have been documented. These impacts will be described later in chapter.

Heavy metals. Motor vehicles are a major source of metal contribution to the environment. Concentration of heavy metals in stormwater runoff can be one to two orders of magnitude greater than that in sanitary sewage. For example, runoff to the Ohio River was found to contain lead, zinc, chromium, arsenic, cadmium, nickel, antimony and selenium (Norman, 1991). Certain heavy metals (e.g., copper, cadmium, lead and zinc) are more soluble in water than others, and may cause toxic effects at concentrations exceeding threshold values. The sources of some of the heavy metals include: lead deposits from the use of leaded fuel, lead oxide and zinc from tire wear, and copper, chromium, and nickel from wear of the plating, bearings, brake linings and other moving parts of a vehicle.

Nutrients are chemicals that stimulate the growth of algae and water plants. The basic macronutrients are carbon, nitrogen and phosphorus. The typical nutrient concentrations in runoff are usually more than sufficient to stimulate the growth of algal and plant species.

BOD5 is a good indicator of the amount of pollution being carried off by the runoff. The urban runoff pollution, if expressed by BOD5 on an annual total load basis, is approximately equivalent to that of a secondary wastewater treatment plant effluent. The common sources of BOD5 are usually vegetation, litter and garbage, and animal waste.

Other toxic chemicals. Priority pollutants are generally related to hazardous wastes or toxic chemicals and can sometimes be detected in stormwaters. A listing was developed and published, but others not on the priority pollutants list can be equally harmful, such as chloride (Wanielista, and Yousef, 1993).

Various chemicals have different types of impacts on the water quality. For example, lead bio-accumulates on the bottom. This may retard fish growth and reduce photosynthesis. At certain concentrations, zinc and copper are toxic to fish and aquatic micro-invertebrates. Cadmium and chromium could be mutagenic and carcinogenic. Biochemical oxygen demanding material can deplete the oxygen level in the aquatic ecosystem resulting in decrease in the fish population. Excess nutrients, such as nitrogen and phosphorus, cause algal blooms which block sunlight and consume oxygen as they decompose. Oil and grease from automobile usage, as well as improper disposal, is toxic to aquatic organisms and affects fish reproduction. Total suspended solids in water increase turbidity level, affecting fish survival (Schueler and Holland, 2000). Some common pollutants found in urban stormwater runoff are profiled in Table 2.2.

Table 2.2: Typical pollutants concentrations found in urban stormwater (Source: Maryland Stormwater Manual, Vol. 1).

Typical Pollutants Found in Stormwater Runoff	Units	Average Concentration *
Total Suspended Solids	mg/l	80
Total Phosphorus	mg/l	0.30
Total Nitrogen	mg/l	2.0
Total organic Carbon	mg/l	12.7
Fecal Coliform Bacteria	MPN/100 ml	3600
E. coli Bacteria	MPN/100 ml	1450
Petroleum Hydrocarbons	mg/l	3.5
Cadmium	µg/l	2
Copper	µg/l	10
Lead	µg/l	18
Zinc	µg/l	140
Chlorides (winter only)	mg/l	230
Insecticides	µg/l	0.1 to 2.0
Herbicides	µg/l	1 to 5.0

*these concentrations represent *mean or median* storm concentrations measured at typical sites and may be greater during individual storms. Also note that mean or median runoff concentrations from *stormwater hotspots* are 2 to 10 times higher than those shown here. Units = mg/l = milligrams/liter, µg/l = micrograms/liter, MPN = Most Probable Number.

During the monitoring of stormwater pollution study in Wisconsin conducted by Roger Bannerman and his colleagues (Bannerman et al., 1993) it was revealed that streets are the single most important source area for urban pollutants in residential, commercial and industrial areas. Not only did streets produce some of the highest concentrations of phosphorus, suspended solids, bacteria, and several metals, but they also generated a disproportionate amount of the total runoff volume from the watershed. Consequently, streets typically contributed four to eight times the pollutant load that would have been expected if all source areas contributed equally.

According to Bannerman et al. (1993), the importance of street runoff for urban pollutant loading is due to a number of factors. First, as streets are directly connected to the

drainage system, they possess a very high runoff coefficient. Second, the curb and gutter system along streets is very effective at trapping and retaining fine particles that blow into them. In addition, as most other sources areas are "upstream" from streets and their gutters, pollutants delivered from sidewalks, driveways, rooftops, and lawns ultimately pass through street gutters on their way to the storm drain.

Finally, streets are strongly influenced by local emissions and leaks from vehicular traffic. Metals that are strongly linked to cars, such as copper and cadmium, reached their highest levels on streets and parking lots. The same pollutants were rarely encountered in roof and lawn runoff.

2.1.2 Construction Site as a Major Stormwater Polluter

Land activities, such as construction, contribute a significant additional amount of pollution in stormwater runoff. There is little doubt that construction sites rank among the most significant sources of sediment today. Construction activity is an important contributor to non-point source pollution in urbanizing areas (Goldman et. al., 1986; Harbor, J., 1999; Novotny and Chesters, 1989; Schueler, 1990; U.S.EPA, 1993; Fifield, 2002; etc.).

When construction disturbs land, erosion occurs during rainfall or wind events. Once suspended in wind or water, soil particles may become a major water pollutant, as follows (Fifield, 2002):

- Sediment loading can be 10 to 20 times greater than soil particles lost from lands where plants grow.
- Sediment loading causes reservoirs and harbours to clog with silt and other sediments.
- Sediment loading causes loss of recreational areas and wildlife habitat.
- Sediment loading reduces the beneficial use of water for human and can harm plants, animals and fish that live in the water.

Sediment loading from construction may increase the amount of nutrients in water. Nutrients (especially phosphorus and nitrates) may come from fertilizers used at construction sites to aid in the establishment of plants. When runoff waters carry sediment downstream into waters, plants that live in the water will absorb the nutrients. The increase in these plants, or biomass, robs the water of oxygen, killing fish and other

organisms living in the water. Pesticides may also be present along with the nutrients found in some soils. These harmful chemicals move with the soil particles from construction projects. The three types of pesticides most commonly used at construction projects are: herbicides to kill plants, insecticides to kill insects, rodenticides to kill rodents, such as mice and rats. Improper application of pesticides could result in the direct contamination of water. Indirect pollution can also occur when the pesticides are suspended in the air and carried from the land surface to the water.

Over half of the trace metals carried in runoff waters are attached to sediment (Fifield, 2002). Sources of these metals found at construction sites include galvanized metal, paint, and preserved wood. Nearly all metals can be toxic to plants, animals, and fish that live in water. In addition, metals can accumulate in the tissues of plants, animals, and fish and have the potential to contaminate drinking water.

Other pollutants found in runoff from construction sites include hydrocarbon compounds. These compounds are the building block for many synthetic chemicals that are widely used on construction projects. Soil from the site can become contaminated as a result of leaks from heavy equipment, hydraulic line failures, spills during refilling, and inappropriate disposal of drained fluids. When runoff occurs, hydrocarbon can be washed into the water, harming plants and animal life. Therefore, it is important to store and use these chemicals properly. Other wastes from construction sites that can lead to unsightly and polluted water include: wash water from concrete mix, plants and planting equipment, waste from cleaning vehicles and equipment, waste from trees and shrubs removed during land clearing, wood, plastic and paper from packaging of building products, food containers, such as paper, aluminum, and metal cans, sanitary waste.

2.1.3 The Effect of Construction on Receiving Waters

Particles suspended in moving water will eventually find their way into downstream waters where they will be deposited. Large-size particles (e.g., sand) may cover fish spawning beds or smother immobile species, such as clams. Smaller-size particles (e.g., clays) can remain suspended for a very long time. When this occurs, less light is available for plants that live in the water. This fine-grain material can also accumulate on the gill surfaces of fish, resulting in fish kills from suffocation.

Pollutants attached to sediment also enter streams and lakes with runoff waters. In some cases, the increased amount of pollutants can make the environment poisonous. When such conditions occur, fish usually leave the contaminated areas for less polluted waters. Unfortunately, many species cannot escape the polluted area and are often doomed.

Eroded soil entering surface waters as suspended solids is a major water quality problem. In a 1977 survey, the rate of soil erosion in the USA was estimated at 7.1×10^9 Mg per year (Dodson, 2000). For a given land area, eroded soil from urban areas and construction sites can be 5 to 20 times greater than that from agricultural land (Dodson, 2000). Goldman computed that construction sites are responsible for an estimated export of 80 millions tons of sediment into receiving waters each year. On a unit area basis, construction sites export sediments at 20 to 20,000 times the rate of other land uses (Goldman. *et al.*, 1986). According to Fifield (2002), while the muddy waters that run off from construction sites are easy to observe, there is no full awareness of the downstream impacts eroded sediments have on both the environment and economy. Given the cost and effort needed for ESC control, it is important to remember why it matters.

The nature of the sediment impacts depend on whether sediments are suspended in the water column or are deposited on a stream channel or lake bottom.

Shueler and Holland (2000) summarized the impacts of suspended and deposited sediment.

Summary of the Impacts of Suspended Sediment on the Aquatic Environment:

- abrades and damages fish gills, increasing risk of infection and disease;
- scouring of periphyton from stream (plants attached to rocks);
- loss of sensitive or threatened fish species when turbidity exceeds 25 NTU;
- shifts in fish community toward more sediment tolerant species;
- decline in sunfish, bass, chub and catfish when monthly turbidity exceeds 100 NTU;
- reduces sight distance for trout, with reduction in feeding efficiency;
- reduces light penetration causing reduction in plankton and aquatic plant growth;
- reduces filtering efficiency of zooplankton in lakes and estuaries;
- adversely impacts aquatic insects which are the base of the food chain;
- slightly increases stream temperature in summer;

- suspended sediments are a major carrier of nutrients and metals;
- increased water treatment costs to meet drinking water standards;
- increased wear and tear of hydroelectric and water intake equipment;
- reduces anglers chances of catching fish;
- diminishes direct and indirect recreational experience of receiving waters.

Summary of the Impacts of Deposited Sediments on the Aquatic Environment:

- physical smothering of benthic aquatic insect community;
- reduced survival rates for fish eggs;
- destruction of fish spawning areas and eggs;
- "imbedding" of stream bottom reduces fish and macroinvertebrate habitat value;
- loss of trout habitat when fine sediments are deposited in spawning or riffle-runs;
- sensitive or threatened darters and dace may be eliminated from fish community;
- significant contributing factor in the alarming decline of freshwater mussels;
- reduced channel capacity, exacerbating downstream bank erosion and flooding;
- reduced flood transport capacity under bridges and through culverts;
- loss of storage and lower design life for reservoirs, impoundments and ponds;
- dredging costs to maintain navigable channels and reservoir capacity;
- spoiling of sand beaches;
- deposits diminish the scenic and recreational value of waterways.

Taken together, the 30 reported impacts confirm that eroded sediment is a major pollutant in waterways.

2.2 Management of Runoff from Construction Sites

2.2.1 Management of Runoff Pollution Using BMP's

Given the high level of concern about construction-site erosion, it is critical to ensure that effective, practical methods of erosion and sediment control are being implemented. Construction-site erosion is one of the easiest sources of non-point source (NPS) pollution to control because construction sites are well defined areas. The primary reason for erosion control failure, according to Harbor et al. (1995), is inadequate implementation of the most effective pollution prevention measures.

Stormwater pollution is controlled through Best Management Practices (BMPs). There are several definitions assigned to BMP's. Taken from James (1995): BMP are "structural devices that are temporarily store or treat urban stormwater runoff to reduce flooding, remove pollutants, and provide other amenities". Another definition belongs to D. Mandelker " (from Tsihrintzis and Hamid, 1997): BMPs are "control measures for slowing, retaining, and absorbing pollutants produced by surface runoff associated with non-point sources.

Tsihrintzis and Hamid (1997) named six basic components of an effective BMP system design: runoff attenuation, runoff conveyance, runoff pre-treatment, runoff treatment, system maintenance, and secondary impact mitigation. Brief description of BMP design is as follows.

Runoff attenuation focuses on reduction of pollutants by minimizing the volume of runoff. Runoff volume can be primarily contained by minimizing basin imperviousness, and delineating and protecting the environmental reserve areas. Runoff attenuation serves to enhance the performance of the remaining components of the BMP system.

Runoff conveyance provides safe transport of stormwater to the BMP with minimum disruption to the existing network. Swales, exfiltration drains, and parallel pipe systems are some of these methods.

Runoff pre-treatment: this captures or traps coarse sediments before they enter the BMP to preserve storage volume and/or prevent clogging within the BMP. Pre-treatment is located in an area where sediment can be easily removed without interfering with the general operation of the BMP. Examples of some pre-treatment methods include stilling basins, grass filter strips, and filter cloth barriers for infiltration systems. For industrial or transportation applications water quality inlets or settling basins should be used to remove oily wastes prior to entering into the BMP system.

Runoff treatment is the heart of the BMP system. In general, there are four basic treatment options available, which include filtration, detention, retention, and infiltration. An effective BMP system may use any or all of these options.

System maintenance: there is a need for a realistic plan to maintain the long-term performance of the first four components of the system. Since the system accumulates significant quantities of sediment and possibly toxic pollutants, the disposal or containment of these residuals should be carefully planned. The design of the BMP must include easy and permanent access, as well as environmentally and economically sound removal procedures.

Secondary impact mitigation: this determines whether the BMP system creates any secondary impacts to the downstream community. For example, secondary impacts from ponds include the discharge of hypoxic and/or thermally enriched water downstream, the removal of downstream riparian cover, and possibly filling or alteration of wetland areas adjacent to the pond. For infiltration systems, they include possible risk of groundwater contamination and system failure.

Strategic watershed planning for urban runoff quality control must also include consideration of the implementation and adoption of effective source controls for stormwater runoff together with the optimization of BMPs. According to Ellis (1989), it includes: optimization of street and road gully cleaning operations; implementation of car parking controls and street zoning restrictions; reduction in the number and frequency of road gullies, especially in residential developments; insertion of flow control devices such as orifice plates into road gullies to throttle high intensity storm events; provision of temporary storage of stormwater runoff on impermeable surfaces within suburban residential districts; reduction to absolute minimum of the amount of chlorides, bromide and grit used for winter deicing operations; provision of effective street and sewer sanitation maintenance in commercial and industrial districts; and control and maintenance of oil interceptors to prevent spillage and seepage to the stormwater sewer system.

BMPs can generally be categorized into structural and nonstructural controls. Structural BMPs consist of an actual structure that collects and treats runoff (U.S. EPA, 1993). Nonstructural BMPs include practices such as public education and awareness, street sweeping and cleaning, fertilizer application control on grass areas, and zoning restrictions to limit population densities. Stormwater management strategies for urbanizing areas involve balancing structural controls with nonstructural controls. Effectiveness of structural

BMP's will be discussed in a latter section. It should be noted that no single BMP type is ideally suited for every situation; various BMPs are used for controlling different pollution sources .

Li (1997) outlined seven potential erosion and sediment problem areas at construction sites where erosion and sediment are likely to occur: (i) steep slopes; (ii) close proximity to streams and waterways, (iii) poorly designed surface drainageways; (iv) inlet and outfall of enclosed drainage; (v) large, flat surface areas; (vi) borrow and stockpile areas; (vii) adjacent properties. According to Li (1997) and Harbor (1999), for an erosion and sediment control program to be effective, it is imperative that provisions for control measures be made in the planning stage. These planned measures, when conscientiously and expeditiously applied during construction, will result in orderly development without environmental degradation and with cost savings. The following principles should be used to the maximum extent possible.

Minimize the extent of the disturbed area and the duration of exposure and stabilize disturbed areas as soon as possible.

Erosion during construction can be reduced significantly by minimizing the time between removal of the pre-construction cover and establishment of the post-construction cover. For small sites this involves delaying clearing and grading operations until shortly before construction begins, and applying final or temporary cover immediately to portions of the site that have reached final grade. For larger sites, the same principles applies, but in addition the site can be divided into phases, so that only the next area to be built on is to be cleared and graded. In regions with distinct seasonal variations in climate, it is usually possible to identify certain portions of the year when erosion potential is relatively low

Use natural and artificial cover on disturbed areas.

Erosion from disturbed areas can be reduced significantly by prompt application of temporary surface cover. For small areas, this can include artificial materials such as erosion control blankets or plastic sheeting; and for large areas, this usually involves mulch and/or seeding to establish temporary cover. Mulch protects the soil from direct rain splash impact, and increases soil moisture retention. Seed and mulch combinations provide immediate protection by the mulch, and long-term protection when mulch decays. Temporary cover may need to be applied several times during the construction sequence,

to protect areas between construction phases. Hydroseeding applications of seed, mulch, water fertilizer and a tackifier are increasingly popular as they allow for treatment of steep slopes and other unstable or difficult areas, and can provide extensive cover very quickly. Detailed research by Harbor *et al.* (1995) was performed on Ohio construction sites. Using field sampling of runoff from treated and untreated sites as well as computer modeling based on site condition maps, it was found that rapid application of surface cover dramatically reduced both the amount of sediment generated by surface erosion and the concentration and total load of phosphorus in stormwater runoff. Rapid applications of surface cover reduced soil erosion by up to 86% and phosphorus loadings up to 80% compared to bare-soil conditions. In average, according to Harbor (1999), temporary cover reduces erosion by 50%.

Keep runoff velocity low.

Runoff velocity should be kept as low as possible. For drainage ways such as ditches, high velocity can be reduced by a series of rock check dams, which break the flow velocity. Minimizing slope length and steepness can reduce overland flow velocity.

Direct runoff away from problems areas.

Erosion on disturbed areas is compounded if runoff from undisturbed areas is directed across exposed areas, particularly on steep slopes. Based on the construction plan, it is possible to identify areas that will be exposed during each project phase, and to install small, temporary diversion *ditches, dikes* or *slope drains* to divert upslope runoff around disturbed areas. At a larger scale, off-site water can be diverted around the construction site to minimize the amount of water entering on-site conveyance and treatment structures. By eliminating off-site flow, discharge and erosion potential for channels on the site is reduced, and with lower total volumes of water, sediment trapping structures such as silt fences and sedimentation basins are much more effective.

Retain sediments within the site area.

To reduce the amount of eroded soil that leaves the site, a variety of sediment trapping measures can be used. One of the commonly used erosion and sediment control measure is the silt fence. The fence is a geotextile with fine sand-sized openings, attached to wooden stakes, which is designed to trap sediment in unconcentrated overland flow. The bottom 20 cm of the fence is buried in a trench, so that the fence forms an "leaky dam",

ponding runoff to allow time for sediment to settle before the water passes through the geotextile. Silt fences can perform very well if properly installed. Sometimes, instead of a silt fence, straw dikes are used. They operate under the same principle: if properly installed they temporarily dam overland flow, allowing time for sediment to settle out.

The other main class of sediment trapping structures are sediment traps, ponds and basins. Although varying in size and design details, all of them temporarily detain surface runoff, releasing it slowly, allowing time for sediment to settle out in the basin. A slow release rate is produced either by construction of a leaky dam or by use of a perforated outlet riser pipe surrounded by geotextile and a gravel cone to restrict the outlet flow rate. In some cases, permanent stormwater detention or retention ponds (required in many areas for flood control) can be modified to act as sediment traps during construction by adding the perforated riser outlet. Sediment basins are popular with developers because in practice they require less maintenance than other erosion and sediment control techniques, and often can be integrated with permanent stormwater management facilities. Oliver and Grigoropoulos (1981) concluded that source control of runoff by detention and natural treatment is an effective means of managing storm-generated pollution. Disadvantages include poor trapping efficiencies for fine sediments, basins that are often too small compared to the volume of flow, and the uses of basins as the only erosion and sediment control techniques on the site, rather than as a part of a comprehensive set of measures.

Implement a thorough maintenance and follow-up program.

This last principle is vital to the success of the six other principles. A site cannot be effectively controlled without thorough, periodic inspections of the erosion and sediment control practices. These practices must be maintained just as construction equipment must be maintained and materials checked and inventoried. An example of applying this principle would be to start a routine "end of day check" to make sure that all control practices are working properly.

Usually, these seven principles are integrated into a system of vegetative measures and structural measures along with management techniques to develop a plan to prevent erosion and control sediment. In most cases, a combination of limited grading, limited time of exposure and a judicious selection of erosion control practices and sediment trapping

facilities will prove to be the most practical method of controlling erosion and the associated production and transport of sediment.

2.2.2 Sedimentation Basins as an Effective BMP's

Over the last two decades, numerous field and laboratory studies have tested the best techniques for preventing erosion and trapping suspended sediment at construction sites. However, very few of the studies have assessed how well these techniques are actually implemented and perform at construction sites.

Typical comments of administrators from open response option on the survey on the performance of common used construction practices in North Carolina, USA, were summarized (Schueler and Holland, 2000). The results of the survey are presented in Figure 2.2.

Fig. 2.2: Administrator's Performance Ratings-Percent Indicating Satisfactory Performance (Source: Schueler and Holland, 2000)

As shown in the Figure, few North Carolina ESC administrators were satisfied with the typical field performance of most construction practices; only three out of 11 construction practices were considered to be good or excellent. Sediment basins, sediment traps, and riprap-stabilized channels received the highest percentage of favorable ratings.

Performance of sediment basins is rated as high as 94%.

Adding to the description of sediment basins given in the earlier section: retention and detention basins are open excavated or natural depressions on the ground surface of varying size and depth. Wet-detention/retention ponds maintain a permanent pool of water. Retention is relatively long-term storage that results in residence times that last weeks or months. Detention is a short-term storage with residence time of a few hours or days with discharge to adjacent surface waters (Wanielista and Yousef, 1993). It was reported that the overall removal efficiency of the retention basin for suspended solids ranges from 10–85% depending on detention time, basin design, outlet structure design and base-flow concentrations (Tsihrintzis and Hamid, 1997). Ferrara and Witkowski (1983) concluded that the effectiveness of a wet basin appears to be related to two factors, namely the processes of equalization and sedimentation. Most ponds approached 80% removal efficiency for suspended solids, approximately 55%- for nutrients, 70%-bacteria and 50-74%- for metals (Schueler and Holland, 2000)

Sediment basins and traps face an imposing performance challenge in removing sediment from construction site runoff: large suspended sediment concentrations. Shown in Table 2.3, field and modeling research indicates that an average total suspended solid (TSS) concentration from construction sites are about 4,500mg/l and could be as high as 17,500 mg/l in some storm events (Schueler and Holland, 2000).

If the containment system is capable of removing 90% of the sediment, it will still discharge sediment at concentration of 450 mg/L. Likewise, if the removal rate is increased to 95%, the discharged TSS concentration will be 225 mg/l, again a high turbid discharge by most standards. Given current practices, it is almost impossible to achieve 99% or more removal to produce a TSS level of 45 mg/l that in any way resembles a clear water discharge.

Table 2.3: The performance of sediment basins and traps. A summary of field, laboratory and modelling results (Source: Schueler and Holland, 2002).

Research Study or Site*	TSS (mg/L)		Mean % Reduction
	Mean Inflow	Mean Outflow	
SR-204	3,502	154	98.6 %
Seattle	17,500	626	86.7%
Mercer Island	1,087	63	75.1%
RT1	359	224	18.0%
RT2	4,623	127	99.8%
SB1	625	322	54.7%
SB2	415	91	80.3%
SB4	2,670	876	66.8%
Pennsylvania Test Basin	9,700	800	94.2%
Georgia Model	1,500-4,500	200-1,000	42-87%
Maryland Model	1,000-5,000	200-1,200	68-99.5%
Uncontrolled construction site runoff	4,200	-	-
Means	4,498	365	75%

* Sources: Horner et al., 1990; Schueler and Lugbill, 1990; Jarrett, 1996; Storm and Kirby, 1991; Barfield and Clar, 1985; York and Herb, 1978.

Surprisingly few sediment basins and traps have been tested in the field. Of the limited number of performance monitoring studies that have been conducted, three of the most informative are: Horner's (1990) studies of three highway sediment basins in Washington state, Jarrett's (1996) Pennsylvania test basin study, and Schueler and Lugbill's (1996) of five basins and traps in the suburban Maryland Piedmont. It was reported that three out of the nine basins or traps removed sediment at a rate of 94%, five basins were in the 55% to 85% range, and one trap removed less than 20% incoming sediment (due to internal erosion at inlets).

Additional research (not related to construction sites specifically) conducted in Colorado, Texas, North Carolina (USA), New Zealand and Canada. The monitoring in Colorado revealed that the pond was reasonably effective at removing many pollutants during storm events. For example, 78% of suspended sediment, 60% of zinc and copper were removed

from the pond. North Carolina pond research in 1978 and Central Texas research in 1997 findings were: 93% removal efficiency for TSS for both ponds. The performance of pond/wetland system was evaluated in 1992 at a highly industrial site in New Zealand. It was found that removal of solids and various forms of phosphorus approached 75%, removal of total copper, lead, and zinc exceeded 85%. At least 80% of suspended solids and total phosphorus were removed by three Canadian wet ponds in 1996.

Stormwater ponds are one of the most effective techniques for providing pollutant removal for urban streams. Stormwater ponds are among the most adaptable, effective and widely applied stormwater treatment practices in developing areas. The popularity of stormwater ponds can be attributed to their proven ability to attenuate flows from design storms; high urban pollutant removal capability; longevity, particularly in comparison to other types of stormwater practices (Schueler and Holland, 2000). Overall, the performance monitoring studies indicate that the removal efficiencies are highly variable and that the current design of most basins is not capable of accomplishing the challenge of 95% to 99% removal.

Because of the difficulties of sampling basins and traps at active construction sites, researchers use computer models to predict removal efficiencies. Examples include the work of Barfield and Clar in 1985 and Kirby in 1991 (Schueler and Holland, 2000). Both model studies suggest that sediment basins can achieve a much higher performance level than reported in the field.

To estimate the removal efficiencies, computer modeling uses algorithms that simulate a behavior referred to as type 1 settling. The basic principles for type 1 settling are: the flow within the basin is quiescent, settling is governed by particle size distribution of inflow sediment, and removal depends on adequate detention time. In the "real world", sediment basin design criteria require some practical and simplifying shortcuts. Most notable, a design particle is used as the spectrum of incoming particle size. The design particle is a convenient representation of the entire range of incoming sediment particles.

It is very difficult to effectively remove most particles less than 10 microns in size (e.g., silt and clays) by sedimentation alone. Detention time is important, as large particles tend to settle swiftly while finer-size particles have a slower settling velocity and tend to remain

suspended in the basin. Therefore the settling velocity of the design particle is a key component of basin design. In an ideal situation, discharge from the basin will not begin until the design particle has settled out. Particles with settling velocity greater than the design velocity will be completely removed. Particles with slower settling velocities will be removed at a ratio of: actual settling velocity/ design settling velocity.

Theory implies that longer detention will provide greater removal efficiencies. However, field laboratory data have shown that most settling occurs within the first few hours and that little additional settling is gained by increasing detention time. As much as 60% of removal is accomplished within the first six hours and additional increments of sediment removal are more difficult to obtain after the rapid initial settling (Schueler and Holland, 2000).

Again, according to Schueler (2000), to make field performance more closely match theoretical performance criteria re-examination of sediment basin design theory and application by focusing on increased removal of smaller particles is the key solution. Some steps towards this goal include selecting smaller design particles, providing more storage, and decreasing incoming sediment loads.

It seems that basic design of sediment basins and traps can be improved and made more reliable, but there are limits to settling. It is safe to assume that an 80 to 90% removable rate is probably the best that can be achieved under field conditions. Likewise, it should be acknowledged that most sediment basins cannot reliably meet "clear water" discharge concentration. However, new methods are being developed and tested to capture the finer particles that remain in suspension because of their low settling velocity.

2.2.3 Management of Fine Sediments

As mentioned above, because fine silt and clay-sized particles have low settling velocities, sedimentation basins are largely ineffective at reducing turbidity caused by these particles.

Research by Przepiora et al. (1997) in North Carolina determined that the turbidity of water discharged from sedimentation basins at two construction sites during a 1-yr period ranged from 120 to 3200 nephelometric turbidity units (NTU), which corresponded to

suspended solids concentrations of 90 to 2800 mg/L. North Carolina regulations state that water discharged into a freshwater stream or reservoir must not cause the turbidity of the receiving water to exceed 50 NTU for drinking water sources and 10 NTU for trout waters (high-quality waters). To ensure compliance with these standards, the turbidity of discharge water should ideally be <50 NTU or <10 NTU. To achieve this goal more effective technologies for removing suspended solids are needed.

Flocculants promote the coagulation of fine suspended particles into larger flocules that settle more rapidly under the influence of gravity. Flocculants such as alum $\text{Al}_2(\text{SO}_4)_3 \times 18\text{H}_2\text{O}$] and organic polymers are widely used in wastewater treatment operations to aid in the removal of suspended solids and associated contaminants. Alum and gypsum ($\text{CaSO}_4 \times 2\text{H}_2\text{O}$) are found to be effective in reducing the turbidity of stormwater (Przepiora et al., 1998). However, when using chemical flocculants, it is important to avoid changes in water chemistry that adversely affect the aquatic ecosystem of the receiving water. For example, when using alum, an additional chemical treatment may be needed to offset any pH reduction caused by this acidic compound. With sulfate compounds, the level of dissolved SO_4 in the discharge water should not exceed water-quality standards (e.g., 250 mg/L is the SO_4 standard adopted in North Carolina).

Robbins and Brockway (1978) evaluated the effect of CaCl_2 additions on suspended solids discharged from sediment basins (ponds) that collected irrigation water from different agricultural settings. Although they demonstrated the efficiency of the CaCl_2 treatment for reducing discharge of suspended solids, no turbidity results were presented. Przepiora et al. (1997) compared the efficiency of several calcium sulfate sources (phosphogypsum, agricultural gypsum, and moulding plaster) for reducing the turbidity of water samples collected from sedimentation basins at construction sites in the Piedmont region of North Carolina. Commercial moulding plaster (plaster of Paris or hemihydrate; $\text{CaSO}_4 \times 0.5 \text{ H}_2\text{O}$) was an efficient chemical flocculant that contained fewer impurities than the other materials evaluated. In laboratory studies on sedimentation basin water, moulding plaster application rates of 350 to 700 mg/l decreased turbidity from as high as 3280 to 50 NTU within 3 h. Also, the amount of chemical flocculant needed to reduce turbidity to a given level decreased as the time allowed for flocculation and gravity-induced settling increased. Therefore, to use the chemical flocculation approach for sedimentation basins at

construction sites, it is desirable to control both the detention time of the impounded water and flocculant application rate.

2.3 Hydrologic Modelling of Urban Runoff

2.3.1 Modelling Concepts

Management of the quantity and quality of stormwater runoff from urban areas is a complex task that has become an increasingly important environmental issue for urban communities. Together with economic and social issues, the increased awareness of the impacts of urban drainage systems has resulted in a need to obtain information regarding the drainage system response to varying conditions. Choi and Ball (2002) proposed two standard approaches for obtaining the desired information:

- monitoring of the system for both water quantity and quality, or
- implementation of catchment modeling systems which simulate the important processes influencing the quantity and quality of stormwater runoff from the urban environment.

Where changes to the management of a stormwater system are proposed and it is desired that the impacts of these changes be assessed then it is necessary to adopt the second approach as the first approach can only provide historical information; consequently, monitoring of the stormwater system can provide the desired information only after implementation of the proposed changes. Implementation of a catchment modelling system simulating flows in a stormwater system, however requires monitored information to ascertain the reliability and robustness of the predicted flow conditions.

Computer modelling can be one of the more effective and efficient methods for predicting the quantity and nature of runoff, and the effectiveness of best management practices (BMPs).

A hydrologic model can be defined as a mathematical model representing one or more of the hydrologic processes resulting from precipitation and culminating in watershed runoff (Zoppou, 1999). Hydrologic models aid in answering questions about the effect of land-management practices on quantity and quality of runoff, infiltration, lateral flow, both

saturated and unsaturated subsurface flow, and deep percolation. While models can be extremely useful in determining the effects of projects on water quality and quantity, a model is most accurate when it is used with actual data and measurements. Also, the more actual measurements properly applied to calibrate a model, the more accurate the model will be.

Hydrologic models can be used in two ways: (1) to assess the existing hydrology and water-quality conditions of a water resource, and (2) to predict future hydrology, which may develop as a result of changes in land use, climate or any other physical alteration to the environment.

Models should be used with caution and within their span of applicability. Each model is developed for a specific purpose with certain underlying assumptions.

Monitoring is always essential. Modelling can never replace monitoring. However, modelling is usually an effective way to evaluate the nature of the problem. The data collected in monitoring can help improve modelling predictions and development. Modelling is feasible only for evaluating problems that are understood well enough to be expressed in concise, quantitative terms. As models are developed to represent complex hydrologic systems, assumptions are incorporated in each model. The equations and formulas used to represent complex system are never complete, due to complexity of the system. In some situations, modeling may not be feasible or necessary. Modeling a situation may help determine whether monitoring would be beneficial. Models are used for analytical convenience. As tools for addressing hydrological questions, models do have limitations.

The main goals of urban water quality modelling are to: characterize the urban runoff; provide input into receiving water analysis; determine effects, sizes and combination of control options; perform frequency analysis of quality parameters; and provide input to cost-benefit analysis (Tsihrintzis and Hamid, 1997). The first two goals are related to the magnitude of the problem and the last three are related to the analyses and solution of the problem. One approach to modelling process in an urban watershed is presented in Figure 2.3.

A brief description of stormwater quality models based on research of Zoppou (1999) and Tsihrintzis and Hamid (1997) is presented. Some of the most popular and comprehensive models used specifically for urban runoff pollution include: SWMM (Storm Water Management Model), STORM (Storage Treatment Overflow Runoff Model), DR3M-QUAL (Distributed Routing Rainfall-Runoff Model), FHWA (Federal Highway Administration), and QQS (Quantity-Quality Simulation). STORM permits individual pollutants to be calculated for buildup purposes as a fraction of dust and dirt. In STORM, pollutants are pre-specified while in SWMM they may consist of up to ten different constituents (up to thirty in recent versions). Pollutant buildup in SWMM is done for each pollutant individually, without needing to use dust and dirt and the pollutant fractions. HSPF has the same flexibility as SWMM for up to ten arbitrary pollutants. STORM arbitrarily adds fractions of suspended and settleable solids to other pollutants, thus accounting for pollutants that adhere to solids.

Fig. 2.3: Urban watershed modelling process (Source: Tsihrintzis and Hamid, 1997).

DR3M-QUAL computes impervious area buildup for up to four constituents individually, whereas for pervious areas it calculates concentration of each pollutant as a linear function of the sediment concentration. In FHWA, up to 13 pollutants can be chosen from a pre-specified list, all of which are calculated as a fraction of suspended solids. QQS does not use dust and dirt buildup, but uses individual parameters for up to two pollutants. FHWA only simulates single-event storms and STORM only provides continuous simulations. The rest of the models provide both single-event and continuous simulations.

The characteristics and capabilities of selected NPS (non-point source) pollution models used in the U.S.A. are comparatively presented in Table 2.4.

Table 2.4: Characteristics and capabilities of selected NPS models (Source: Tsihrintzis and Hamid, 1997)

Model	Land use				Hydrology			Water quality			Data needs		Time scale	
	Urban	Agri- cultural	Forest natural	Mining application	Surface runoff	Subsurface flow	Sediment	Sediments	Stressors	Pesticides toxics	Detailed	Moderate	Event loads	Continuous simulation
ARM	*			*	*	*	*	*	*	*	*		*	*
NPS	*	*	*		*	*	*	*	*	*	*		*	*
HSPT	*	*	*	*	*	*	*	*	*	*	*		*	*
CREAMS	*	*		*	*			*	*	*	*		*	*
ANSWERS	*	*	*	*	*	*	*	*	*	*	*		*	*
ACRIMO	*			*	*	*	*	*	*	*	*		*	*
SWMM	*				*	*	*	*	*	*	*		*	*
STORM	*				*	*	*	*	*	*	*		*	*
PRZM			*		*	*	*	*	*	*	*		*	*
DRSMQUAL	*				*	*	*	*	*	*	*		*	*
FWQA	*				*	*	*	*	*	*	*		*	*
QOS	*				*	*	*	*	*	*	*		*	*

* Capability included in model.

2.3.2 SWMM Description

SWMM is among the most widely used urban water quality simulation models. The EPA's SWMM is a comprehensive hydrological and water quality simulation model developed primarily for urban areas (James, 2000). It is capable of both single-event and continuous simulation for almost all components of rainfall, runoff and water quality processes within a catchment. SWMM comprises five main subroutine modules or blocks, which can simulate different components of the hydrological cycle. Each block has a specific function, and the results of each block are entered on working storage devices to be used as part of the input to other blocks.

The main calling program of the model is called the Executive block. This block is the first and last to be used and performs all the necessary interfacing among the other blocks.

The RUNOFF block is used in for storm water runoff simulations. Hydrological computations in the RUNOFF block are based on the theory of non-linear reservoirs. Time of concentration is computed based on the kinematics' wave theory. Two pervious area

infiltration loss equations are available, the Horton and Green-Ampt The Runoff block uses Manning's equation to route the uniform rainfall intensity over the overland flow surfaces, through the small gutters and pipes of the sewer system into the main sewer pipes, and out of the sewer pipes into the receiving streams. This block also provides time-dependent pollutional graphs (pollutographs).

A third package of subroutines, the TRANSPORT Block, determines the quality and quantity of dry weather flow, calculates the system infiltration, and calculates the water quality of the flows in the system.

A package of subroutines for water quality determination is contained in the Storage Block. The STORAGE Block allows the user to specify or have the model select sizes of several treatment processes in an optional wastewater treatment facility that receives a user-selected percentage of the peak flow. If used, this block simulates the changes in the hydrographs and pollutographs of the runoff as the water passes through the selected sequence of unit processes. Evaporation from reservoirs is simulated by a monthly coefficient (supplied by a user) multiplied by the surface area.

The EXTRAN Block completes the hydraulic calculations for overland flows, in channels, and in pipes and culverts. It solves the complete hydrodynamic equations, assesses surcharging, performs dynamic routing, and provides all the depth, velocity, and energy grade line information requested.

SWMM is the only event-based model listed that uses Horton's equation for calculating watershed infiltration losses. Input for Horton's equation consists of the maximal and minimal infiltration rates and the recession constant. The Green-Ampt equation is also used in SWMM.

Urban storm drainage components are modeled using Manning's equation and the continuity equation. The water depth over a subcatchment will increase without inducing an outflow until the depth reaches a specified detention requirement.

Surface runoff is computed in SWMM for any rainfall hyetograph, considering land use type and topography, and accounting for antecedent moisture conditions, infiltration losses

in pervious areas, surface detention, overland flow, channel/pipe flow and constituents carried by runoff into inlets. Important input parameters are: the catchment's slope, pervious and impervious depression storage, channel and conduit layout, geometry and properties, the Manning's roughness coefficient for both overland and channel flow, and rainfall intensity, among others.

The RUNOFF block can also simulate quality of runoff processes within a drainage basin, and the routing of flows and contaminants along storm drain lines, leading to the calculation of a number of inlet hydrographs and pollutographs.

Pollutants in storage systems can be modelled as either complete mixing or plug flow. The stand-alone module EXTRAN permits SWMM to rout inflow hydrographs through open channel and a closed conduit system using an explicit numerical solution of the shallow water wave equations. Eight conservative pollutants are: suspended solids, settleable solids, BOD, COD, total nitrogen, total P, oil/grease, total coliforms as well as an arbitrary pollutant and erosion simulated in surface runoff.

Three general types of output are provided in SWMM. If waste treatment processes are simulated or proposed, the capital, land, and operation and maintenance costs are produced. Plots of water quality constituents versus time present the second type of output. These pollutographs are produced for several locations in the system and in the receiving waters. Quality constituents handled by SWMM include suspended solids, settleable solids, BOD, nitrogen, phosphorus, and grease. The third type of output is hydrologic. Hydrographs at any point, for example, the end of a gutter or inlet, are determined for designated time periods. The Statistics Block provides frequency analysis of storm events from a continuous simulation.

2.3.3 Modelling Studies

Studies related to SWMM validation and applications have been undertaken in the past by various authors (e.g. Jewell and Adrian, 1978; Jewell et al., 1978; Zaghloul, 1981; Zaghloul and Al-Shurbajia, 1990; Baffaut and Delleur, 1990; Warwick and Tadepalli, 1991; Tsihrantzis and Hamid, 1998; Lei, Li and Schilling, 2002; Dent, 2003). These studies are briefly described herein as they relate to this project.

A detailed sensitivity analysis was conducted on the main parameters of the SWMM RUNOFF-TRANSPORT blocks by Zaghloul (1981). The main purpose was to establish which are the most sensitive parameters affecting the Runoff-Transport simulation. The parameters' sensitivities were judged based on their effects on the simulated hydrograph in terms of shape, peak flow, volume of runoff, time to peak and consistency of the results. The most sensitive parameters found by Zaghloul (1981) are: percentage of area impervious in the RUNOFF block and conduit length in the Transport block.

Zaghloul and Al-Shurbaji (1990) described a comprehensive study conducted to implement SWMM for urban areas in Kuwait. Fine and discretized modeling approaches showed little difference in hydrographs. It was noticed that due to high infiltration capacity of the prevailing sandy soil, there was no runoff contribution by the pervious areas. Hence, all model parameters related to pervious areas did not need to be accurately represented in the model.

The SWMM was applied to a 10 m² urbanized area residential area in Dallas by Warwick and Tadeipalli (1991). Three different levels of watershed spatial abstraction were investigated in concert with the impact of using two different parameters for model calibration (pervious depression storage and percentage of area impervious). The calibrated model performed well at predicting both total runoff volume and peak flow rate. Water quality simulation was also quite acceptable, but with a consistent underestimation of total suspended solids concentration.

Tsihrintzis and Hamid (1998) applied SWMM to simulate the quantity and quality of urban stormwater runoff from four sites in South Florida. The objectives were to test the applicability of the model in small subtropical urban catchments. It was found that SWMM performed very well in small areas. Average model-predicted concentrations for the four constituents (BOD₅, TSS, TKN and Pb) during model verification showed good agreement with published values in Florida.

There are a variety of methods that have been developed to calibrate mathematical or conceptual rainfall-runoff models. Jewell et al. (1978) described a methodology for calibrating coupled quantity-quality urban stormwater management models using SWMM on a 1014-acre basin in Greenfield, Massachusetts. By separating the quantity and quality

portions of the model it was possible to calibrate each using measured data. Verification results showed good agreement between observed and predicted values.

Jewell and Adrian (1978) presented the SWMM pollutant washoff functions and stressed the importance of calibrating each model for the given basin. They described a methodology that can be used effectively to adjust the parameters for a given watershed.

Baffaut and Delleur (1990) developed an interactive program to automate the calibration of the water-quality parameters of the RUNOFF block of SWMM by using Expert-system technology. It acts as a front end in the estimation of the parameters and the build up of the input files. The goal of the Expert system is to obtain a set of parameters for which the predicted pollutant loads are close to the measured loads. The Expert system has been tested on several watersheds including the Denver watershed (Colorado), and it was found that it could perform the calibration but that shortcomings exist in the model itself that cannot be alleviated through calibration.

Lei, Li and Schilling (2002) developed a new model calibration procedure called Stepwise Hypothesis Test Model Calibration procedure (SHYTMC) that tries to overcome the limitation and problems of classical model calibration/ verification procedures. The objective of model calibration using SHYTMC is to find a parameter space that results in a band of modelled output time series. The specific feature is that the SHYTMC procedure is not intended to verify a model; it uses all observed data for calibration.

CHAPTER 3

STUDY SITE

3.1 Study Site and Stormwater Catchment Area Description

The study site is approximately 15.1 hectares in size located south of Sunset Beach Road and west of Bayview Avenue within Community of Oak Ridges in the Town of Richmond Hill. The development lands are surrounded by Sunset Beach Drive in the north, Bayview Avenue in the east and existing developments in the west and south as shown in Figures 3.1 and 3.2. The site is known as Ballymore on Bayview Development Phase I and II (formerly known as the Longmoor lands).

The stormwater catchment area consists of two subcatchment areas which discharge the stormwater runoff into Ballymore sediment control pond. One of the subcatchments is 12.96 hectares in size and located at the south-east side of the pond. It discharges runoff into a pond through the pipe with a diameter of 1070 mm. Through the study we will be referring to it as Catchment-1070 (C-1070), or Construction Catchment. The subcatchment with an area of 2.14 ha on the north-west side of the pond discharges the runoff through the pipe with a diameter of 510 mm and will be referred to as Catchment-510 (C-510), or Stable Catchment.

At the time of the study (fall 2002-fall-2003), Catchment-510 had been completely developed and Catchment-1070 was under development with active construction of building structures. At the time monitoring began construction activities at Catchment-1070 were in a stage with houses and roads already built, but driveways and lots were exposed to erosion. During this time period, piles of earth were present throughout the inlet of Catchment-1070 area and the roads were completely covered with soil that had eroded from the site.

As a result, this study will provide specific information on the water quality from construction sites with active building structures and performance of sediment control ponds in addition to other general construction site characteristics.

Fig. 3.1: Ballymore Study Area

Fig. 3.2: Key Plan

Bulkheads were installed at both inlets to reduce the amount of sediment entering the pond during the construction period. The bulkheads are removed after construction is complete and the sediment control pond is converted to a stormwater management pond. The use of bulkheads is a standard practice for construction sites using sediment control ponds. These are installed in the maintenance chamber of the sewer pipe discharging runoff into the pond. They are designed to decrease the amount of sediments entering the pond.

At the beginning of the monitoring program, the sediment control pond was experiencing erosion along its banks (Figure 3.3). The vegetation growth was not completed for the most of the 2002 fall sampling period.

Fig.3.3: Ballymore Pond bank erosion, September 2002 (Source: Pyatt, 2003).

Figure 3.4 represents the image of the pond banks vegetation almost at the end of the monitoring period in September 2003.

Fig.3.4: Ballymore Pond banks vegetation, September 2003.

3.1.1 Soils and Drainage

The site is situated on Markham till plain, on medium textured shale and limestone Woburn loam and Woburn sandy loam. This is typically susceptible to sheet erosion. Both external and internal drainage is good (Hoffman and Richards, 1955). Till here has been modified by lacustrine sand, silt and clay, or by kame deposition consisting of sand and gravel. The regional topography is moranic, where occasional thick peat deposits occur in the local depressions. The subsurface conditions included a stratum of silty clay till.

The soil within the study area primarily consists of about 1.5 meters of sandy silt till (or silt and sand till) over stone clayey silt till. Around the perimeter of the sandy silt area, the clayey silt till is closer to the surface and predominates (Sabourin Kimble & Associates Ltd., 2000).

In the pre-development scenario the surface drainage from the study area was draining via overland sheet flow and ditch systems northward to lake Wilcox. Under post development scenario the drainage from the site is conveyed to SWM facility through curb, gutter, storm sewers and the discharge from the facility will be conveyed through a swale to the downstream storm sewer and then to Lake Wilcox.

3.2 Pond Design Features

The storm water management (SWM) facility, which is currently used as a construction sediment control basin for the site is located in the north-west corner of the site. The SWM facility was designed to serve an area of approximately 15.1 hectares in size, which primarily consists of residential land use. The storm drainage from the study site is conveyed to the SWM facility through major and minor systems and the outflow from the facility eventually feed into Lake Wilcox downstream.

In addition to permanent pool volume, the SWM facility is designed to store the runoff from a 25-mm storm event for 48-hr (drawdown time), and 1:2 through 1:100 year peak flow control to a maximum outflow of 1.4 m³/sec which is less than the capacity of the downstream receiving ditch (Sabourin Kimble & Associates Ltd., 2000).

The permanent pool volume is based on MOE Stormwater Management Practices Planning and Design Manual (Enhanced Level of Protection). The facility is designed with a shallow sediment forebay. Table 3.1 compares the MOE's SMPD manual wet pond guidelines for Enhanced Level of Protection (with 45% surface imperviousness) and the measured Ballymore pond as-built conditions. Other design parameters are shown for reference. As shown, the pond meets the MOE sizing requirements for maximum permanent pool volume, extended detention volume above permanent pool volume, and drawdown time.

Table 3.1: Comparison pond design features

Design Parameter	Objective	MOE SMPD Manual	Ballymore Pond
Permanent pool volume (m ³ /ha)	Enhanced Level of Protection	125*	154
Permanent pool depth (m)	Minimize resuspension	1-2 (mean); 3 max	2.4 max
Active storage depth (m)	Storage and flow control	1 to 1.5; max 2	1.6
Extended detention (m ³)	Runoff from 25 mm storm	40	110
Quantity control volume (m ³)	2-100 year water quantity control	N/A	242
Drawdown time (hours)	Suspended solids settling	24	48
Length to width ratio	Maximize flow path and minimize short-circuiting	3:1	2:1

* Based on Enhanced Level of Protection and 45% surface imperviousness (MOE, 2003)

Ballymore Pond with two inlets and an outlet is represented on Figure 3.5. Pond's cross-section is shown in Figure 3.5.

Fig. 3.5: Ballymore Construction Sediment Control Pond

The pond has a total storage volume of 6071 m³, which includes a permanent pool volume of approximately 2360 m³. The extended detention outflow is controlled by a 112 mm diameter orifice resulting in a 48 hour drawdown time (runoff from a 25 mm storm). Two

orifice plates (444 mm and 515 mm diameters) situated within Ditch-Inlet-Catch-Basins (DICBs), control the flow during 1:2 to 1:100 year storms. The outflow from the pond currently discharges into an open 42-m ditch south of Sunset Beach Road.

Lake Wilcox is the primary receiving water body from the outflow of the pond. Located within York Region, and the Oak Ridges Moraine, Lake Wilcox has been recognized as a valuable recreational and environmental resource (FCM 2000; Town of Richmond Hill 2003). Lake Wilcox is a kettle lake, formed by the melting of a remnant block of glacial ice (Town of Richmond Hill 2003). The lake has a surface area of approximately 55.6 ha, with a watershed area extending over 260 ha within the moraine (Town of Richmond Hill 2003).

Unfortunately, Lake Wilcox has been exposed to various pollutants through the ever-increasing anthropogenic activities undertaken within its watershed (Town of Richmond Hill 2003). This has resulted in an unhealthy aquatic ecosystem. According to the Town of Richmond Hill (2003), issues associated with the water quality include the buildup of phosphorus in the water column, a lack of oxygen in the bottom waters, too many nuisance plants in the water and too few fish of desirable species. Nutrients from fertilizers, septic systems, and naturally occurring sources within the watershed have collected within the lake over time (Town of Richmond Hill, 2003). Other issues include the lack of clarity in the water, altered shoreline, inadequate water balance creating the need to control the outlet via dam structure, and a shift in aquatic communities (Town of Richmond Hill, 2003).

Fig. 3.6: Ballymore Pond's cross-section.

CHAPTER 4

METHODOLOGY

This chapter discusses a system of methods used in this research. The chapter is sectioned into the following parts: (i) monitoring, including rainfall and runoff monitoring, water quality sampling, and monitoring of construction activities and bottom sediments accumulation; (ii) monitored data analysis, including water quantity and quality analysis; (iii) the PCSWMM component with the description of RUNOFF and STORAGE/TREATMENT blocks that are used, calibration techniques, and continuous simulation.

4.1 Monitoring

Assessment of Ballymore Pond facility performance was based on coordinated measurements of rain, runoff volumes and water quality at the inlet and outlet during fall 2002 (September-October) and spring / fall 2003 (May-November) period.

In cooperation with the Government of Canada's Great Lakes Sustainability Fund (GLSF), Town of Richmond Hill (RH), Toronto and Region Conservation Authority (TRCA), Department of Fisheries and Oceans (DFO), Ontario Ministry of Environment (MOE), National Water Research Institute (NWRI), Ryerson University has monitored a sediment control pond in the Town of Richmond Hill since 2002. This monitoring program was implemented to evaluate the pond's performance throughout the construction period and to help to determine what changes (if any) are necessary to improve current design criteria. Monitoring was conducted by L. Pyatt from the beginning of the program with the help of the author from May 2003. L. Pyatt left the program on June 2003. The author continued monitoring until the end of the program in November 2003.

The primary objectives of the monitoring program were to collect water quantity and quality data representative of the construction sites draining into the local receiving waters and monitoring of water quantity and quality for all phases of construction which would provide relationship between construction phase, pollutant loads and removal efficiency of the pond.

4.1.1 Rainfall and Runoff

Rainfall data are necessary to estimate the amount of runoff generated during an event, which is then used to predict runoff volumes and predict responses to events of different magnitudes.

When monitoring, it has been recommended that rain gauges be placed at least every 2.5 to 5 square kilometers (Keefe et al., 1995). A tipping bucket rainfall gauge and data logger has been set up since 1996 on the roof of a municipal building near the construction site (within 1 square kilometer) and operated by TQI Thompson Flow Investigation on behalf of the Town of Richmond Hill. The hourly rainfall records have been received from 1996 to 2003.

Measured rainfall at a short time interval (i.e. 15 to 60 minutes) within the study area reassures the event start times for measured flow and level within the pond. A local rain gauge also gives cleaner hydrographs since the rainfall should reflect the intensity and duration of the event when plotted against level and flow measurements.

The collected raw rainfall data was processed for volume, duration, intensity and antecedent periods' values and used for runoff simulation

Runoff flow measurement is needed to calculate pollutant loads and design BMP's.

Flow data was collected using a flow logger, and an area velocity sensor. The 4150 Flow Logger, manufactured by ISCO Inc., is capable of measuring the average velocity and pond water level, while calculating the flow rate of the flow stream (ISCO, 1993). The depth and velocity sensors are both contained within a single probe, which was installed at the invert of the sewer pipe. The data logger used FLOWLINK3, ISCO's flow-data management software for programming and calibration. Readings were retrieved using a laptop computer. The software facilitated to program and download data from the loggers. Downloaded data was converted to EXCEL spreadsheet for interpretation and analysis.

The Area Velocity Sensors (AV probes) were used at each inlet and outlet. Using technology based on the Doppler effect, the velocity sensor directly detects the average

velocity of a stream as the flow moves up or downstream (ISCO, 1993). In addition, the a/v probes contain a differential pressure transducer that senses the hydrostatic pressure produced by the water above the sensor (ISCO, 1997). The velocity sensors are programmed to trigger the ISCO 6712 samplers when there is an increase in level or flow. At the Richmond Hill study site, the a/v probes were programmed to trigger the samplers based on an increase in level. Description and location of measuring devices are given in Table 4.1.

Table 4.1: Installation location and description of measuring devices

Station	Description	Quantity
King Rd. and Yonge St. intersection	Tipping bucket rainfall gauge	1
Inlet-1070 (south-east side of the pond)	ISCO 6712 Water Quality Sampler	1
	4150 ISCO Flow Logger	1
	Area Velocity Sensor (AV probe)	1
Inlet -510 (north-west side of the pond)	ISCO 6712 Water Quality Sampler	1
	4150 ISCO Flow Logger	1
	Area Velocity Sensor (AV probe)	1
Outlet (north part of the pond)	ISCO 6712 Water Quality Sampler	1
	4150 ISCO Flow Logger	1
	Area Velocity Sensor (AV probe)	1

With the concern for potential damage of the flow monitoring devices during the winter/early spring season, flow-monitoring devices were installed only for the late spring/summer/late fall season (August 2002 to November 2002 and May 2003 to November 2003).

All the devices being used for data collection were frequently inspected for any faults or problems. Current maintenance of installed equipment, such as cleaning the probes from debris was performed to make sure the flow readings were correct.

The automatic sampler is powered by a 12-volt deep cycle DC power source. Battery life depends on the type of battery used, the recording interval and how frequently the

automatic sampler triggering mechanism is initialized. One standard 12V DC battery provided the power for each logger and was adequate for the collection of at best one event.

4.1.2 Water Quality

The ISCO 6712 portable samplers were selected for wet weather water quality analysis. These samplers have enough memory to store five sampling programs and sampling data that can be viewed through the sampler display (ISCO, 1997). The samplers were chosen based on their ability to collect individual samples over specified time intervals to account for the variability in constituent concentration throughout the course of any runoff event (ISCO, 1997). The samplers are equipped with 24 bottles that collect water samples for quality testing throughout the course of the event. For wet-weather events the samples were activated automatically (triggered by increases in water level) to capture the entire storm hydrograph. Samples were then flow-composited and analyzed to also measure event mean concentration (EMC).

Samples were submitted to the Ministry of Environment and Energy Lab in Toronto and analyzed following principles outlined in *Standard Methods* (Eaton *et al.*, 1998) for metals, nutrients (P and N) and general chemistry. Particle size analysis of suspended solids was undertaken using an optical laser light diffraction method and results were reported by size class in percentage by weight. Appendix A summarizes the analytical procedures used in this study.

Some programming features are difficult to determine until several events have occurred and the data is reviewed. This period is commonly referred to as the 'trial and error' period. For example, in this study, flow proportional sampling was requested. However, after an event, the pond experiences a slow drawdown time causing back flow to occur up the two inlet pipes. The back flows caused pooling and reverse flow measurements. Thus, the samplers were not able to collect water samples under these programming conditions.

As a result the samplers were set to trigger on an increase in level and programmed to collect every five minutes. This way the logged flow data (at five-minute intervals) and the samples could be calculated to reflect flow proportioning. The samplers were programmed

to collect 1 sample per bottle (24 bottles) at five-minute intervals, over a period of 120 minutes. Each bottle has a capacity of 1L. Discrete water samples were collected for each event and analyzed for Suspended Solids (SS). Portions from each discrete sample were extracted and mixed to form composite samples. Composite samples were analyzed as average concentrations for several parameters including metals, nutrients, and general chemistry.

Depending on site characteristics, a sampling program designed to collect time-weighted samples at five-minute intervals (120 minutes duration) should be monitored carefully. For example, if the storm duration is less than 120 minutes, baseflow may be collected in some of the 24 bottles, resulting in diluted composite samples. If the storm duration is longer than the 120 minutes, then the sampler will not be able to characterize the entire event. In this study runoff flow peaks were observed within the 120 minutes of sampling, enabling the analysis to be representative of the major moments in an event (i.e. just before the peak of the hydrograph, or the first flush). Therefore, during the spring (2003) sampling season, it was decided to alter the sampling program and change the sampling intervals from five minutes, to fifteen minutes. This change in time interval extended the sampling period from 120 minutes to 360 minutes, or 6 hours. Summary of collected data is included in Appendix B.

The summer of 2003 experienced frequent but short-duration rainfalls. This caused the sampler to trigger and start the collecting process. This short rain duration was enough to provide a collection of 3-4 bottles, and at other times no collection was experienced. When a heavy rainfall followed this condition there would be no collection due to the fact that the sampler was previously triggered and not reset before the event. Often times the monitoring staff was not aware of the earlier short rainfall. This occurrence would only be evident when the staff arrived to collect samples.

Flow data was collected from the inlets and the outlet on a continuous basis. Maintaining the equipment was very important. If any of the loggers malfunctioned, flow data would not be recorded, or if a sampler triggered earlier or did not trigger at all due to incorrect settings, there would be no samples collected from that station. For example, samples from the outlet during August 2003 were not collected due to the incorrect setting of a

trigger mechanism. In July-August the pond level was too low to be influenced by rainfall. Because the triggering time was set too high, there no samples were collected.

4.1.3 Monitoring of Construction Activities

Performance monitoring at construction sites is not an easy task. A construction site is never the same from month to month, and each storm event creates an ever-changing series of channels and gullies that contribute to runoff and sediment at multiple points.

The housing construction phase was ongoing in Catchment-1070 at the time of monitoring period, thus the state of the lots and driveways was monitored to determine the area directly exposed to erosion. A checklist was developed that indicated the lot # and whether the lot was exposed, or sodded and whether the driveways were gravel or paved. The drainage area serviced by Inlet 1070 was completely exposed for the majority of the fall 2002 and spring 2003 sampling period. These conditions were reflected in the samples collected.

Figure 4.1 demonstrates the difference in samples collected from each monitoring station.

Figure 4.1: Water quality samples of each monitoring station (Pyatt, 2003).

In addition, these conditions were also apparent when comparing the conditions of the roads in both areas. The roads within the Catchment-510 drainage area were clean. Figure 4.2 demonstrates the road conditions during the construction.

Figure 4.2: Road Conditions in Catchment-1070 during construction 2002 (Pyatt, 2003).

Figure 4.3 represents road conditions during summer 2003 period. Roads are cleaner but lots of debris and piles of earth are still apparent beside lots under construction.

Figure 4.3: Road Conditions in Catchment-1070 during construction 2003.

4.1.4 Bottom Sediments Accumulation Monitoring

A significant amount of sediments accumulates within the facility during the life-span of a construction sediment pond, which typically ranges between one to three years, depending upon the size of development area. The higher accumulation rate attributed to the high soil erosion rates experienced at construction sites during rainfall events.

Marsalek et al. (1997) identified that once the sediment accumulation within the facility reaches a threshold level, the performance of the pond will be affected. The factors that affect performance include: (i) reduced settling times resulting from reduced storage volume; (ii) potential erosion of bottom deposits, and (iii) release of contaminants from the sediment into the overlying water column and their discharge from the pond into the receiving waters.

To measure bottom sediment accumulation within the pond, standard surveying techniques were used. A submersible surveying rod was constructed to meet the needs of this task. The rod was designed with a flat bottom with spikes to help anchor the rod to the bottom of the pond. By examining the pond elevation drawings, thirteen points were selected, where elevation measurements were taken. Stakes were driven into the pond bottom that extended above the pond's surface to mark where each of these points was selected. At each stake, the rod was submersed and the elevation marked. This was later converted into absolute elevation levels. The difference between the pond's bottom elevation and the measured elevation using the rod was then calculated. In this study method was applied at the end of monitoring period in October 2003. From these measurements, the total accumulation of sediments was obtained.

It is important to note that this method of measurement is regarded only as an approximation of bottom sediment accumulation. It is recognized that in using standard surveying techniques the elevation levels observed may be inaccurate, but can provide a general understanding of the rate of accumulation experienced in the pond. Therefore, it was verified from the modelling, which is discussed in a later section (Chapter 8).

4.2 ANALYSIS OF MONITORED DATA

4.2.1 Water Quantity Data Analysis

Water quantity data obtained during the monitoring include the rainfall data and the data collected through the flow and level measurement devices described in a previous section.

Rain data is presented in the form of *hyetograph*, which is a plot of rainfall depth versus time. In this study a hyetograph is plotted as a bar graph using an inverse y-scale (Fig. 4.4).

Rain falling on the watershed in quantities exceeding the soil and vegetation (interception and evapotranspiration) uptake becomes surface runoff (Viessman, 2002). Using other words, runoff occurs when excess precipitation moves across the land surface. The volume of runoff passing through a flow section is called discharge, or runoff rate, or flow rate (Akan, 2003).

The runoff reaches the inlet (or design point) from different parts of the catchment at different times and rates. Therefore, the discharge at the catchment inlet during and after a storm event varies with time. A plot of the discharge versus time is called a *hydrograph*. Hydrograph provides information on peak flows, time distribution of flows, the total flow volume over a certain duration which is very important in pond sizing.

A runoff hydrograph is generally bell-shaped, although multi-peaked hydrographs can result from variable rainfall rates. The general schematic of rainfall-runoff process is shown in Figure 4.4.

Fig. 4.4: Schematic of hyetograph and hydrograph.

Rainfall volume is the sum of rainfall during a rainfall event, and the rainfall event is one separated by a period of no rainfall (inter-event dry period) (Wanielista, 1993). For some research, 4 hours is the minimum interevent time for storms to be considered independent (Wanielista, 1993). In this study the interevent time of 12 hours is used to separate the events to be used in later modelling.

The total influent/effluent volume is determined by summation over the given time intervals (5 or 15 minutes). It is calculated as:

$$V = \sum_{k=T_1}^{T_3} Q_{ik} \Delta t_k \quad , \quad (4.1)$$

where Q is a flow measured over finite time interval, Δt ; T_1 represents the start of the runoff flow, and T_3 represents the end of the runoff flow.

Given the surface area of the catchment, flow data can be converted to a uniform depth of water over the catchment area.

The runoff coefficient for the catchment is the ratio of the runoff volume (or depth) to the rainfall volume (or depth) over an event. The runoff coefficient is a measure of the ability of the catchment to transmit rainfall, rather than allowing it to percolate into the ground or return to the atmosphere through evaporation and transpiration. A high value of the runoff

coefficient is indicative of a large percentage of impervious surfaces in the catchment. For construction sites, value of runoff coefficient provides an idea of the degree of runoff to be expected.

A stormwater quality pond designed for a frequently occurring event should (i) detain the design runoff long enough to achieve the targeted level of treatment, and (ii) empty the design runoff soon enough to provide available storage for the next event. Thus, the key design concepts for stormwater quality ponds are the *detention time* and the *emptying time* (drawdown time) (Akan, A.O., 2003).

Pond influent and effluent hydrographs are used to find parameters such as detention time and drawdown time. The time difference between the centroids of inflow and outflow is defined as the *hydraulic detention time*, or the average time by which the bulk of fluid is held back or detained by the pond. It is a measure of the ability of the facility to reduce its impacts on receiving waters.

Detention of 24 hours or more has been shown to remove 90% or more of the suspended solids (Wanielista and Yousef, 1993). However, soluble and colloidal fractions may not be significantly removed.

For the design of stormwater quality control ponds, *drawdown time* (time to drain a full pond) of 24-40 hours is used (Papa, 1999). At the same time it was pointed out that drawdown time often overestimates the actual detention time (Papa, 1999).

Sediment control ponds are designed with specific quantity control criteria including a minimum of 24 hours detention time. The Ballymore pond was designed for a 48 hours detention time. Thus, it is important to determine if the Ballymore Pond is performing as it was designed.

4.2.2 Water Quality Data Analysis

The Laboratory Services at the MOE performed the analytical tests of water quality results. The parameters analyzed in this study are outlined in the Table 4.3. The

analytical procedures used by the MOE lab for each parameter measured are included in Appendix A.

U.S. EPA (1993) defines discrete and composite samples as follows:

Discrete sample: individual samples collected at specific times collected manually or automatically, often combined to create a composite sample. *Composite sample*: samples combined based on a predetermined formula involving flow weighting, time interval, or other approach.

Of the water quality parameters listed in Table 4.2, SS was measured in the discrete samples collected at the site. The composite samples were analyzed for the remaining parameters. Once the samples are analyzed and results are received from the MOE laboratory services, they were interpreted for analysis of the pond's performance.

Table 4.2: Water Quality Analysis

Parameters	
General Chemistry	Conductivity, pH, turbidity, particle size distribution, chemical oxygen demand (COD), alkalinity, total solids, suspended solids, dissolved solids, chloride
Nutrients	Ammonia+ammonium, nitrite, nitrate+nitrite, TKN Phosphate, total phosphorus
Metals	Aluminum, Arsenic, Barium, Beryllium, Calcium, Cadmium, Cobalt, Chromium, Copper, Iron, Magnesium, Manganese, Molybdenum, Nickel, Lead, Selenium, Strontium, Titanium, Vanadium, Zinc
Organics	<p><i>PAHs:</i> Naphthalene, 2-methylnaphthalene, 1-methylnaphthalene, 2-chloronaphthalene, Acenaphthylene, Fluroene, Phenanthrene, Anthracene, Fluoranthene, Pyrene, Benzo(a)anthracene, Chrysene, Benzo(b)fluoranthene, Benzo(k)fluoranthene, Benzo(a)pyrene, Dibenzo(a,h)anthracene, Benzo(g,h,i)perylene, 1-chloronaphthalene, Perylene, Indole, 5-nitroacenaphthene, Biphenyl</p> <p><i>Herbicides and Pesticides:</i> 2,4-dichlorophenol, 2,4,6,-trichlorophenol, 2,4,5-trichlorophenol, 2,3,4-trichlorophenol, 2,3,4,5-tetrachlorophenol, 2,3,4,6-tetrachlorophenol, Pentachlorophenol, Silvex, Bromoxynil, Picloram, Dicambia, 2,4-D-propionic acid, 2,4-D, 2,4,5-T, 2,4-DB, Dinoseb, Diclofop-methyl</p>

4.2.2.1 Discrete Data Analysis

Stormwater quality refers to the pollutants in the water. Runoff pollutant concentrations typically vary with time as a result of erosive forces (flow rate) and the duration of runoff events. Consequently, water quality data are often represented by pollutographs. Pollutographs are measured by collecting discrete samples at uniform time intervals, and graphed as time-series data sets.

The primary quantitative measure of a runoff quality is its *concentration*. Concentration is defined as the mass of a constituent per unit volume of water and is mathematically represented as

$$C = \frac{M}{V}, \quad (4.2)$$

where M is quantity(mass) of a constituent, V is volume of water.

Concentration units used in this study are mg/L. The mass load is estimated for a given volume V by $M=CV$. The load per unit time is evaluated by $M=CQ$, where Q is the volumetric discharge rate. Both pollutant concentration and pollution load (mass) are used to evaluate the effect of a constituent on a water body.

Even though concentrations often vary by several times of magnitude during a storm event, a single index known as event mean concentration (EMC) can be used to characterize runoff constituents (Sansalone and Buchberger, 1997; Charteneau and Barrett, 1998). The EMC is defined as total constituent mass M discharged during an event divided by total volume V of discharge during the event (Huber, 1993). Mathematically,

$$EMC = \frac{M}{V} = \frac{\int C(t)Q(t)dt}{\int Q(t)dt}, \quad (4.3)$$

where $C(t)$ is constituent concentration at time t and $Q(t)$ is stormwater discharge at time t . The EMC is a flow-weighted average of constituent concentration. Total mass loading of a constituent during the storm is obtained by multiplying EMC by total volume of storm runoff.

Use of EMC is appropriate for evaluating effects of stormwater runoff on receiving waters. Receiving water bodies respond relatively slowly to storm inflows compare to the rate at which constituent change during a runoff event. Thus, it is total load or EMC that is important parameter.

The average event mean concentration (AEMC), that is the arithmetic mean of two or more individual storm runoff Event Mean Concentrations, is also used to characterize the quality of runoff.

4.2.2.2 Composite Data Analysis

The composite samples represent average concentrations, or total load, of each pollutant from all monitoring stations per event. Pollutants include metals, nutrients, and physical and chemical properties such as chemical oxygen demand, suspended solids, pH, alkalinity and etc.

The maximum and minimum average event mean concentrations are estimated and plotted in comparison with the PWQO to determine if any of constituents are exceeding the provincial guidelines.

Removal efficiency characterizes the performance of the pond during different stages of construction. Removal efficiencies for different pollutants are calculated using methods described in latter section.

Included in the water quality analysis of the composite data are the particle size distributions. The particle size distribution is significant as it describes the nature of particles that are entering and exiting the pond. The average cumulative particle size distributions were plotted and the D_{50} and D_{10} values were calculated for this study. The value for D_{50} represents the median diameter. This size is assumed to characterize the

bulk of the distribution (Simons & Sentrk, 1992). The D_{10} value represents the size of sediments where 10% of the distribution is larger size fractions (Chorley et al., 1984). Alternatively, everything smaller than the D_{10} values accounts for 10% of the distribution. This value holds significance because the proportion of fine material largely controls many of the dynamic properties of sediments (i.e. porosity, permeability, shearing resistance, etc.)

4.3 APPLICATION OF PCSWMM

Hydraulic and hydrologic conditions of the stormwater catchment's area and facility were modelled using the Stormwater Management Model (SWMM 4.3) developed for the EPA and run as the engine within the PCSWMM™ shell. The model simulates influent and effluent hydrographs and predicts sediment accumulation rates within the facility based on measured flow volumes, SS loads and rainfall recorded near the study site.

The model PCSWMM was selected for the following reasons: continuous water quantity and water quality simulation; accommodation of various hydraulic conveyance, storage and diversions elements with the drainage work; provision of storage/treatment capability; and popular support and acceptance of SWMM4 for continuous water quality and quantity modelling.

4.3.1 Runoff and Storage/Treatment Blocks

For this study 2 blocks of the program were used:

RUNOFF

This block generates surface runoff and pollutant loads in response to precipitation and surface pollutant accumulation. It also has a limited ability to route flows through pipes and gutters. Rainfall data is also executed within the RUNOFF block. The catchment was not subdivided, but was modeled as one lumped subcatchment. Construction catchment was modelled separately to investigate the behavior of catchment undergoing construction.

STORAGE/TREATMENT (S/T)

This block is designed to route flow and pollutant loads through a storage/treatment facility. The user is given a great deal of flexibility by the block's ability to connect as many

as five storage/treatment units, which may be given storage characteristics or be modeled as a simple flow-through device. We use one storage and treatment facility unit.

The SWMM Storage-Treatment block provides a framework to simulate hydraulic storage and treatment of up to three different pollutants in as many as five interconnected storage/treatment units. Modelled pollutant simulated in this study included only suspended solids. S/T was originally conceived to simulate the routing of flows and pollutants through a dry- or wet-weather storage unit or treatment plant, but it has been enhanced and is now general enough to wide application (Newman, et al., 2000). S/T may accept inputs for inflow and influent quality from any properly formatted source including output from the SWMM RAIN and RUNOFF blocks. In our case these flows and loads come from the RUNOFF block. Model output, which consists of either time series or summaries of discharged flows and pollutant concentrations, may be used as input for other SWMM blocks or may be re-processed for use with a host of other applications.

In addition to the inflow and concentration information provided in the RUNOFF interface files, the S/T block requires a number of other inputs to simulate pond performance. These inputs include a description of the physical and operational characteristics of the pond, options for either a completely mixed or a plug-flow regime, and information to describe the presumed decay rates of the pollutants to be modelled.

In this study, the SS treatment was simulated as the completely mixing reactor because of: (i) the construction pond permanent pool volume was large compared to the average event runoff volume, (ii) the high concentration of inflow SS, and (iii) mixing was facilitated by the presence of two inlets located opposite to each other. In this mode, the incoming sediments were instantly distributed uniformly throughout the facility resulting in uniform pollutant concentration throughout the facility. The removal efficiency was obtained as a function of the pollutant decay coefficient, which in conjunction with simulation time step, determines the decay rate. The analyses described herein utilized the first-order, exponential decay rates for pollutant removal. The S/T block was set-up as illustrated in the SWMM documentation (James, 2000) for the assignment of coefficients for Data Group G3 to analyze exponential decay in completely mixed systems.

4.3.2 Sensitivity Analysis and Model Calibration

Before modelling, it is advisable to understand the general behaviour of a water-quality model. One way to do it is called a *sensitivity analysis*.

According to James (2003) sensitivity analysis consists of varying model coefficients or parameters one at a time, with the amount varied being representative of the uncertainty in the parameter being analyzed. There is a variety of ways to implement such an analysis. Two of the most common are simple parameter perturbation and first-order sensitivity analysis. The parameter perturbation sensitivity analysis method is used in this study. As the name implies, *parameter perturbation* consists of varying each of the model parameters (for example raised and lowered a fixed percent) while holding all other terms constant (Chapra, 1997).

Calibration follows sensitivity analysis. W. James (2003) defines calibration as a “procedure to discover the global optimum of an array of modelling parameters that can only be discovered with estimation and are not directly measurable in the field”. Calibration of a catchment modelling system requires that the control parameters (input data) be determined so that the results of process model and input information mimic the real response of the catchment. Since surface runoff varies with the catchment characteristics, calibration of a catchment modelling system usually requires adjustment of the model control parameters to minimize prediction errors.

According to Choi and Ball (2002), there are two categories of the control parameters: (i) measured parameters (parameters that are physically measured, such as pipe diameters, catchment areas, rainfall depth or rainfall intensity, etc; and (ii) inferred parameters (parameters that are not measured and are determined from the application of a model: depression storage, Manning's roughness, imperviousness, etc.). In general, the values of inferred parameters are considered those that need to be adjusted during calibration, while measured parameters are assumed error free during the calibration. Inferred control parameters in this study are determined by “trial and error” method whereby the values of the input parameters are modified in a systematic manner until the simulated and monitored hydrographs and pollutographs are similar.

Figure 4.5 depicts how the model was calibrated.

Fig. 4.5: A flow chart depicting the calibration process of each model data
(Source: Choi and Ball, 2002).

Choosing values for input parameters is called parameter estimation (James, 2003). Uncertainty for input parameters should be estimated before calibration. All input parameters can be divided into 5 groups (groups B, 1, 2, 3 and 4) according to their level of uncertainty (from James, 2003):

B.*Binary*: Input that acts like switches, or run control input parameters that may be either completely correct (in the sense that the datafile runs correctly) or completely incorrect (the datafile crashes or does not run successfully).

1.*Parameters that can be measured with almost total certainty* (catchment areas, pipe diameter, and other conduit geometries, conduit slopes and elevations, storage areas and other). These are not good candidates for calibration.

2.*Parameters that can be estimated with a high degree of certainty in the field, design office or laboratory* (% imperviousness, Manning's n for pipes, particle size distributions, temperature, flow, concentrations and others). These can and should be modified within narrow limits during calibration.

3.*Parameters that cannot be easily measured in the field or laboratory* like infiltration rates, rainfall, pollutant build-up, pollutant wash-off, and many others. These are good candidates for calibration.

4.*Parameters that cannot be measured with any certainty at all*, such as mean ground slope in some situations, catchment widths, and several others.

For these categories, uncertainty varies in broad ranges:

B.uncertainty is either null or complete,

1.uncertainty is small, a few percentage points, perhaps 5-10%,

2.perhaps 10-25%,

3.perhaps 25-50%, and

4.who knows? If any estimate can be made at all, perhaps assume 50-100% as a starting point.

Tables of uncertainty classes for SWMM4 are listed in book of W.James "Rules for responsible modeling". Details are given in Chapter 7.

4.3.3 Continuous Simulation

In order to assess the Ballymore Pond performance and estimate the sediment load generation from construction watersheds with active housing construction condition, a long-term simulation model was developed. The long-term simulation was conducted using Toronto Buttonville Airport rainfall record. All input parameters subject to calibration procedure were averaged.

4.4 Assessment of Pond Performance

To assess the pond performance two sets of runoff quality data were used: (i) field data and (ii) data obtained as modelling results. Thus, two sets of removal efficiency values were obtained.

After quantity calibration, that is, matching modelled and observed combined inflow and outflows, the water quality calibration was conducted for each of the events. In this case, the observed SS load was compared for the simulated load for the sampling period during the event. If the runoff event duration is smaller than sampling period then the complete calibration for the event was obtained, otherwise a partial calibration was obtained.

The SS load based removal efficiency is defined as follows:

$$RE = \left[\frac{[(V_i \times EMC_i) - (V_o \times EMC_o)]}{(V_i \times EMC_i)} \right] \times 100\% , \quad (4.4)$$

where V_i is inflow volume, EMC_i is inflow concentration, V_o is outflow volume and EMC_o is outflow concentration and RE is removal efficiency.

CHAPTER 5

WATER QUANTITY ANALYSIS

In this section the results of water quantity analysis from the observed data are presented. Due to the unavailable data required for rainfall and flow, not all sample events were included in this analysis.

5.1 Rainfall-Runoff

Rainfall during the storm events in studied region ranged from approximately 7 mm to 38 mm. More detailed information about each storm event can be found in Table 5.1 and Appendix C. An inter-event time of 12 hours was selected to identify the individual events.

The rainfall events are classified based on the event volume: (i) large storms – greater than 20 mm, (ii) medium storms – between 10 mm to 20 mm, and small storms – less than 10 mm. During the monitoring period, two small size storms, eleven medium storms and six large storms were recorded.

Table 5.1: Rainfall event characteristics.

Event	Event Date	Total Rainfall (mm)	Rainfall Duration (hr)	Average Intensity (mm/hr)	Maximum Intensity (mm/hr)	Inter-Event Period (days)
1	14-Sep-02	28.8	8.4	3.5	47.5	23.3
2	20-Sep-02	13.3	5.3	2.6	72.5	0.5
3	27-Sep-02	18.4	8.9	2.1	7.5	4.5
4	2-Oct-02	10.0	13.8	0.7	17.5	5
5	19-Oct-02	13.0	23.5	0.6	5	0.5
6	25-Oct-02	9.4	6.3	1.5	5	1.9
7	2-May-03	6.8	9.5	0.7	2.4	0.6
8	5-May-03	17.4	14.5	1.2	6.4	3.4
9	11-May-03	17.8	13.8	1.2	11.2	4.8
10	20-May-03	10.8	4.5	2.2	8.8	3.5
11	4-Jun-03	13.8	17.0	0.8	5.6	3.5
12	8-Jun-03	23.6	21.3	1.1	19.2	3.4
13	13-Jun-03	15.2	11.6	1.3	7.2	0.5
15	11-Aug-03	14	5.8	2.2	13.6	2.0
16	15-Sep-03	15.0	9.8	1.5	12.8	0.7
17	19-Sep-03	38.0	23.8	1.6	10.4	2.4
18	22-Sep-03	25	8.5	2.8	8.8	2.2
19	14-Oct-03	30.7	19.0	1.6	14.4	10.6
21	2-Nov-03	32.2	49.3	0.7	5.6	2.6

5.2 Runoff Coefficient

The volumetric runoff coefficient was determined by dividing the total runoff volume by the total rainfall volume for each event monitored, that is, the fraction of rainfall volume that was converted to immediate stormwater runoff during an event. Table 5.2 presents the volumetric runoff coefficient values for the construction Catchment -1070.

Table 5.2: Rainfall-runoff coefficient.

Event Date	Total Rainfall (mm)	Observed Runoff (mm)	Runoff Coefficient
14-Sep-02	28.8	6.8	0.24
20-Sep-02	13.3	1.7	0.13
27-Sep-02	18.4	6.9	0.38
2-Oct-02	10.0	2.2	0.22
19-Oct-02	13.0	3.0	0.23
25-Oct-02	9.4	3.0	0.32
2-May-03	6.8	2.9	0.43
5-May-03	17.4	7.0	0.40
11-May-03	17.8	5.1	0.29
20-May-03	10.8	2.9	0.27
4-Jun-03	13.8	5.3	0.38
8-Jun-03	23.6	15.9	0.67
13-Jun-03	15.2	6.9	0.45
11-Aug-03	14	4.9	0.35
15-Sep-03	15.0	6.0	0.40
19-Sep-03	38.0	25.3	0.67
22-Sep-03	25	17.3	0.69
14-Oct-03	30.7	23.2	0.76
2-Nov-03	32.2	19.2	0.60

The volumetric runoff coefficients calculated for the events varied between each of the events. The broad range extends from 0.13 to 0.76. It may be noted that the runoff coefficient gradually increases from the fall 2002 to fall 2003, as per construction activities on Catchment-1070. Figure 5.1 presents the rainfall –runoff relationship in the watershed. The figure shows that surface runoff volume increases with the rainfall volume. It was estimated that on average, storms over 20 mm produced in average 60% of runoff, storms between 10 and 20 mm and less than 10mm produced 38% and 37% runoff, consequently.

Fig. 5.1: Rainfall-runoff relationship.

On average, 25%, 41% and 58% of rainfall appeared as surface runoff during storm events over the three monitoring periods (Fall 2002, May-July 2003 and August-November 2003).

There are many factors that may explain the variability in runoff coefficients among the events. One of the main factors that can influence the rate of runoff during an event is the amount of depression storage and infiltration activity over the catchment area. Because construction sites incur several changes on the catchment's landscape, the amount of depression storage and the rate of infiltration can be altered continuously. Thus, for each event the runoff coefficients were influenced by the state of the site's condition. The inter-event times and antecedent moisture conditions can also influence the runoff coefficient values. For this study it is noted that for the inter-event period less than 1 day, average runoff volume was found to be 29% of total rainfall volume; for the inter-event period from 1 to 2 days runoff volume increased to 34%; and for the period more than 2 dry days average runoff volume was 41%.

5.3 Peak Flow Attenuation

One of the functions of stormwater control ponds is to attenuate peak flow rates (Whipple, 1979; Wu et al., 1996; Fennessey et al., 2001). Table 5.3 shows the volumes and peak discharges for the various storms monitored over the study period. Flow mass balance between the inflow and the outflow is also presented.

Table 5.3: Peak attenuation and flow mass balance summary.

Date	Inflow <u>Peak Flow (l/s)</u> <u>Volume (m³)</u>	Outflow <u>Peak Flow (l/s)</u> <u>Volume (m³)</u>	Difference <u>Peak Flow</u> <u>Volume</u>
14-Sept-02	321 1090.6	12.6 1044.5	-96% -4%
20-Sept-02	120.4 433.1	8.6 422.4	-93% -3%
27-Sept-02	144.9 1413.1	16.3 1505.2	-89% 6%
2-Oct-02	99.4 491.5	72.4 337.9	-27% -45%
19-Oct-02	57.9 629.8	10.4 614.4	-82% -2%
25-Oct-02	48.9 706.6	7.4 737.3	-85% 4%
2-May-03	24.9 522.2	8.4 506.9	-66% -3%
5-May-03	151.4 1306	16.8 1244.2	-89% -5%
11-May-03	100.1 1152	16.6 1090.1	-83% -6%
20-May-03	94.7 844.8	17.9 783.4	-81% -8%
4-Jun-03	49.5 768	10.6 721.9	-79% -6%
8-Jun-03	385.7 2872.3	54.1 4024.3	-86% 29%
15-Sep-03	136.5 967.7	14.4 952.3	-89% -2%
19-Sep-03	243.1 3932.2	16.3 1858.6	-93% -112%
2-Nov-03	85.3 2949.1	7.5 1643.5	-91% -79%

A sample rainfall and observed hydrographs at both the inlets and hydrograph at the outlet are presented in the Figure 5.2 (a-d).

b)

c)

d)

Fig. 5.2 (a-d): Samples observed hydrographs at the inlets and the outlet.

Outflow hydrographs from the pond show that SWM facility significantly shaved the peak flow rates of the inlet hydrograph during storm events.

The maximum peak discharge for the inflow is found to be 385.7 l/s while the maximum peak discharge for the outflow is only 72.4 l/s. An average difference between inflow and outflow peak values is 82%. The outflow volume of 17963.5 m³ is 12% less than inflow volume of 20078.6 m³. Analyzing the event inflow-outflow balance: some minor losses may have occurred through evapo-transpiration and infiltration. The primary losses (events of Oct. 2, 2002 and June 8, Sept.19 and Nov 2, 2003) would be attributed to flow monitoring error.

5.4 Hydraulic Detention Times and Drawdown Times

As mentioned in Chapter 4, the hydraulic detention time is defined as the time difference between inlet and outlet hydrograph centroids, which provides a measure of detention of inlet hydrograph within the facility during the storm event. Detention time is a function of the water volume in the pond and the outflow rate. Typically longer detention times are required for greater pollution removal efficiencies. It is suggested that a detention time of 24 hr or more can achieve a 90% or more removal efficiency of suspended solids (Wanielista & Youseff, 1993). However, according to the same authors, a study using model detention ponds concluded that a minimum detention time of at least 72 hr is needed to remove more than 95% of the suspended solids and 30% to 70% of nutrients and metals. The latter pollutants are typically found in dissolved form. This finding creates doubt for the current design criteria that requires a 24 hr detention time, or a 48 hr detention time that is commonly used in practice (Sabourin, Kimble & Associates Ltd., 2000).

The average hydraulic detention time was found to be 12 hours. This is low in comparison to the expected drawdown time of 48 hours intended by the design of the pond.

The drawdown time for each of the events was estimated by determining the time delay between the maximum water elevation reached during the event runoff to that of minimum elevation (i.e., passing of the storage volume) at the end of the event. The drawdown time

is defined as the time from maximum to minimum active storage volume. Drawdown will vary depending on the active storage volume captured during the event.

Table 5.4 represents the estimated hydraulic detention and drawdown times from the observed inflow and outflows for the Ballymore pond. In this case, the inlet hydrograph to the pond constitutes the combined hydrographs from Catchment- 510 and Catchment - 1070.

An average drawdown time of 46.0 hours was calculated. For some events the estimated drawdown time was very high because of a large storm size, large flow duration, longer duration of the storm and, probably, some contribution from the baseflow. The estimated average drawdown favorably matches with the designed drawdown of 48 hours. Higher drawdown times than designed occur due to prolonged inflow after the end of the storm events (hydrograph recession).

Figure 5.3 represents the sample drawdown time estimation. The combined inlet hydrographs to the pond and pond outflow hydrographs were used for the drawdown time calculation.

Table 5.4: Hydraulic detention and drawdown times.

Event Date	Hydraulic Detention Time (hr)	Drawdown Time (hr)
14-Sep-02	11.4	25.8
20-Sep-02	10.1	51.5
27-Sep-02	13.4	107.8
2-Oct-02	8.1	36.5
19-Oct-02	9.9	39.0
25-Oct-02	15.4	94.3
2-May-03	7.8	24.3
5-May-03	19.9	27.3
11-May-03	5.7	29
20-May-03	16.6	16.0
4-Jun-03	10.6	14.5
8-Jun-03	14.4	21.8
13-Jun-03	11.3	9.0
15-Sep-03	9.8	86.5
19-Sep-03	15.3	101.0
14-Oct-03	19.7	N/A
2-Nov-03	39.5	N/A
Average	11	46

Fig. 5.3: Drawdown time estimation for May 5th 2003 event.

CHAPTER 6

WATER QUALITY ANALYSIS

In this section the results of water quality analysis are presented. Similar to water quantity analysis, water quality analysis is conducted for the events for which complete inflow and outflow information were available. The water quality analysis includes results from both discrete and composite samples.

6.1 Discrete Analysis

Discrete samples were analyzed for suspended solids. For each of the events pollutographs were developed.

6.1.1 Suspended Solids

Suspended solids concentration is a critical parameter in stormwater because many stormwater contaminants are strongly associated with suspended solids (Schueler and Holland, 2000). Therefore, suspended solids concentrations are often used to gauge the general level of water quality improvement in stormwater facilities. As mentioned in Chapter 1, elevated SS concentrations can also adversely affect stream benthos, primary photosynthetic productivity, and fish habitat.

Discrete samples were collected using two different time intervals. As discussed earlier, for the 2002 fall season, 24 bottles were collected every 5 minutes for the first 2 hours of an event. Subsequent to the analysis of the fall events, it was determined the sampling period could be extended to collect every 15 minutes for the first 6 hours of the event. This was to broaden the representation of the pollutant load for an event through water quality samples. From the samples, pollutographs were generated for suspended solids. Table 6.1 represents the summary of observed SS event mean concentrations during the sample period and maximum concentrations during the event at the inlets and the outlet of the Ballymore Pond.

Table 6.1: Concentrations from inlets and outlet of Ballymore Pond.

Event Date	Sample Period (hr)	Rainfall (mm)	Construction Watershed Inlet 1070		Stable Watershed Inlet 510		Outflow from the Pond	
			SS average Concentration (mg/L)	Max. SS Concentration (mg/L)*	SS average Concentration (mg/L)	Max. SS Concentration (mg/L)*	SS average Concentration (mg/L)	Max. SS Concentration (mg/L)*
14-Sep-02	2 hr	28.8	8766	20100	297	450	277	415
20-Sep-02		13.3	16551	34003	13	36	27	59
27-Sep-02		18.4	6004	12200	143	429	75	189
2-Oct-02		10	9935	19100	806	2190	7	10
19-Oct-02		13	1150	3800	151	385	29	67
25-Oct-02		9.4	13801	40700	92	188	17	62
2-May-03	6 hr	6.8	412	979	22	49	30	52
5-May-03		17.4	1040	2350	53	214	36	60
11-May-03		17.8	2266	6110	NA	NA	224	470
20-May-03		10.8	1448	4100	83	252	100	192
4-Jun-03		13.8	1499	3380	258	327	49	202
8-Jun-03		23.6	5030	8560	NA	NA	NR	NR
13-Jun-03		14	NA	NA	136	1320	82	144
2-Aug-03		NA	591	3400	28	89	NA	NA
11-Aug-03		14	1050	4190	55	160	NA	NA
26-Aug-03		20.4	NA	NA	58	120	NA	NA
15-Sep-03		9.8	687	3030	47	100	121	213
22-Sep-03		25	238	538	46	46	28	46
14-Oct-03		30.7	806	2910	36	163	205	325
25-Oct-03		8.2	385	2800	NA	NA	NA	NA
2-Nov-03		32.2	366	533	36	92	88	197
12-Nov-03	6 hr	NA	NA	NA	173	427	670	856
19-Sep-03	12 hr	38	367	1100	47	47	93	259
Average (whole period)			3620		129		120	
Average			9368		250		72	
		Fall 2002						
		May-July 2003	1949		110		87	
		August-November 2003	561		58		201	

NA=Data is not Available; NR=Data is not Reliable

The estimated average SS EMC from the Catchment-1070 during the sampling period was 3620 mg/L, within a range of 238 to 16550 mg/L. This is comparable to the average inflow value of 4498 mg/L from construction catchments described in 'Literature Review' (Chapter 4). The maximum instantaneous SS concentration recorded in this study was 40700 mg/L in October 25, 2002. The estimated average SS EMC from stable Catchment-510 during the sampling period was 129 mg/L within a range of 13 to 806 mg/L. Maximum concentration of suspended solids of 2190 mg/L was measured on October 2, 2002. Average outflow SS event mean concentration was determined as 120 mg/L within a range of 7 to 670 mg/L. The highest SS concentration of 856 mg/L was recorded at the end of the study period, on November 12, 2003.

The first phase of monitoring, which was Fall 2002, is characterized with quite high average SS concentrations for the inflows. The average event mean concentration (AEMC) concentration of SS during Fall 2002 period for the construction catchment, stable catchment and the outlet were: 9368 mg/L, 250 mg/L, and 72 mg/L, respectively.

During monitoring of phase II for the period of May to July 2003, it was observed that SS AEMC decreased for the construction catchment to 1949 mg/L and for the stable catchment to 110 mg/L while increased for the outlet up to 87 mg/L.

A further decrease in SS concentration for inflows was observed during the third phase of monitoring (August-November 2003). Average SS EMC's of 561 mg/L and 58 mg/L were recorded for construction catchment and stable catchments, respectively. However, the outlet exhibited an average increase in outflow of up to 201 mg/L.

The average observed SS EMC for the outlet was gradually increasing during the monitoring period, starting at 72 mg/L for the fall 2002 (2-hours sampling time) and going up to 201 mg/L by November 2003. This concentration is best explained by the fact that at the end of the study period the pond was established for well over a year. So, obviously its SS content was higher compared to the beginning. Most of the suspended particles that didn't settle were very fine. They are of particular interest because these fine particles were pushed first to enter the outlet by the incoming runoff and were collected within the first hours of sampling.

Examples of pollutographs for three events (each one represents a different phase of monitoring) during the study period were generated from observed data and are presented in Figure 6.1(a-c).

Suspended Solids Concentrations for October 2, 2002

Suspended Solids Concentrations for May 20, 2003

(a), (b)

(c)

Fig. 6.1 (a-c): Suspended solids concentrations.

The average SS EMC from Inlet 1070 on October 2nd reached almost 10,000 mg/L, while Inlet 510 showed an average of 806 mg/L in the first two hours of the event. At the same time the outlet produced a significantly reduced concentration of exiting the pond suspended solids (7 mg/L). Although both events received similar rainfall volumes (approximately 10mm), the outlet SS concentration was significantly higher for May 20th (100 mg/L) compared to October 2nd event (7 mg/L). This shows the variation of SS effluent concentration between the events.

SS concentrations in Fall 2002 were obtained during 2 hours of sampling. It is possible that a limiting sampling time alters results. Actual average inflow concentration would likely be lower if the sampling time was lengthened.

It was observed that the average SS EMC for construction catchment decreased by 79% from phase I to phase II and by 72% from phase II to phase III, resulting in an average decrease by 94% from phase I to phase III. At the same time a 77% decrease in concentration was observed for the stable catchment (C-510).

Figure 6.2 shows the change in concentration of suspended solids during the study period.

Fig. 6.2: Observed average EMC of SS.

On May 20th, Inlet 1070 average suspended solid concentrations decreased down to half of that experienced on October 2nd (approximately to 5000 mg/L). This may be attributed to the progression in construction activities where additional lots were sodded during the spring sampling period. However, the outlet experienced higher suspended solids concentrations exiting the pond, indicating that by the end of Summer 2003 concentration of suspended solids of 58 mg/L observed in the inflow from Catchment -510 at the end of study period (August-November 2003). It can be explained that although catchment 510 is stable it is still a newly-developed area, which was undergoing personal home construction, such as fences, gardening, patios etc., during first two monitoring phases (Fall 2002-Summer 2003).

Table 6.2 represents the estimated inlet and outlet SS load and instantaneous removal efficiencies for the monitored events. The average instantaneous removal efficiency of SS for the observed events was estimated as 94%. The removal efficiency based on the estimation of loads for the entire event is presented in the later section.

Table 6.2: Observed SS loads from inlets and outlet and removal efficiency.

Event Date	Rainfall (mm)	SS Load (kg)		SS Load from Outlet	Load based Removal Efficiency
		Construction Catchment (Inlet 1070)	Stable Catchment (Inlet 510)		
14-Sep-02	28.8	1307	10	12.7	99%
20-Sep-02	13.3	414	1	1.5	100%
27-Sep-02	18.4	953	42	3.6	100%
2-Oct-02	10	1717	499	0.5	100%
19-Oct-02	13	74	11	2	98%
25-Oct-02	9.4	2190	13	0.5	100%
2-May-03	6.8	88	3	2.5	97%
5-May-03	17.4	266	5	4.3	98%
11-May-03	17.8	1205	NA	596.3	NA
20-May-03	10.8	557	32	20.4	97%
4-Jun-03	13.8	318	5	1.7	99%
13-Jun-03	14	NA	46	14	NA
2-Aug-03	NA	265	3.1	NA	NA
11-Aug-03	14	609	13.4	NA	NA
26-Aug-03	20.4	NA	7.8	NA	NA
15-Sep-03	9.8	433	7	31	93%
22-Sep-03	25	387	NA	6.2	NA
14-Oct-03	30.7	832	10	26	97%
25-Oct-03	8.2	124	NA	NA	NA
2-Nov-03	32.2	118	4.6	11	91%
12-Nov-03	NA	NA	29.5	70.7	NA
19-Sep-03	38	745	1.5	22.1	97%
Average					94%
Total		12602	744	829	

According to the load-based removal efficiencies (LE) shown in Table 6.2, the pond is performing very well. These removal efficiencies values are higher than results obtained from other studies, such as: 78% of removal efficiency in Colorado pond, 93% and 67% - in North Carolina and 93% in stormwater Ponds in Central Texas (Schueler and Holland, 2002), 86% removal efficiency in the Canadian Heritage Park Pond (MOE SWAMP Report, 2002), 78% - Canadian Harding Park Wet ED Pond (TRCA, 1996).

However, percentage removal efficiencies are not necessarily the most reliable method for determining the pond's performance. Ultimately, the determining factor is the outflow

concentrations. The EMC values presented in Table 6.1 are suggesting that the pond is unable to reduce suspended solids concentrations to safe levels under certain conditions.

6.2 Composite Analysis

The composite samples are a mixture of each discrete sample. For example, of the 24 bottles collected, a portion from each was extracted into one composite bottle. This composite bottle was then divided into several bottles for the analysis of water quality parameters outlined in Table 4.3. It should be noted that all samples analyzed for PAHs, herbicides and pesticides produced a "NMR" ("no measurable response") according to the MOE laboratory services. Because these parameters were not detected in large enough quantities in the samples, these results are not included.

The composite water quality data was also partitioned into 3 periods, or phases, as construction progressed: Fall 2002, May-July 2003, and August-November 2003. Summary water quality tables for each of the events for the inflow and outflow are presented in Appendix F.

Fall 2002 results show that during that time the pond was able to significantly reduce the mass load of pollutants entering the facility. For the Fall 2002 season, the average removal efficiency for the various contaminants monitored ranged from -180% to 97.5%. The highest removal efficiency achieved was for suspended solids (97.5%), followed by the total phosphorus (93.7%) and total solids (91.3%). Negative value of -180% is obtained for cadmium.

The average removal efficiency of the pond in May-July 2003 period ranged from -92.2% to 86.7%. The highest removal efficiency observed during this period was also for SS (86.7%), followed by total phosphorus (85.1%) and COD (80.3%). Beryllium exhibited the maximum negative removal efficiency of -92.2%.

The third sampling period of August-November 2003 is characterized by a noticeable decrease in the average removal efficiencies, practically for all parameters. Suspended solids and total phosphorus experience the higher removal efficiencies (72.4 and 70.2%)

compare to the metals. Table 6.3 and Figures 6.3-6.5 represent the average removal efficiencies for different parameters throughout the study period.

Table 6.3: Total performance of the Ballymore Pond throughout the study period.

Parameter	Performance (%)			
	Fall 2002	May-July 2003	August-November 2003	Whole Study Period
Chemical Oxygen Demand	55.1	80.3	61.4	65.6
Suspended Solids	97.5	86.7	72.4	85.5
Dissolved Solids	5.3	-8.5	3.9	0.2
Total Solids	91.3	51.2	53.3	65.3
Total Phosphorus	93.7	85.1	70.2	83.0
TKN	76.2	58.0	46.6	60.3
Aluminum	1.7	67.6	41.9	37.1
Barium	80.5	59.0	39.2	59.6
Beryllium	-17.5	-92.2	-52.2	-54.0
Calcium	80.4	62.4	46.4	63.1
Cadmium	-180.1	-71.5	95.3	-52.1
Cobalt	37.4	118.7	11.7	55.9
Chromium	5.7	37.6	46.9	30.1
Copper	26.4	29.3	-135.4	-26.5
Iron	-6.2	41.2	30.8	21.9
Magnesium	47.0	18.8	21.3	29.0
Manganese	81.3	72.5	58.1	70.7
Nickel	14.0	52.9	35.0	34.0
Lead	31.0	55.3	-203.1	-38.9
Strontium	57.4	30.9	13.9	34.1
Titanium	-143.8	18.9	4.1	-40.3
Vanadium	-47.0	51.1	24.8	9.7
Zinc	22.8	73.8	56.6	51.1

Fig. 6.3: Total load –based removal efficiencies for the Fall 2002 period.

Fig. 6.4: Total load –based removal efficiencies for the May-July 2003 period.

Fig. 6.5: Total load –based removal efficiencies for the August-November 2003 period.

Negative removal efficiencies suggest that there is an internal source within the pond (i.e. bottom material), or from the eroded banks along the pond's edge. Another possible explanation for the negative removal efficiencies includes the gradual accumulation of pollutants in the basin sediments before they are driven out in a storm. For example, residents that received new sod on their lots were encouraged to water their lawns frequently. This may have produced enough runoff to enter the pond, while carrying some pollutants from the site. These pollutants can gradually build up so that during the next event a higher concentration may exit the pond than what initially entered during the event. Also, runoff acidity may melt the metals contributing to their concentration increase in the outflow.

As with the discrete analysis, the removal efficiencies for the composite results are not the determining factor of the pond's performance. The actual concentrations of the pollutants exiting the pond are considered to be the ultimate indication of the pond's ability to protect

downstream habitat. The results of this study are indicating that high removal efficiencies do not determine safe levels of pollutant concentration.

6.2.1 General Water Chemistry

The general water chemistry was analyzed and includes the following: chemical oxygen demand (COD), suspended solids (SS), total solids, dissolved solids, conductivity, pH, alkalinity, turbidity, dissolved organic carbon, dissolved inorganic carbon, chloride, and silicon.

The average events mean concentrations for general physical and chemical parameters analyzed in this study are presented in Table 6.4. Provincial Water Quality Objectives are also included in the table for comparison reason.

Table 6.4: Average Events Mean Concentrations (AEMC's) and Provincial Water Quality Objectives (PWQO's) for general chemistry.

Parameter	Average EMC									Average EMC (whole period)			PWQO's
	Fall 2002			May-July 2003			Aug.-Nov. 2003						
	Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet	
COD (mg/L)	66.6	35.6	23	69.5	50.0	24	100	41	77	78.8	42	41	-
Suspended Solids (mg/L)	4412	163	62	1017	48.1	106	377	85	285	1935	99	151	-
Total Solids (mg/L)	4696	381	293	1282	212	483	577	241	444	2185	278	407	-
Dissolved Solids (mg/L)	284	218	231	267	164	377	193	149	159	248	177	256	-
Conductivity (uS/cm)	436	336	355	397	254	611	299	241	245	377	277	404	-
pH	8.48	7.98	8.05	8.0	7.97	8.16	8.0	8.0	8.1	8.2	8	8	6.5 to 8.5
Alkalinity (mg/L CaCO ₃)	44.7	57.0	45	72.7	72.0	60	88	71	83	68.5	67	63	-
Turbidity (FTU)	1547	207	81	1454	329	166	504	133	605	1167	223	284	-
Carbon (DOC) (mg/L)	5.38	8.3	6	5.1	3.5	5	12.5	7.8	8	7.7	7	6	-
Carbon (DIC) (mg/L)	9.90	13.3	8	12.5	10.0	18	20.5	16	19	14.3	13	15	-
Cl (mg/L)	39.0	26.2	29	24.6	17.2	113	14.9	13	13	26.2	19	52	-
Silicon (mg/L)	5.72	3.1	4	3.1	1.5	2	2.3	1.8	1	3.7	2	2	-

6.2.1.1 Suspended Solids

As mentioned in earlier chapters, suspended solids (SS) concentration is a critical parameter in stormwater. As expected, with construction progressing towards the end, inflow SS concentration from the construction catchment experienced a significant decrease throughout the study, from phase I (Fall 2002) to phase III (November 2003).

The average inflow SS concentration for Fall 2002 was 4412 mg/L within a range from 23 to 8680 mg/L. It decreased down to 1017 mg/L in the May-July 2003 sampling period (ranging from 348 to 2300 mg/L), and experienced further decrease down to 377 mg/L in the last season. The average SS EMC from the stable catchment decreased from 163 mg/L in the Fall 2002 to 48 mg/L in May-July, and increased up to 85 mg/L in the last sampling phase. It averaged 99 mg/L for the whole study period. However, the outlet concentration of suspended solids shows significant increase from Fall 2002 to spring 2003 (from 62 mg/L to 106 mg/L) and further increase up to 285 mg/L by the end of study. Though removal efficiency for SS was quite high throughout the sampling periods (varied from 97.5% at the beginning to 72.5% by the end of study), effluent average SS concentration of 151 mg/L is very high.

One of the earliest works on suspended sediments effects on fish was conducted by a group of European scientists who attempted to develop criteria for suspended sediment concentration in relation to fisheries quality (MOE, SWAMP, 2002). The criteria for continuous suspended load were as follows: less than 25 mg/L: not harmful; 25 to 80 mg/L: fish yield somewhat reduced; 80-400 mg/L: good fisheries unlikely; and greater than 400 mg/L: poor fisheries. Thus, the average effluent suspended sediment load at Ballymore Pond would unlikely provide good fisheries. The average SS composite effluent value of 151 mg/L is close to the average SS EMC of 120 mg/L obtained by the analysis of discrete samples.

It should be considered that these values are obtained during a time-limited sampling period of 2 to 6 hours. Further investigation on concentration of suspended solids described in the following chapter using a modelling approach should give an answer.

6.2.1.2 pH and Alkalinity

The mean inflow pH for the Fall 2002 period was 8.2; for May-July 2003 it was 8.1, and for August-November 8.0. Outlet pH varied from 8.1 to 8.2 throughout the study period. There was little variability in pH levels among storm events (Table 6.5). All pH values observed at the site lay within the 6.5 to 8.5 range recommended by the Ontario Ministry of Environment and Energy Provincial Water Quality Objectives (MOE, SWAMP, 2002).

Alkalinity, reported as the concentration of calcium carbonate (CaCO_3), displayed some variability among events, ranging from 33 to 90 mg/L at the inlets during the Fall 2002 period, from 55 to 102 mg/L at the May-July 2003 period, and from 55 to 107 mg/L at the last monitoring phase. Outlet alkalinity varied from a minimum value of 34 mg/L in the Fall of 2002 to 106 mg/L in the Fall of 2003, showing a graduate increase from phase to phase. The average EMC during the whole study period were very close: 67 mg/L at the inlets and 62 mg/L at the outlet.

6.2.1.3 Turbidity

Turbidity of stormwater coming from the construction catchment is found to be gradually decreasing from 1547 NTU (Fall 2002) to 1453 (May-July 2003), and down to 503 NTU in the last sampling period. The average turbidity value from inlet 1070 is 1168 NTU which is significantly higher than turbidity levels of 400-600 NTU obtained in Maryland construction site (Schueler and Lugbill, 1990). Inflow turbidity values from stable catchment averaged 223 NTU. A much higher turbidity level for the construction catchment is a result of progressing construction activities.

Turbidity levels for the outlet experience a significant increase throughout the study period: 81 NTU in the Fall 2002 period changed to 166 NTU in the May-July 2003 and to 605 NTU in the last sampling period indicating that fine particles are accumulated in the pond throughout the study period. These outflow values are comparable to turbidity levels found by Przepiora et al. (1997): turbidity of water discharged from sedimentation basins at two construction sites during a 1-year period ranged from 120 to 3200 NTU, which corresponded to SS concentrations of 90 to 2800 mg/L. According to Canadian Water Quality Guidelines, turbidity of receiving waters with background between 8 and 80 NTU

should not exceed background levels by more than 8 NTU. When background exceeds 80 NTU, turbidity should not be increased by more than 10% of the measured background level at any one time (Canadian Water Quality Guidelines, 1988). Obviously, concerning turbidity levels, the performance of Ballymore pond may be rated as very poor.

In addition, a strong linear relationship between EMC of SS exiting the pond and turbidity levels was obtained in the study. As shown in Figure 6.6, outflow turbidity levels in Ballymore pond construction site can be predicted by the equation:

$$\text{Turbidity (NTU's)} = 2.46(\text{SS}) - 73.72, \quad (6.1)$$

where concentration of SS is measured in units of mg/L. This linear regression yields correlation coefficient (R^2) of 0.92. Consequently, given the strength of this relationship, turbidity can be readily predicted from the available SS event mean concentration.

Fig. 6.6: Outflow turbidity vs. EMC.

6.2.2 Nutrients

During all periods of sampling, all nitrogen species showed positive removal on a load basis. Average EMC's and comparison of measured concentrations to PWQO's are shown in Table 6.5.

Table 6.5: Average Events Mean Concentrations (AEMC's) and Provincial Water Quality Objectives (PWQO's) for nutrients during the study period.

Parameter	Average EMC									Average EMC (whole period)			PWQO
	Fall 2002			May-July 2003			Aug.-Nov. 2003						
	Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet	
Nitrogen (NH3+NH4) (mg/L)	0.04	0.26	0.05	0.18	0.23	0.12	0.22	0.19	0.19	0.15	0.23	0.12	-
Nitrogen (NO2) (mg/L)	0.09	0.07	0.05	0.05	0.05	0.04	0.08	0.05	0.04	0.07	0.06	0.05	-
Nitrogen (NO2+NO3) (mg/L)	0.68	0.80	0.41	0.90	0.77	0.75	0.89	0.75	0.42	0.83	0.77	0.53	-
Phosphate (mg/L)	0.04	0.13	0.02	0.07	0.08	0.01	0.20	0.12	0.10	0.10	0.11	0.04	-
Total Phosporus (mg/L)	4.22	0.33	0.12	1.24	0.33	0.17	0.60	0.25	0.43	2.02	0.30	0.24	0.03
TKN (mg/L)	4.03	1.73	0.81	2.73	2.18	1.45	2.57	1.41	4.32	3.11	1.77	2.19	-

Throughout the study period the average Total Kjeldahl Nitrogen removal efficiency was 60% ranging from 76% to 47%.

Total phosphorus (TP) removal efficiency was observed as 94%, 85% and 70% within the whole sampling time, averaging 83%, which are significantly higher than reported rates of 51% (Urban BMP's, Washington and MOE, 1991) and 49-60% (Saburin and Kimble, 2000). However, the average TP influent concentration from construction catchment varied from 4.22 mg/L in the Fall 2002 to 2.73 mg/L in May-July 2003, and to 2.57 mg/L in the August-November 2003 period, which is very high compared to the acceptable value of 0.03 mg/L. Average inflow TP concentration from the stable catchment is significantly lower: It decreased from 0.33 mg/L in the first two sampling periods to 0.25 mg/L in the Fall 2003.

The outlet average TP EMC is 0.24 mg/L, which is significantly higher than the recommended maximum TP concentration of 0.03 mg/L intended to avoid excessive plant growth in the pond (MOE, SWAMP, 2002).

6.2.3 Metals

Over half of the trace metals carried in runoff waters are attached to sediments (Fifield, 2001). The main sources of metals in runoff from construction sites include galvanized metals, paint and preserved wood. Also, atmospheric fallout and rooftops runoff make an important contribution to the metal's content. Table 6.6 outlines the study's results compared to PWQO's.

Table 6.6: Average Events Mean Concentrations (AEMC's) and Provincial Water Quality Objectives (PWQO's) for metals.

Parameter	Average EMC									Average EMC (whole period)			PWQO's
	Fall 2002			May-July 2003			Aug.-Nov. 2003						
	Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet	
Al (ug/L)	944	1663	873	1866	952	611	1579	470	1082	1463	1028	855	-
Ba (ug/L)	111	33.7	18.9	84.8	29.7	27.0	44.5	23.4	41.4	80.0	28.9	29.1	-
Be (ug/L)	0.3	0.1	0.1	0.3	0.1	0.2	0.1	0.0	0.2	0.2	0.1	0.1	1100
Cd (ug/L)	0.3	0.1	0.2	0.3	0.3	0.3	0.3	2.3	51.0	0.3	0.9	17.1	0.5
Ca (mg/L)	344	62.5	50.9	149	41.8	44.1	68.1	28.8	50.2	187	44.4	48.4	-
Chromium (ug/L)	5.4	5.9	4.7	35.2	20.9	3.4	2.3	1.5	1.3	14.3	9.4	3.1	1
Co (ug/L)	1.8	1.9	0.9	3.0	1.4	0.6	1.7	0.8	1.8	2.1	1.4	1.1	0.9
Cu (ug/L)	4.2	22.7	7.7	8.4	13.6	6.9	8.0	8.1	5.7	6.9	14.8	6.7	5
Fe (ug/L)	987	1801	921	1211	912	584	1346	403	915	1181	1039	807	300
Pb (ug/L)	2.6	4.7	1.8	5.5	3.6	2.2	5.5	-0.8	0.3	4.5	2.5	1.4	5
Mg (ug/L)	10.3	6.0	74.0	6.5	2.7	5.0	5.0	2.7	3.9	7.3	3.8	27.6	-
Mn (ug/L)	537	132	66.0	374	127	69.6	1734	50.0	147	361	103	94.3	-
Mo (ug/L)	2.8	1.1	1.1	0.3			-0.2	35.4		0.9	18.3	1.1	-
Ni (ug/L)	3.6	4.0	2.3	35.2	2.2	1.6	3.2	1.3	1.9	14.0	2.5	1.9	25
Sr (ug/L)	740	285	265	416	146	286	216	157	180	457	196	243	-
Ti (ug/L)	7.3	10.3	9.1	6.3	7.8	5.8	13.5	8.2	11.7	9.0	8.8	8.9	-
V (ug/L)	5.0	7.7	6.3	5.6	4.4	2.9	4.8	2.6	3.6	5.2	4.9	4.3	6
Zn (ug/L)	10.6	21.1	8.2	23.7	24.0	9.7	20.4	11.0	12.0	18.3	18.7	10.0	20

The analysis indicates that Fall 2002 removal efficiencies for metals are ranging from -180% for cadmium to 81% for manganese. Removal efficiencies in May-July 2003 period ranged from -92 for beryllium to 118% for cobalt. Fall 2003 efficiencies ranged within -203% for lead to 95% for cadmium.

Stormwater metals with average removal efficiencies above 50% in the Fall of 2002 include barium, calcium and strontium; in May-July 2003: aluminum, barium, calcium, cobalt, manganese, nickel, lead, vanadium, and zinc. This indicates that pond performed better in a second sampling period.

In the last period of August-November 2003 metals such as cadmium, manganese and zinc experienced removal efficiency higher than 50%.

During all three monitoring periods, the average effluent concentration of chromium, copper and iron exceeded Ontario's PWQO's. Cobalt's effluent concentration exceeded provincial objectives only during August-November 2003 period. Trace level amounts of beryllium and nickel were found in both inlets and outlet samples, all at concentrations well below their respective PWQO's.

6.3 Particle Size Distribution

The performance of a stormwater management facility is controlled, among other factors, by the size of incoming sediment. The distribution may vary from storm to storm. The important criterion in the design and sizing of ponds is the selection of the design particle size that would be equal to or greater than the particles to be removed (Greb, 1997). The resulting performance of a pond will reflect how well the chosen size class matches actual conditions.

The particle size distribution (PSD) of stormwater is important for several reasons. First, the relationship between suspended solids removal and the removal of other constituents is greatly influenced by suspended particle size. Clay particles, in particular, have a large capacity to carry nutrients and contaminants due to their high cation exchange capacity, and large surface area to weight ratio. Second, the change in size distribution observed between the inlet and outlet is an important indicator of size selective particle removal either by settling, flocculation or filtration. Third, the outlet particle size distribution has important implications for effluent impacts to receiving waters.

In this study, particle size distributions were determined from the composite water quality samples. Particle size analyses were performed on both inlets and the outlet suspended solids material. All particle size measurements were performed at the MOE Lab. Cumulative distributions and classes summarized particle-size data. Categories corresponded to size classes traditionally designated as sand (62 to 2000 microns), silt (4 to 62 microns), and clay (smaller than 4 microns) (Chow, 1964; Greb, 1997).

A total of 57 field samples were collected from the study site, including 41 inflow samples from the both inlets, and 16 outflow samples. All cumulative distribution curves were summarized by averaging the "percent greater than" values for each measured particle size. 21 size categories ranging from 0.43 microns to 999 microns in diameter were analyzed. The D_{10} values represent 10% of the distribution that is greater than this value. The D_{50} value is representative of 50% of the particle size distribution.

Table 6.7 shows the D_{10} and D_{50} values for the both inlets and outlet for each event and average values reflecting 3 monitoring stages (Fall 2002, May-July 2003 and August-November 2003).

Table 6.7: D_{10} and D_{50} particle size.

	Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet
Event	D_{10}			D_{50}		

14-Sep-02	20.99	41.50	14.42	7.07	3.15	2.23
20-Sep-02	-	19.28	-	-	3.45	-
27-Sep-02	13.47	15.68	19.30	2.57	2.86	2.41
02-Oct-02	20.10	-	-	3.60	-	-
19-Oct-02	39.90	18.50	-	5.60	2.32	-
25-Oct-02	-	-	-	-	-	-
Average:	23.61	23.74	16.86	4.71	2.95	2.32
02-May-03	10.72	24.80	6.09	2.17	4.26	1.00
05-May-03	14.21	47.95	16.94	2.59	6.34	2.17
11-May-03	14.79	-	7.25	2.98	-	2.16
12-May-03	16.84	31.80	14.14	2.39	2.98	1.99
20-May-03	19.70	76.44	7.41	3.35	8.86	2.43
05-Jun-03	26.00	-	2.37	2.97	-	7.84
08-Jun-03	94.17	-	12.58	6.61	-	2.99
21-Jul-03	13.82	11.15	-	2.60	2.75	-
Average:	26.28	38.43	9.54	3.21	5.04	2.94
02-Aug-03	20.64	-	-	3.17	-	-
09-Aug-03	33.37	-	-	7.01	-	-
11-Aug-03	27.20	34.82	-	3.13	4.69	-
26-Aug-03	26.99	50.69	-	4.73	6.93	-
15-Sep-03	42.65	18.59	15.87	5.42	3.18	4.13
19-Sep-03	32.82	-	24.01	4.97	-	5.09
22-Sep-03	42.68	71.12	27.24	6.37	11.97	5.27
27-Sep-03	15.79		18.79	3.10	-	4.07
14-Oct-03	27.87	19.90	23.45	2.79	3.35	4.93
18-Oct-03	52.95	-	-	4.97	-	-
25-Oct-03	14.59	13.25	-	3.77	1.86	-
02-Nov-03	18.83	49.07	14.71	2.69	4.47	2.87
12-Nov-03	12.83	-	12.53	3.27	-	3.53
Average:	28.40	36.78	19.51	4.26	5.21	4.27
Total Average	26.96	34.03	14.82	4.00	4.59	3.44

The particle size distribution of incoming sediments was composed of extremely fine-grained, primarily consisting of fine silts, clays, and colloidal materials particles. 90% of particles entering the pond from both inlets are finer than 30 microns. 90% of particles exiting the pond are smaller than 15 microns in diameter.

Figures 6.7-6.9 show the average cumulative particle size distribution for three consequent periods of the monitoring. PSD's for each of the events monitored are included in Appendix G. The median particle size (D_{50}) of the average PSD is found to be approximately 4.0, 4.6, and 3.4 μm at the inlet 1070, inlet 510 and the outlet, respectively.

Fig. 6.7: Average cumulative particle size distribution for Fall 2002.

Fig. 6.8: Average cumulative particle size distribution for May-July 2003.

Fig 6.9: Average cumulative particle size distribution for August-November 2003.

Tables 6.8 and 6.9 summarize the particle class, masses, and performances as regrouped into very fine to coarse sand, silt and clay groups.

Table 6.8: Particle size class and distribution.

Particle Class	Size Range (microns)	Fall 2002			May-July 2003			August-November 2003		
		%			%			%		
		Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet
Fine to Coarse Sand	62-999	4.3	4.3	4.1	5.7	6.4	0.2	4.9	6.1	4.1
	average for the whole period	5.0	5.6	2.8						
Silt	4-62	51.0	49.4	48.3	44.4	56.3	11.94	54.6	55.2	61.8
	average for the whole period	50.0	53.6	40.7						
Clay	< 4	44.7	46.3	47.6	49.9	37.3	87.9	40.5	38.7	34.1
	average for the whole period	45	40.8	56.5						

Table 6.9: Average particle size, mass proportion and performance.

Particle Class	Size Range (microns)	Particle Size			Mass			Removal Efficiency (%)
		%			kg			
		Inlet 1070	Inlet 510	Outlet	Inlet 1070	Inlet 510	Outlet	
Fine to Coarse Sand	62-999	5.0	5.6	2.8	497.6	36.1	3.9	99.3
Silt	4-62	50	53.6	40.7	5006	345.2	56.9	98.9
Clay	< 4	45	40.8	56.5	4505	262.8	79	98.3

The clay fraction (smaller than 4 μm) contributed 40.8-45% of the weight to the suspended solids material in the influent. The silt-size fraction contributed more (50.0-53.6%), with the remaining sand-size fraction contributing only 5.0-5.6%.

Effluent characteristics in terms of PSD are: content of clay fraction is 56.5%, silt and sand-size are 40.7% and 2.8, respectively.

Based on obtained results, this pond performs very well in removing all three particle classes: removal efficiency for the clay, silt and sand particles are 98.3%, 98.9%, and 99.3%, respectively.

According to soil classification based on various combinations of sand, silt and clay given by Davis and Bennett (1949), sediments incoming from Catchment-1070 and Catchment-510 belong to silty clay soil class while outflow sediments represent clays class.

Particle size distributions indicate that fine sediments dominate the sediment loads entering and leaving the pond.

CHAPTER 7

SWMM APPLICATION

This chapter covers the set up and calibration of the PC SWMM model. RUNOFF and STORAGE/TREATMENT blocks input parameters and calibration procedures are discussed in depth.

7.1 Modelling Objectives and Methodology

Modelling objectives included the assessment of: (i) the event mean concentration and load of suspended solids for the monitored individual events, (ii) the long-term sediment generation from the construction watershed; and (iii) the long-term performance of the construction sediment control pond.

As mentioned in Chapter 4, the model used in the study is PCSWMM (US EPA SWMM version 4.4.), which is a parametric, deterministic simulation model that uses rainfall data to simulate runoff and pollutant load from a user defined watershed condition. While it is impossible to develop the construction watershed model and pond simulation model that will simulate observed conditions with 100% accuracy, the models with reasonable accuracy were developed for the assessment of construction site and pond performance. As a result, the model outputs are viewed as a guiding estimate of field conditions.

To simulate the typical construction watershed condition, a representative construction watershed model was developed for Catchment-1070. To account for the inflow from the stable catchment (Catchment-510), the area of the stable catchment was added to the construction catchment area, thus creating the Combined simulated catchment.

The construction activities make this watershed very dynamic in terms of hydrology. The standard hydrologic calibration procedure typically used in stable developed catchments was not applicable in this case because of variable watershed conditions over the period. Therefore the following methodology was adopted to develop the construction watershed model:

1. The entire monitoring period was divided into three separate periods from which three individual construction watershed models were created. The three periods include: (i) September to October 2002, (ii) May to July 2003, and (iii) August to November 2003. It is assumed that during these periods the watershed conditions, particularly imperviousness and corresponding soil exposure due to construction activities are reasonably constant.
2. The construction model was calibrated with available observed runoff quantity data (i.e., runoff volume, and peak flow) for each of the events. The hydrologic model parameter values that produce matching runoff hydrographs were identified.
3. The calibrated runoff quantity models for each of the periods were further used for the calibration of runoff quality using the SS concentration data (i.e., SS pollutographs). Since observed SS data is partial (i.e., first 2 to 6 hrs), the calibration procedure was limited to matching portions of observed and simulated pollutographs. In other words, if the first 2 to 6 hours of simulated pollutograph was reasonably matched with observed data, the model was selected for the generation of the entire pollutographs of the event.
4. A continuous simulation model for the construction watershed was developed to assess the long-term sediment generation conditions.

7.2 SWMM Data Input

RUNOFF block

The RUNOFF block input file is comprised of consequent data lines from A to K that accommodate all input parameters for this block. Input data is arranged in the following manner: after the titles contained in A line, the control data are listed in lines B1 through B3, the C lines hold the data concerning the snow input, the E lines contain the rainfall data, and the F lines are used for the evaporation data. The channel and control structure data are listed in G lines; H lines provide the subcatchment data for the quantity simulation. The subcatchment snow data are listed on lines I. In this study we neglect snow input because monitoring did not take place in winter.

Rainfall data are the single most important group of hydrologic data required by SWMM. In SWMM, Line D1 is the first rainfall control line. It defines the precipitation input option.

Data group E1 (rainfall control line) defines the type of precipitation (KTYPE), precipitation values or pairs per line (KINC), precipitation print control (KPRINT), variable precipitation intervals (KTHIS), time units (KTIME), precipitation input type (KPREP), number of precipitation values (NHISTO), and the default rainfall interval (THISTO). Line E3 is used to input precipitation data. Input is a function of the parameter KTYPE on data group E1. For this study rainfall data have been entered as the starting time in minutes for the interval and the interval precipitation value.

The quality data fit into four lines labeled J1 to J4. Line J1 identifies the number of constituents to be modeled and the land use types, line J2 sets up the dust and dirt characteristics, line J3 sets up the constituent build up equations and line J4 allows a fraction of one constituent to be added to another. The K line provides the erosion data and the L lines provide subcatchment surface quality data. The remaining M lines are concerned with print controls.

Table 7.1 lists some of the run, rainfall and quality controls that were used in the RUNOFF block of the model. Details on the other input parameters will be discussed in later sections.

Table 7.1: PCSWMM RUNOFF block control input parameters.

Run Control			Rainfall Control			Quality Control		
Parameter	Description	Value	Parameter	Description	Value	Parameter	Description	Value
B1			D1			JJ		
Metric	Metric input-output	1	ROPT	Precipitation input option	1	IMUL	Trigger multiple land uses	0
ISNOW	Snowmelt parameter	0	E1			J1		
NRGAG	Number of hyetographs	1	KTYPE	Type of precipitation input	2	NQS	Number of quality constituents	1
INFILM	Choice of infiltration equation	0	KINC	Number of precipitation values	0	JLAND	Number of land uses	1
KWALTY	Quality (erosion) simulated	1	KPRINT	Print control	0	IROS	Erosion simulation parameter	1
IVAP	Evaporation parameter	0	KTHIS	Variable THISTO option	0	IROSAD	Option to add erosion to constituent	1
B3			KTIME	Precipitation time units	0	DRYDAY	Number of dry days prior to storm	varied
WET	Wet time step	300	KPREP	Precipitation unit type	1	CBVOL	Av. catchbasin storage volume	0
WETDRY	Transition between wet and dry	300	NHISTO	Number of data points for hyetograph	varied	DRYBSN	Dry days required to recharge	0
DRY	Dry time step	300	THISTO	Time interval between values	varied	RAINIT	Highest av. 30-min rainfall intensity	varied
LUNIT	Units of LONG	4	TZRAIN	Initial time of precipitation input	varied			

STORAGE/TREATMENT Block

All control input data fits into lines B1 and C1-C2. These lines define the starting and ending date and time and print control. Monthly evaporation rates are required to correct for evaporation from detention units. Line D1 provides evaporation data.

General information is listed in lines F1-F2. Line F1 includes a name for the treatment facility, line F2 contains a unit's description. Lines G1-G4 provide pollutant removal information such as removal equation type and removal coefficients.

All S/T block control data is summarized in table 7.2; details on other input parameters will be discussed in later section.

Table 7.2: Storage/Treatment block control input parameters.

Parameter	Description	Value
B1		
NOTAPE	Input Data Source	0; input from external input file
JNS	External element number from the external	200
NDT	Total number of simulation time steps	288
DS	Size of time step	900
NU	Number of storage/treatment units	1
NP	Number of pollutants routed	1
COST	Cost calculations performed?	0; no
METRIC	Metric input-output	1; use metric unit

7.3 SWMM Water Quantity

7.3.1 RUNOFF Block Parameter Development and Calibration

Surface runoff is computed in SWMM for any rainfall hyetograph, considering land use type and topography, and accounting for antecedent moisture conditions, infiltration losses in pervious areas, surface detention, overland flow, channel/pipe flow and constituents carried by runoff into inlets. There are several key parameters used in the PCSWMM RUNOFF quantity input files that should be discussed as to how they were chosen for this

study. These include hydrologic parameters such as *infiltration* and *subcatchment characteristics*.

Infiltration

INFILM – This parameter recognizes the type of infiltration simulation that will be used in the runoff model. SWMM allows two options for infiltration calculation of pervious areas. Horton's and Green-Ampt techniques. Horton's technique was employed in this study. Soil infiltration is considered a function of time:

$$f_p = f_{\infty} + (f_0 - f_{\infty}) e^{-\alpha t} , \quad (7.1)$$

where f_p is the infiltration capacity into soil, mm/sec; f_{∞} is the minimum or ultimate value of f_p (WLMIN) in mm/sec; f_0 is the maximum or initial value of f_p (WLMAX), mm/sec; (t) is the time from the beginning of the storm in seconds; and (α) is the decay coefficient (DECAY) in sec^{-1} . The equation was originally developed to depict the reduction of a watershed's infiltration capacity in the presence of surface moisture. The Horton equation was chosen for several reasons. The first reason is because it is the most well known and accepted of several infiltration equations (Huber and Dickinson, 1992; James and James, 2000; Viessman et al., 1993; Elliot and Ward, 1995). The second reason was because PCSWMM used an integrated form of the equation that compensates for the reduced loss of soil infiltration capacity when a light rainfall occurs (Nix, 1994).

Although the Horton infiltration equation is probably the best-known of the several infiltration equations available, there is not enough published data available to help to select values of parameters f_0 and f_{∞} for a particular application (James and James, 2000). Since the values of f_0 , f_{∞} and α depend on soil, vegetation, and initial moisture content, ideally these parameters should be estimated using results from field infiltrometer tests for a number of sites of the watershed and for a number of antecedent wetness conditions. At this moment of the research field data to find estimates of f_0 , f_{∞} and α for studied subcatchment were not available, thus choice of parameters f_0 and f_{∞} is based on average values obtained from different literature sources.

Subcatchment characteristics

Data groups G1 (channel/pipe data) and H1 (subcatchment data) are used to establish surface flow routing for the RUNOFF module. Surface flow routing is accomplished using subcatchment elements and pipe elements (circular channel flow). Subcatchment elements receive rainfall, account for losses due to evaporation and infiltration (via Horton's equation), and permit surface depression storage to account for losses such as retention on grass or pavement. Surface flow from subcatchment goes into channel pipe/inlet.

Flow routing for both a subcatchment and a pipe in SWMM is accomplished by approximating them as non-linear reservoirs. This is a coupling of a spatially lumped continuity equation with the Manning equation (James and James, 2000). Input channel/pipe data (group G3) include physical parameters of the pipe such as diameter and length of channel/pipe, invert slope and Manning's roughness coefficient. Flow routing data such as subcatchment width WW1 and area of subcatchment WAREA, percent imperviousness (WW3), slope (WSLOPE) and percentage of subcatchment imperviousness (WW3) is usually derived from topographic maps, aerial photos and drainage system plans. These are customarily obtained from the local agency responsible for drainage, usually the city or county. Some of the data were not available and the input parameters such as slope, percent imperviousness, depression storage, Manning's coefficients values are derived with an approximation from available materials or taken from the reference sources.

Calibration

To be useful for the solution of practical problems, the model should be calibrated, meaning that values for the model parameters should be estimated prior to running the model. It has to be done to enable the model to closely match the behavior of the real system it represents (Gupta, 1998). According to Delleur (1998), proper calibration of the runoff quantity model is necessary before attempting to calibrate the quality portion.

Calibration focused on adjusting the values of SWMM parameters to minimize the deviation between measured and model predicted parameters. The purpose of calibration is to find "best" values for the difficult parameters (James, 2003). In urban runoff quantity modelling, calibration can be comparatively simple: e.g., computed peak flow is plotted

against observed peak flow for a number of different rainfall events. If the model is good, the points should fall on 45-degree line with little scatter. The purpose of calibration is to best fit the line of equality, and to reduce the scatter (improve the model accuracy).

Calibration was performed on an event basis. The procedure for calibration was as follows: for each quantity calibration run, the observed and simulated hydrographs were first matched to achieve the observed volume, flow peaks and shape. For each quality run, the observed pollutograph was matched to part of simulated pollutograph to match SS concentration, load and shape. This was done by adjusting parameters obtained during sensitivity analysis.

As mentioned in Chapter 4, sensitivity analysis is required to check the "robustness" of the model. Sensitivity analysis is intended to prioritize the model parameters. It proceeds by holding all parameters but one constant at their expected value, and perturbing that parameter within reasonable expected limits (James, 2003). If apparently small perturbations of a parameter produce large changes in the outcome, the system is to be sensitive to that parameter. The following quantity parameters are found as the most sensitive: percent imperviousness, subcatchment width, impervious area depression storage, Manning's roughness coefficient, and a slope. Their brief description as follows.

Imperviousness is defined as the percentage of the catchment area, which is impervious and hydraulically directly connected to the outlet such as driveways and rooftops with downspouts (James, 2003). It falls into class 3 of uncertainty meaning uncertainty is 25%-50%. Percent imperviousness was found to be the most sensitive parameter affecting both total flow volume and peak flow. It corresponds with the findings of Zaghloul (1981) and Jewell (1978). The percentage of imperviousness of a subcatchment varied almost linearly with the computed peak flow and runoff volume. The peak flow and runoff volume increases as the percent of imperviousness increases. The initial value of percent imperviousness used for calibration was 45%. This value was suggested by Choi and Ball (2002) for medium density residential land use. The final calibrated values are presented in Table 7.3. They averaged 35% for construction catchment and 54% for combined catchment for I phase of construction (Fall 2002 period), 64% and 75% respectively for the II phase (May-July 2003) and 69% and 79% for the III construction phase (August-November 2003).

Parameter WW(1), width of subcatchment (uncertainty class 4, "who knows"), was also found to be sensitive to peak flow and volume. It was noted that peak flow was affected primarily as a result of change in width. It was observed also that width appeared to be less sensitive at higher values than at lower ones. The reduced value of the width resulted in a delayed and attenuated peak hydrograph causing the build up of the surface runoff on the subcatchment plane. Conversely, the increased value of the width allowed the rapid rain drain of water from the subcatchment plane resulting in an advanced larger peak hydrograph. The average calibrated width of the subcatchment varied from 124 to 278 m for the construction catchment and from 173 to 217 m for the combined catchment, gradually increasing towards the end of study period, Fall 2003 (Table 7.3).

Depression storage is defined as a volume that must be filled prior to the occurrence of runoff on both pervious and impervious areas. It represents a loss, or "initial abstraction" caused by surface ponding, surface wetting, interception and evaporation (James and James, 2000). Impervious area depression storage parameter was mostly found to be sensitive to first peak flow. Its uncertainty category is 3 (25-50%). Calibrated values for impervious area depression storage for construction and combined catchments varied from 0.1 to 5 mm. The highest suggested upper limit is 5.1 mm (0.2 in) given by Brater (1968) in James and James (2000).

Parameter WSLOPE (uncertainty class 2-4:10-50%) was used to adjust the main peak flow. Subcatchment slope is estimated by dividing the change in elevation by the length of flow path. Typical change in elevation is approximately 1 to 10 mm (James and James, 2000). For flatter slopes, there is a considerable sensitivity of the peak flow and the runoff volume. This is attributed to the build up of water on the subcatchment surface, which will run off slowly at a longer time. As the slope increases, the runoff flow occurs faster with the result of higher values of peak and runoff volume. Value of 0.01 was used as an initial value for the simulation. Calibrated values varied from 0.004 to 0.02 for construction and combined catchments (Table 7.3).

Table 7.3: RUNOFF block quantity calibration parameters summary.

Calibrated Quantity Parameter	Calibration Purpose	I Phase Fall 2002		II Phase May-July 2003		III Phase August-November 2003	
% Imperviousness WW(3)	Primarily volume adjustment (peaks)	15-45 35	24-90	43-88	65-81 75	47-90 69	50-95
Subcatchment width (m) WW(1)	Primarily peaks adjustment (volumes)	53-170 124	53-290 173	76-250 139	65-300 162	215-400 278	170- 300/217
Imperv. area depression storage (mm) WSTORE1	Primarily first peak adjustment (other peaks)	0.5-6.3 2.3	0.1-7.5 2.3	0.5-4.5 3.0	0.1-6.6 2.8	0.8-5 2.32	1.5-5 2.8
Slope WSLOPE	Primarily peaks adjustment	0.004-0.01 0.008	0.0096-0.02 0.012	0.005-0.02 0.01	0.009-0.015 0.01	0.01	0.005-0.01 0.008

Manning's roughness coefficient is the measure of resistance to the runoff flow. The value of the roughness coefficient depends on the type of soil, surface cover and vegetation in pervious areas. In impervious areas such as streets and building roofs, the coefficient depends on the type of the material used in construction. Manning's coefficient for impervious areas is found to affect peak flows. Its uncertainty class is 2 (10-25%). It was noted that peak flow decreases as the roughness increases. At low values of roughness the sensitivity is greatest. This is due to the fact that smooth surfaces permit faster runoff from the subcatchment. Impervious Manning's coefficient was applied within suggested range of 0.010-0.015 (James and James, 2002).

Appendix I includes quantity calibration parameters for each event calibrated. Summary Table 7.3 presents quantity calibration parameters for construction and combined catchments.

The values obtained confirm that catchment conditions were changing: imperviousness value for development phase (I) was 35 % which gradually increased to 69% by the end of construction. The same pattern in increase for % imperviousness from phase I to phase III (from 54 to 75 and to 79%) is observed for the combined catchment as construction progressed.

Table 7.4 contains important water-quantity input parameters that were used in the model.

Table 7.4: Common RUNOFF block water-quantity input parameters.

Parameter	Description (units)	Value	Uncertainty Class
WW(1)	Width of subcatchment (m)	162-217*	4
WW(3)	Percent of imperviousness	54-79*	3
WSLOPE	Ground slope	0.008-0.01*	2-4
WW(5)	Impervious Manning roughness	0.013-0.015*	2
WW(6)	Pervious Manning roughness	0.03	4
WSTORE1	Impervious depression storage (mm)	2.3-4.8*	3
WSTORE2	Pervious depression storage (mm)	4.5	4
WLMAX	Horton's max infiltration rate (mm/hr)	127	4
WLMIN	Horton's min infiltration rate (mm/hr)	0.036	4
DECAY	Horton's infiltration decay rate (sec ⁻¹)	0.00115	4

*calibrated range

7.3.2 STORAGE/TREATMENT Block Parameter Development and Calibration

Lines D1 (evaporation data), F2 (S/T unit parameters), and H1-H3 (Detention Unit Data) accommodate the input water quantity parameters.

Evaporation data was obtained from Clarifica Inc. (Toronto). Appendix H contains the input file with estimated monthly evaporation values for the studied region. Lines H1 and H3 are used to describe the special characteristics of the detention unit (Ballymore Pond). Parameter IROUTE(I) recognizes the complete mixing assumption. Parameter IOUT describes the depth-treated outflow relationship that characterizes the discharge of treated flow from unit I. In this model the depth-treated outflow relationship is described by 10 data pairs in line H3. Storage-stage data are obtained from the Design Brief on Ballymore pond (Sabourin Kimble and Associates, 2002) and accompanying drawings.

Volume parameter (STORE) is left blank in every H3 line. Thus, the program estimates the volume at each depth by averaging the surface area at each depth and the lower adjacent depth, multiplying by the difference in depth, and adding the result to the estimated

volume at the lower adjacent depth (i.e., by a trapezoidal rule integration) (James and James, 2000). H3 line input parameters are presented in Table 7.5.

Table 7.5: S/T block line H3 input parameters.

Depth (m)	Area (m ²)	Volume (m ³)	Treated Outflow (m ³ /s)	Residual Outflow (m ³ /s)
0	94	0	0	0
0.5	704	0	0	0
1.5	1366	0	0	0
2.4	2575	0	0	0
2.5	2650	0	0.016	0
3.0	2958	0	0.023	0
3.3	3144	0	0.024	0
3.5	3265	0	0.027	0
3.75	3880	0	0.030	0
4	4495	0	0.033	0

Total volume of water in a unit at the start of simulation WARN(I) fits into line H8, which defines the initial conditions in detention unit I.

Calibration

The most sensitive parameters found were the initial volume within the facility WARN(I) followed closely by the discharge rate from the facility. They fall into uncertainty category1 which means that "uncertainty is small, a few percentage points, perhaps 5-10%. Total volume of water in the pond at the start of simulation is 2700 m³. Calibrated values vary from 2500 to 3000 m³ that lies in 8.5-11% range

7.4 SWMM Water Quality

7.4.1 RUNOFF Block Parameter Development and Calibration

Simulation of urban runoff quality is very inexact. Very large uncertainties arise both in the representation of the physical, chemical and biological processes and in the acquisition of data and parameters for model algorithms (James and James, 2000).

The RUNOFF block in the SWMM model is the origin of water quality constituents. Several mechanisms constitute the genesis of stormwater quality, most notably *build up* and *washoff*. In an impervious urban area, it is usually assumed that a supply of constituents is built up during dry weather on the land surface. Alternatively, quality loads (mass/time) can be generated by a rating curve approach where loads are proportional to flow to some power.

Buildup refers to pollutant accumulation over the catchment surfaces, and is the outcome of a complex array of dry-weather processes that occur between rainfall events, such as atmospheric deposition, and many anthropogenic urban activities (James, 1995; Behera, 2001). Buildup occurs over the number of dry days prior to the beginning of simulation (DRYDAY) and also during continuous simulation when runoff is very small (<0.013 mm/hr) (Delleur, 1998).

The RUNOFF block simulates quality of runoff processes within a drainage basin, and the routing of flows and contaminants along storm drain lines, leading to the calculation of a number of inlet hydrographs and pollutographs. There are several options for computing accumulation and wash-off of pollutants in SWMM (James and James, 2000). Here, an accumulation method that follows an exponential equation was used:

$$PSHED = QFACT(1) * (1 - e^{-QFACT(2)*t}), \quad (7.2)$$

where PSHED is the constituent quantity at time t ; t is the preceding dry weather period ; QFACT(2) is the power or exponent for the build-up parameter; and QFACT(1) is the first build-up parameter, e.g. limit.

Washoff is the process of erosion and transport of constituents from a catchment surface during the period of runoff (Warwick and Tadepalli, 1991; Delleur, 1998). The relationship used within SWMM describes washoff at each time step to be proportional to the runoff rate (r) raised to a power (WASHPO)

$$POFF(t) = RCOEFX * r^{WASHPO} * PSHED, \quad (7.3)$$

where $POFF(t)$ is constituent load washed off at time t ; $RCOEFX$ is washoff coefficient ($RCOEFX = RCOEFF/3600$; $RCOEFF$ is washoff coefficient; r is runoff rate over subcatchment; $WASHPO$ is a runoff rate exponent.

Equations (7.2) and (7.3) are commonly used equations in SWMM and were the most appropriate to use with the given data. The RUNOFF block forms the source of generating hydrographs and pollutographs for most other SWMM blocks, and may be run for periods ranging from minutes to years.

Both buildup and washoff processes are conceivably continuous processes occurring over the catchment. Quality buildup and washoff parameters were subject to calibration process. Details are given in later section.

Erosion Input

Erosion and sedimentation are often cited as major problems related to urban runoff (James and James, 2000). In this study an attempt was made to simulate erosion of solids. In SWMM, erosion simulation falls under the water quality component of the RUNOFF module. Erosion is treated as an additional water quality constituent, so that one of the fewer pollutants can be simulated. In addition, it is required that at least one quality constituent must be simulated (e.g., TSS). No particular soil characteristics (e.g., particle size distribution) are assigned to the erosion parameter, and its title is "Erosion" with units of mg/L, in the output.

To simulate soil erosion in SWMM, the parameter IROS in Line J1 was indicated. Erosion may be added to another constituent, e.g., suspended solids, if desired using parameter IROSAD in J1. However, the Erosion parameter was maintained as an individual parameter throughout the RUNOFF Module.

Other important input parameters are: (1) the maximum 30-minute rainfall intensity of the storm (single event) or of simulation period (continuous), RAINIT, (group J1); (2) the area of each subcatchment subject to erosion, ERODAR, (group K1); (3) the flow distance from the point of origin of overland flow over the erodible area to the point at which runoff enters inlet, ERLIN, (group K1); (4) the soil factor K, SOILF, group K1); (5) the cropping

management factor C, CROPMF, (group K1); and (6) the control practice factor P, CONTPF, (group K1).

PCSWMM uses the Universal Soil Loss Equation (USLE) to predict the average soil loss for a given storm or time period. The USLE was developed by Wischmeier and Smith (1958) as an estimate of the average annual soil erosion from rainstorms for a given upland area, L, expressed as the average annual soil loss per unit area:

$$L = R * K * LS * C * P \quad , \quad (7.4)$$

where R is the rainfall factor, K is the soil erodibility factor, LS is the slope length gradient ratio, C is the cropping management factor or cover index factor, and P is the erosion control practice factor.

Maximum 30-minute rainfall intensity of the storm, parameter RAINIT, was estimated from an inspection of the input hyetograph prior to simulation.

Parameter ERODAR (group K1) represents the area of the subcatchment subject to erosion and in this study indicates the land area on which soil is exposed. 3 different values of ERODAR were obtained for each of three stages of development. With progressing construction activities, the area of soil exposed decreased from 3.96 ha in the Fall 2002 to 0.23 ha at the end of construction in November 2003 (Table 7.6).

Table 7.6: Input values for ERODAR SWMM parameter.

Observation Period/Date	Area exposed after housing development %	Catchment area exposed* %	Catchment area exposed ha	Total catchment area exposed including banks area** ha
Fall 2002	97	29.6	3.84	3.96
27-May-03	80	25.1	3.25	3.38
27-Jun-03	54	16.9	2.19	2.32
14-Jul-03	54	16.9	2.19	2.32
28-Jul-03	40	12.6	1.63	1.76
13-Aug-03	12	3.7	0.48	0.61
11-Sep-03	12	3.7	0.48	0.61
10-Oct-03	12	3.7	0.48	0.61
13-Nov-03	2.5	0.8	0.10	0.23

*Catchment area=15.1 ha, soil exposed area after housing development=4.05 ha
Sabourin Kimble and Associates, 2000)

**Banks area=0.126 ha

The soil factor, K, is a measure of the susceptibility of soil particles to rainfall erosion and runoff transport. The input K value is estimated based on MTO recommendations (J. Li, 1997).

CROPMF, or cropping management factor 'C', is dependent upon the type of ground cover, the general management practice and the condition of the soil over the area of concern. There are 3 different values for CROPMF that were exercised in this study in accordance to the phase of development.

Control Practice Factor 'P' (CONTPF) accounts for the erosion-control effectiveness of superimposed practices, such as contouring, terracing, compacting, sediment basins and control structures. Value 'C' is taken from Fifield (2001).

Summary of RUNOFF block quality input parameters is presented in Table 7.7.

Table 7.7: Water quality calibration on event basis.

Event Date	Phase	Calibrated Quality Model Parameters			
		QFACT(1)	WASHPO	RCOEFF	ERLEN
14-Sep-02	I	400	0.725	0.02	150
20-Sep-02		200	1.5	0.1	56.8
27-Sep-02		300	0.878	0.1	200
2-Oct-02		210	1.2	1	200
19-Oct-02		250	0.64	0.01	150
25-Oct-02		250	1.9	7	100
Average		268	1.141	1.372	143
2-May-03	II	200	2	0.246	20
5-May-03		430	3	0.05	150
11-May-03		210	2.43	0.1852	300
20-May-03		200	2	0.138	100
4-Jun-03		200	2	0.001	173
8-Jun-03		200	1.55	0.438	150
Average		240	2.163	0.176	149
15-Sep-03	III	200	1.217	0.313	300
19-Sep-03		200	1.09	0.059	150
22-Sep-03		265	1.06	0.027	300
Average		222	1.122	0.133	250
Average		243	1.475	0.560	181

Calibration

Water quality calibration focused on matching SS loads and shapes of pollutographs as close as possible to measurements by varying the sensitive parameters within the range given in the literature and the manual of the model.

Four input quality parameters were found to be the most sensitive and were used to calibrate the loads of SS and shapes of pollutographs, namely: QFACT1, WASHPO, RCOEFF, and ERLEN. The last parameter ERLEN represents the erosion input into a simulation. All of these parameters, except ERLEN, are in a category 4 of uncertainty, which means that these parameters cannot be measured with any certainty at all (James, 2003). Their uncertainty falls into a range which James suggests as "who knows?" If any estimate can be made at all, perhaps assume 50-100% as a starting point". Parameter ERLEN is scaled into category 2, meaning that its uncertainty is 10-25%.

The washoff exponent rate WASHPO and coefficient RCOEFF are by far the most sensitive parameters during all the events. The initial value for QFACT1 was determined by simulating the SS loads from the stable catchment. Its average value was found to be 250. A summary of quality calibration parameters on an event basis is also shown in Table 7.7.

Calibrated values for QFACT1 varied from 210 to 430 throughout the monitoring period. Washoff parameters WASHPO and RCOEFF were used to adjust initial values for SS and the maximum concentration. Calibration values for WASHPO fell into an average range of 1.14 to 2.16. This almost corresponds with the observations from Kuch's (James 2003) and Delleur's (1998) that typically the exponent WASHPO takes values between 1.5-3.0 for particulate and less than 1.0 for dissolved constituents.

RCOEFF is the coefficient in the washoff equation. The value of RCOEFF for SS varied from 0.001 to 7, exhibiting the highest values for the events with highest observed SS concentration.

Parameter ERLLEN is scaled to 2 in the uncertainty category. Its value varied from 57 to 300, with initial starting value of 150, which was averaged from design maps.

Table 7.8 presents the water-quality input parameters used in all SWMM simulations in this study.

Table 7.8: Common RUNOFF block water-quality input parameters.

Parameter	Description	Value	Uncertainty Class
KALC	Exponential constituent buildup	2	B
KWASH	Power-exponential washoff	0	B
KACGUT	Pollutant buildup functionality	1	B
QFACT(1)	First buildup parameter (limit)	222-268*	4
QFACT(2)	Second buildup parameter (power or exponent)	1	4
WASHPO	Runoff rate exponent	1.141-2.163*	4
RCOEFF	Washoff coefficient, in ⁻¹	0.133-1.372*	4
ERODAR	Area of erosion, ha	0.61-3.97*	1
ERLEN	Flow distance	143-250*	2
SOILF	Soil factor 'K'	0.3	3
CROPMF	Cropping management factor 'C'	0.8-0.1*	3
CONTPF	Control practice factor 'P'	1	3

*calibrated range

7.4.2 S/T Block Parameter Development and Calibration

Suspended Solids are characterized by concentration alone, their removal is simulated through removal equations. Data Groups G1 through G3 are used to establish these removal equations. Removal of a SS is simulated as a function of its influent concentration and removal equation is

$$R=(a_{12}+a_{13} e^{a_{16} x_3})^{a_{16}}, \quad (7.5)$$

where x_3 is the removal equation variable; a_{12} , a_{13} , a_{16} are coefficients; and R is a removal fraction, $0 \leq R \leq 1.0$.

Calibration

Quality calibration for the outlet in S/T block included adjusting the a-coefficients (pollutant removal values) and PCO(I) (concentration in the pond at the start of the simulation). PCO(I) values fall into category 4 of uncertainty, and a-coefficients – into category 2. Their values are shown in Table 7.9.

Table 7.9: Calibrated water-quality parameters for S/T block.

Calibrated Parameter	Value range
a_3	From -0.000005 to -0.001
a_{12}	From 0.000065 to 1
a_{13}	From -0.000065 to -1
a_{16}	From 0.140 to 7
PCO(I)	From 0.1 to 2300

CHAPTER 8

MODELLING RESULTS

This chapter provides the results generated from the PCSWMM model. The results are presented separately for the construction catchment, combined catchment and the outlet.

8.1 Water Quantity Results

From the calibrated SWMM model, the runoff volumes and peak flows for monitored events were estimated.

Table 8.1 represents the comparison of observed and simulated inlet runoff volumes and peak flows for the construction catchment. The difference in runoff volume between observed and simulated events ranged between 0 and 8.3% and the difference in peak flow ranged between 0.17 and 5.9%. The total observed runoff volume over the total sampling period is found to be 113 mm compared to the total of 115 mm of simulated runoff volume over the same period. The average difference between observed and simulated runoff volume is 2%. The average difference between peak flows is also 2%.

Table 8.1: Comparison of observed and simulated water quantity results for the construction catchment.

Event Date	Rainfall (mm)	Comparison of Runoff Volume			Comparison of Peak Flow		
		Observed (mm)	Simulated (mm)	% Difference	Observed (l/s)	Simulated (l/s)	% Difference
14-Sep-02	28.2	6.80	6.80	0.00	231.0	231.4	0.17
20-Sep-02	13.3	1.70	1.80	5.56	99.4	101.0	1.58
27-Sep-02	18.4	6.90	7.00	1.43	70.9	71.9	1.39
02-Oct-02	10.0	2.20	2.40	8.33	72.4	72.8	0.55
19-Oct-02	13.0	3.00	3.20	6.25	24.0	25.5	5.88
25-Oct-02	9.4	3.02	3.10	3.23	29.0	30.5	4.92
02-May-03	6.8	2.90	3.00	3.33	16.7	17.5	4.57
05-May-03	17.4	7.00	7.10	1.41	97.9	99.4	1.51
11-May-03	17.8	5.10	5.30	3.77	63.7	65.0	2.00
20-May-03	10.8	2.90	3.00	3.33	66.8	68.3	2.20
04-Jun-03	13.8	5.30	5.30	0.00	49.5	50.4	1.79
08-Jun-03	23.6	15.90	16.20	1.85	375.7	377.4	0.45
15-Sep-03	15.0	6.00	6.10	1.64	106.7	108.0	1.20
19-Sep-03	38.0	25.30	25.90	2.32	222.6	223.0	0.18
02-Nov-03	32.2	19.00	19.20	1.04	77.7	78.5	1.02
Total		113.0	115.4				
Average				2.0			
Correlation		0.9			0.9		

Figures 8.1 and 8.2 show a strong correlation between observed and simulated volumes and peak flows for construction catchment.

1:1

Fig. 8.1: Relation between observed and simulated runoff volume for the construction catchment.

Fig. 8.2: Relation between observed and simulated peak flows for the construction catchment.

Figure 8.3 (a-c) compares observed and simulated hydrographs for some events.

a)

b)

c)

Fig. 8.3 (a-c): Comparison of observed and simulated hydrographs for the construction catchment.

Table 8.2 represents the comparison of observed and simulated water quantity results for the combined catchment. The difference in runoff volume between simulated and observed events ranged between 0% and 12% and difference in peak flow ranged between 0.17% and 5.88%. Simulated and observed total volumes differ by only 0.2%, average difference between peak flows is 1.25%.

Table 8.2: Comparison of observed and simulated water quantity results for the combined catchment.

Event Date	Rainfall (mm)	Comparison of Runoff Volume			Comparison of Peak Flow		
		Observed (mm)	Simulated (mm)	% Difference	Observed (l/s)	Simulated (l/s)	% Difference
14-Sep-02	28.2	7.12	7.13	0.14	231.0	231.4	0.17
20-Sep-02	13.3	2.82	2.82	0.00	99.4	101.0	1.58
27-Sep-02	18.4	9.24	9.72	4.94	70.9	71.9	1.39
02-Oct-02	10.0	3.18	3.36	5.36	72.4	72.8	0.55
19-Oct-02	13.0	4.11	4.21	2.38	24.0	25.5	5.88
25-Oct-02	9.4	4.62	4.63	0.22	29.0	30.5	4.92
02-May-03	6.8	3.41	3.68	7.34	16.7	17.5	4.57
05-May-03	17.4	8.50	8.60	1.16	97.9	99.4	1.51
11-May-03	17.8	7.52	7.65	1.70	63.7	65.0	2.00
20-May-03	10.8	5.50	4.91	-12.02	66.8	68.3	2.20
08-Jun-03	23.6	18.68	18.89	1.11	375.7	377.4	0.45
15-Sep-03	15.0	6.30	6.32	0.32	106.7	108.0	1.20
19-Sep-03	38.0	25.60	25.13	-1.87	222.6	223.0	0.18
02-Nov-03	32.2	19.20	19.00	-1.05	77.7	78.5	1.02
Total		125.8	126.05	0.20			
Average							1.2
Correlation		0.9			0.9		

Figures 8.4 and 8.5 show very strong correlation between observed and simulated volumes and peak flows for combined catchment.

Fig. 8.4: Relation between observed and simulated runoff volume for the combined catchment.

1:1

Fig. 8.5: Relation between observed and simulated peak flows for the combined catchment.

Table 8.3 presents the comparison of observed and simulation water quantity results for the outlet. The difference in runoff volume between simulated and observed events ranged between 1.8% and 84% averaging 7.4%; and difference in peak flow ranged between 0.3% and 28.8% averaging in 1.3%.

Table 8.3: Comparison of observed and simulated outlet runoff volume and peak flow for the outlet.

Event Date	Rainfall (mm)	Comparison of Volume			Comparison of Peak Flow		
		Observed (m ³)	Simulated Observed (m ³)	% Difference	Observed (l/s)	Simulated (l/s)	% Difference
14-Sep-02	28.2	1044.5	1073.2	2.7	12.6	12.8	1.0
20-Sep-02	13.3	422.4	506.4	16.6	8.6	8.6	-0.9
27-Sep-02	18.4	1505.3	1533.4	1.8	16.3	16.4	0.6
02-Oct-02	10.0	337.9	386.0	12.4	10.6	11.0	3.3
19-Oct-02	13.0	614.4	574.1	-7.0	10.4	10.4	-0.4
25-Oct-02	9.4	737.3	529.3	-39.3	7.4	7.6	2.4
02-May-03	6.8	506.9	283.8	-78.6	8.4	8.5	0.6
05-May-03	17.4	1244.2	1045.2	-19.0	16.8	16.8	-0.3
20-May-03	10.8	783.4	834.3	6.1	17.9	17.6	-1.6
08-Jun-03	23.6	3970.9	5800.8	31.5	31.6	44.3	28.8
15-Sep-03	15.0	952.3	607.7	-56.7	14.2	14.4	1.4
19-Sep-03	38.0	1858.6	1010.0	-84.0	16.3	16.6	1.9
02-Nov-03	32.2	3091.0	1703.0	-81.5	18.8	16.7	-12.6
Total		17068.9	15887.0	-7.4			1.3
Correlation			0.8			0.9	

The relationship between observed and simulated peak flows is shown on Figure 8.6.

Fig. 8.6: Relation between observed and simulated runoff volume for the outlet.

Value of 0.8 is obtained indicating a strong correlation between two variables.

Fig. 8.7: Relation between observed and simulated peak flows for the outlet.

Simulated outlet peak flow rates match the observed ones more accurately. Strong correlation of 0.9 is found (Figure 8.7).

Figure 8.8 (a-c) represents the comparison of observed and simulated inflow and outflow hydrographs for the combined catchment and the outlet for several events. Hydrographs for all of the events modeled are included in Appendix I.

Sept. 14, 2002
Combined Catchment and Outlet
Rain=28.8 mm

May 5, 2003
Combined Catchment and Outlet
Rain=17.4 mm

a)

c)

Fig. 8.8 (a-c): Comparison of observed and simulated hydrographs for the combined inlet and the outlet.

In summary, the construction catchment total observed and simulated flow volume and peak flow rates are matched within 8% and 6%, respectively, while differences between observed and simulated volumes and observed and simulated peak flows averaged 2%. At the combined catchment total volume differs from the simulated total volume by 0.2%, Simulated peak flow in the combined catchment differ from that observed by 1.2% in average, or within 6%. The outlet total observed volume is 7% bigger than the simulated. Peak flow differs by only 1.3 % in average.

8.2 Water Quality Results

As was mentioned earlier, stormwater quality modeling is an inexact exercise because of the many variable and interdependent factors that can influence water quality (James and James, 2000).

The runoff sediment load from a construction site yields from two sources: (i) buildup and washoff of sediments from the watershed surface, and (ii) soil erosion from the exposed pervious area. Accordingly, SWMM uses two routines for sediment generation during a runoff event. First, a buildup and washoff routine which is typically used for simulating SS load from catchments. Second, soil erosion routine, which uses Universal Soil Loss Equation to model sediments from soil erosion. The simulated sediment load for the event is the combination of both sources.

Construction Catchment

The parameter values of buildup and washoff processes and erosion processes for the Catchment-1070 were obtained during runoff quality calibration. Regarding the erosion input: the exposed soil area for the construction site which was subjected to erosion comprised of two sources: (i) soil exposure in the individual lots which were monitored, and (ii) soil exposure from the banks of the construction sediment control pond.

As mentioned previously, the observed SS values were obtained by monitoring at the inlet during the first 2 to 6 hours of an event. This data was sufficient for the events with short durations; however, it was only partial for the most of the events.

Table 8.4 represents the comparison of observed and simulated water quality results. During the sampling events (2-6 hours duration), a total mass load of 17294 kg was observed and a total mass load of 18783 kg was simulated. The difference between observed and simulated total mass load for individual events ranged between 6 and 105%. This is typical in case of water quality simulation. The total simulated load for the whole sampling period was found to be 22784 kg.

Total simulated load from erosion is 351.6 kg, which is only 1.5% of the total SS load coming into the pond. In average, 70% of the mass load is entering the pond within the first hours.

Table 8.4: Comparison of observed and simulated mass loads for the construction catchment.

Event Date	Rainfall (mm)	Comparison of SS Loads for sampling period (Catchment-1070)		% Difference	Simulated SS load for the Whole Event (kg)	Load from the erosion (kg)	% Load from the erosion
		Observed (kg)	Simulated (kg)				
14-Sep-02	28.2	1307	638	-104.9	1758	16.07	0.9
27-Sep-02	18.4	953	952	0.0	1979	31.0	1.6
02-Oct-02	10.0	1717	1834	6.4	2422	32.0	1.3
19-Oct-02	13.0	74	63	-17.5	154	6.0	3.9
25-Oct-02	9.4	2190	3436	36.3	2764	5.0	0.2
02-May-03	6.8	88	156	43.6	268	0.7	0.3
05-May-03	17.4	266	282	5.7	2862	19.4	0.7
11-May-03	17.8	1205	1043	-15.5	1941	31.0	1.6
20-May-03	10.8	557	765	27.2	1097	18.4	1.7
08-Jun-03	23.6	7254	6707	-8.2	2514	37.1	1.5
15-Sep-03	15.0	433	642	32.6	1118	1.0	0.1
19-Sep-03	38.0	745	1328	43.9	1928	1.4	0.1
22-Sep-03	25.0	387	787	50.8	1020	1.3	0.1
02-Nov-03	32.2	118	149	20.8	959	0.3	0.0
Total		17294	18783	7.93	22784	351.6	
Correlation		0.9					

A strong correlation of 0.9 is found between observed and simulated SS loads (Figure 8.9).

Fig. 8.9: Relation between observed and simulated mass load for the construction catchment.

Table 8.5 shows that the observed average SS concentration from the construction catchment is estimated to be 3288 mg/L, simulated – 3984 mg/L. Observed average SS concentration varied from 74 mg/L in Oct.2, 2002 to 7254 mg/L in June 8, 2003. The difference between simulated and observed SS concentration averaged 17.5% within the range of 105%.

Table 8.5: Comparison of observed and simulated SS concentrations for the construction catchment.

Event Date	Rainfall (mm)	Comparison of SS Concentrations for sampling period (Catchment-1070)		% Difference	Simulated EMC for the Entire Event (mg/L)
		Observed (mg/L)	Simulated (mg/L)		
14-Sep-02	28.2	8766	4281	-104.8	860
27-Sep-02	18.4	6004	4613	-30.2	2180
02-Oct-02	10.0	9935	10561	5.9	7813
19-Oct-02	13.0	1150	973	-18.2	370
25-Oct-02	9.4	13801	22112	37.6	6876
02-May-03	6.8	412	771	46.6	685
05-May-03	17.4	1040	1104	5.8	3135
11-May-03	17.8	2266	1968	-15.1	2809
20-May-03	10.8	1448	2399	39.6	2798
08-Jun-03	23.6	5030	4650	-8.2	1195
15-Sep-03	15.0	687	1030	33.3	1422
19-Sep-03	38.0	367	662	44.6	574
22-Sep-03	25.0	238	481	50.5	449
02-Nov-03	32.2	366	462	20.8	385
Average Correlation		3288	3984	17.5	2254
		0.8			

The average event mean concentration (AEMC) from the Ballymore construction watershed was estimated as 2254 mg/L within a range of 385 mg/L to 7813 mg/L.

Figure 8.10 shows the relationship between observed and simulated SS concentrations. Correlation of 0.8 is determined, which is less than correlation obtained for the mass loads.

Fig. 8.10: Relation between observed and simulated SS concentrations for the construction catchment.

Figure 8.11 (a-d) represents the comparison of observed and simulated pollutographs for September 14, 2002, May 5, 2003 and May 20, 2003, and show the portion of observed and simulated SS during the sampling period of the whole event.

a)

b)

c)

d)

Fig. 8.11: Comparison of observed and simulated SS pollutographs for 4 events.

The duration of May 20, 2003 event was only 8 hours. Because the time of the observed pollutograph matched the time of simulated pollutograph, there was a chance to verify the model's performance: the difference between observed and simulated loads was 27% which is a fairly good result for quality calibration.

Based on simulated EMC results, a graph of change of EMC's during the whole monitoring period was created (Figure 8.12).

Fig 8.12: Evolution of EMC for the construction catchment.

Combined Catchment

For the combined catchment the decrease in EMC during the study period was observed as well. Simulated results for mass loads and EMC are shown in Table 8.6. The highest value of event concentration of 5957 mg/L is obtained for the phase I event in October 2002. The lowest SS EMC is 378 mg/L and characterizes the very last monitored event in phase III.

Table 8.6: Simulated EMC and mass load and EMC for the combined catchment.

Event Date	Rainfall (mm)	Simulated SS Load for the Whole Event (kg)	Simulated EMC (mg/L)	SS Load from Erosion (kg)	% of SS from Erosion
14-Sep-02	28.2	850	755	122.0	14
22-Sep-02	13.3	111	256	24.6	22
27-Sep-02	18.4	2807	1880	48.8	2
02-Oct-02	10.0	3074	5957	32.0	1
19-Oct-02	13.0	226	306	5.0	2
25-Oct-02	9.4	3273	4441	3.0	0
02-May-03	6.8	448	806	0.7	0
05-May-03	17.4	4687	3532	24.5	1
11-May-03	17.8	2798	2383	20.0	1
20-May-03	10.8	1842	2440	15.0	1
08-Jun-03	23.6	2999	1034	36.0	1
15-Sep-03	15.0	1346	1388	1.0	0
19-Sep-03	38.0	2256	584	1.4	0
02-Nov-03	32.2	1104	378	0.3	0
Total		1987	1867		
Average				23.9	1

For the combined catchment the total simulated SS mass load for the whole study period is 1987 kg, average EMC is 1867 mg/L, ranging from 256 to 5957 mg/L. Mass load coming from erosion is 24 kg which is only 1% of the total mass load of SS. Similar to results from construction catchment, EMC experiences gradual decrease from phase I to phase II and to phase III : 3620 mg/L in the Fall 2002 period, 2124 mg/L in May-July 2003; and 708 mg/L in August-November 2003 period. Figure 8.13 represents the evolution of EMC's throughout the study period.

Fig 8.13: Evolution of EMC for combined catchment.

Outlet

Table 8.7 presents the comparison of observed and simulated SS loads results. The total observed mass load is 380.6 kg which is 15% less than simulated load of 447.2 kg for the whole study period. Simulated total SS load for the whole period (event of June 8 was not considered) is 656.7 kg, which indicates that within 6 hours of average sampling period only 15.5% of sediments exited the pond's outlet. The rest 84.5% seems to pass out later.

Table 8.7: Comparison of observed and simulated SS loads for the outlet.

Event Date	Rainfall (mm)	Comparison of SS Loads for sampling period (Outlet)		% Difference	Simulated SS load for the Entire Event (kg)
		Observed (kg)	Simulated (kg)		
14-Sep-02	28.2	12.7	20	37	303.8
20-Sep-02	13.3	1.5	2.7	44	17.1
27-Sep-02	18.4	3.6	5.6	36	89.9
02-Oct-02	10.0	0.5	0.6	18	3.4
19-Oct-02	13.0	2.0	2.7	26	40.3
25-Oct-02	9.4	0.5	0.7	29	3.5
02-May-03	6.8	2.5	2.7	7	5.4
05-May-03	17.4	4.3	4.4	2	71.0
20-May-03	10.8	20.4	19.4	-5	35.0
08-Jun-03	23.6	268.5	345.4	22	4599.0
15-Sep-03	15.0	31	16.0	-94	18.1
19-Sep-03	38.0	22.1	15.0	-47	15.8
02-Nov-03	32.2	11.0	12.0	8	53.4
Total		112.1	101.8	-10.1%	656.7
Correlation		0.7			

With a total observed mass load of 112.1 kg and a simulated mass load 101.8 kg this exhibits a difference of 10%. Correlation of 0.7 is observed between simulated and observed loads.

Fig. 8.14: Relation between observed and simulated mass load for the outlet.

Regarding the modelling of SS concentration, the following results are obtained (presented in Table 8.8): average SS observed concentration is 202.5 mg/L, which is 17% less than simulated SS concentration of 242.6 mg/L. Correlation coefficient between observed and simulated SS concentration is 0.84 (Figure 8.15). AEMC is 93 mg/L.

Table 8.8: Comparison of observed and simulated SS concentrations for the outlet.

Event Date	Rainfall (mm)	Comparison of SS Concentrations for sampling period (Outlet)		Difference (%)	Simulated EMC (mg/L)
		Observed (kg)	Simulated (kg)		
14-Sep-02	28.2	277	395	30	278
20-Sep-02	13.3	27	58	53	55
27-Sep-02	18.4	75	120	38	59
02-Oct-02	10.0	7	9	22	9
19-Oct-02	13.0	29	41	29	66
25-Oct-02	9.4	17	23	26	8
02-May-03	6.8	30	32	6	19
05-May-03	17.4	36	28	-29	65
20-May-03	10.8	110	105	-5	42
08-Jun-03	23.6	1630	1862	12	316
15-Sep-03	15.0	121	66	-83	33
19-Sep-03	38.0	93	80	-16	16
02-Nov-03	32.2	88	197	55	184
Average		202.5	242.6	17%	93
Correlation		0.8

Fig. 8.15: Relation between observed and simulated SS concentrations for the outlet.

Figure 8.16 shows the change in EMC during the whole study period. EMC for Fall 2002 is found to be 93 mg/L, for May-July it is 110.5 mg/L and for August- November 137 mg/L. It was found to increase slowly which indicates that overall SS concentration of the pond increased due to unsettled sediments accumulated over the period of time.

Fig. 8.16: Evolution of EMC for the outlet.

Figure 8.17 (a-c) show the comparison between outlet pollutographs for events of October 2002 and May 2003.

a)

b)

c)

Fig. 8.17 (a-c): Comparison of observed and simulated SS pollutographs for 3 events for the outlet.

Using formulas described in Chapter 3, load-based and event-based removal efficiencies are calculated. The results are shown in Tables 8.9 and 8.10.

Table 8.9: Load-based removal efficiency.

Event Date	Inflow Load Simulated (kg)	Outflow Load Simulated (whole event) (kg)	Removal Efficiency
14-Sep	850	395	53.5%
20-Sep	111	58	7.7%
27-Sep	2807	120	95.7%
2-Oct	3074	9	99.7%
19-Oct	226	41	81.9%
25-Oct	3273	23	99.3%
2-May	448	32	92.9%
5-May	4687	28	99.4%
20-May	1842	105	94.3%
15-Sep	343	66	95.1%
19-Sep	2256	80	96.5%
2-Nov	1104	197	82.2%
Average			87%

Table 8.10: Concentration-based removal efficiency.

Event Date	Inflow Concentration Combined Simulated (mg/L)	Outflow Concentration Simulated (mg/L)	Removal Efficiency
14-Sep	755	278	63.1%
20-Sep	1880	55	97.1%
27-Sep	5957	59	99.0%
2-Oct	306	9	97.2%
19-Oct	4441	66	98.5%
25-Oct	806	8	99.0%
2-May	3532	19	99.5%
5-May	2383	65	97.3%
20-May	1034	42	95.9%
15-Sep	1388	33	97.6%
19-Sep	584	16	97.3%
2-Nov	378	184	51.5%
Average			91%

CHAPTER 9

CONTINUOUS SIMULATION AND BOTTOM SEDIMENT ACCUMULATION

This chapter covers the assessment of sediment load entering the pond during the study period. The PCSWMM modeling approach and comparison of modeling results along with field results obtained by actual measurements of bottom sediment accumulation was implemented. Also, assessment of long-term removal efficiency by the pond is presented.

9.1 Bottom Sediment Accumulation

To measure bottom sediment accumulation within the pond, standard surveying techniques were used, as described in detail in Chapter 4. This method was applied near the end of the monitoring period in October 2003. Thirteen measurement points with known calculated elevation values were selected. From these measurements, the total accumulation of sediments was obtained.

Initial bottom pond elevations in August 2002, measured elevations in October 2003 and total accumulation during the study period are shown in Table 9.1.

Table 9.1: Sediment Accumulation during Fall 2002-Fall 2003.

Elevation in August 2002 (m)	Elevation in October 2003 (m)	Total Accumulation (m)
298	298.07	0.07
297.5	297.58	0.08
297.5	297.6	0.1
298	298.09	0.09
298	298.1	0.1
298	298.08	0.08
298	298.1	0.1
298	298.09	0.09
298	298.07	0.07
298	298.15	0.15
298	298.25	0.25
298	298.2	0.2
298	298.3	0.3
Average		0.13

Applying the calculated value of 0.13 m for average sediments' depth and known pool's area value of 704 m² and sediments' density of 1230 kg/m³ (MOE, 2003), value of 111903.5 kg of total mass accumulated within study period is calculated. Considering contributing area of 15.1 ha, sediment accumulation rate of 6.0 m³/ha is obtained.

9.2 Continuous Simulation

9.2.1 Assessment of Sediment Load, Concentration and Removal Efficiency

In order to estimate the sediment loads and pond performance during the study period from September 2002 to November 2003, long-term simulation PCSWMM was conducted. The continuous simulation model was based on 9 months of hourly rainfall data (from September 2002 to June 2003) extracted from Toronto Buttonville Airport 30-years rainfall record.

All of the calibrated quantity and quality parameters of RUNOFF and S/T blocks that vary from event to event, including percentage imperviousness, impervious area depression storage, subcatchment width, slope, impervious Manning's coefficient, washoff coefficients

and etc., were averaged. Average values of these calibrated parameters served as an input parameters to RUNOFF and S/T blocks of PCSWMM. Input files are included in Appendix H.

Based on model results, 69290 kg of sediments entered the pond and 3187 kg are exited the pond during the 9 months of simulation. To account for the July-October months, the average monthly sediment load values of 7699 kg for inflow and 354 kg for the outflow were used. Thus, total estimated sediment loads entering and exiting the pond during the study period were 100086 kg and 4603 kg, respectively. The remaining 95482 kg, or a layer of 0.11 m sediments is calculated to have been deposited at the bottom of the pond over the study period. Considering the contributing area of 15.1 ha, estimated accumulation rate is $5.1 \text{ m}^3/\text{ha}$.

The difference of 0.02 m between modelled depth of sediments and measured depth can be explained either by crude measurements or errors during stormwater quality modeling.

Figure 9.1 represents PCSWMM plot output file results in the form of outlet treated flow and SS concentration for the study period.

2002-2003 Continuous Simulation

Outlet Flows and Outlet SS Concentration

Fig. 9.1: Long-term continuous simulation for the period of September 2002- November 2003.

Applying modelled total simulated inflow and outflow volumes values, average inflow and outflow concentrations of sediments are calculated. For the study period average SS concentration for the inflow is found to be 2033 mg/L, for the outflow 99 mg/L. These values are closely matching with the average EMC's simulated on an event basis: 1867 mg/L for the inflow from the combined catchment and 93 mg/L for the outflow.

Pond performance during the period of 2002-2003 was estimated. Removal efficiencies (RE) results are shown in Table 9.2.

Table 9.2: Summary of long-term simulated, event-based simulated, and observed instantaneous removal efficiencies.

Average C-Based RE (%)		Average Load-Based RE (%)		Average Instantaneous Observed RE (%)
Continuous Simulation	On Event Basis	Continuous Simulation	On Event Basis	Load-based
91	95	95	87	96

These values are very close, averaging 93%, indicating high sediment removal efficiency by the pond.

9.2.2 Long-Term Performance

Long-term continuous simulation was conducted to estimate the cumulative construction sediment loads leaving the site. The continuous simulation model was based on 3 years hourly rainfall data from Toronto Buttonville Airport for average and extreme wet year conditions. The average rainfall-year condition was assessed using the 1978 to 1980 rainfall record and the extreme rainfall year condition was assessed u

sing the 1990 to 1992 rainfall record. The May 2003 watershed condition, which represents the active building construction scenario, was used for the continuous simulation.

Tables 9.3 and 9.4 represent the water quantity and quality results of continuous simulation of pond model.

Table 9.3: Long-term simulation of water quantity.

Parameter	Average Wet Year Condition (April 1978 – November 1998)		Extreme Wet Year Condition (April 1990 – November 1992)	
	(mm)	(m ³)	(mm)	(m ³)
Total precipitation	1,662	255,250	1,860	285,610
Total infiltration	438	67,260	490	75,250
Total evaporation	390	59,880	434	66,700
Surface runoff	874	134,210	983	151,000

Table 9.4: Long-term simulation water quality.

Parameter	Average Wet Year Condition (April 1978 – November 1998)	Extreme Wet Year Condition (April 1990 – November 1992)
	(kg)	(kg)
Total inflow load	186,360	209,000
Total outflow load	16,772	20,450
Removal efficiency(%)	91	90

The long-term SS removal efficiency for the Ballymore Pond was estimated as 91% and 90% for average and extreme wet year conditions. This satisfies the Level 1, Enhanced receiving water protection. This removal performance meets the highest criteria under the MOE SMPD manual ("Enhanced Protection"). However, the overall system performance depends on the receiving water impacts due to actual flow rates and concentration discharged into receiving waters.

The annual sediment-loading rate from the construction site was estimated to be 3.2 and 3.4 m³/ha for average and wet year conditions, respectively. This compares to 1.9 m³/ha for stable watersheds with similar imperviousness (MOE, 2003).

Figure 9.2 represents the sample continuous simulation results in the form of outlet flow and SS concentration for May 2003.

Figure 9.2: Sample long-term continuous simulation results for May 2003.

Figure 9.3 represents the comparison of observed and simulated flow for May 2003 as a model verification.

Fig. 9.3: Comparison of observed and simulated flow for May 2003.

CHAPTER 10

RECEIVING WATER ANALYSIS

This section presents the preliminary impacts assessment for receiving water, due to effluent discharge from construction sediment control facility. The receiving water analysis accounts for concentration and duration of exposure in the receiving water body. Figure 10.1 presents conceptually the receiving water impact assessment approach.

Fig. 10.1: Receiving water impacts assessment approach.

During runoff events the effluent from a catchment enters a control the facility; it enters the watercourse and mixing occurs in the stream. The concentration in the downstream zone depends on:

- Effluent concentration from the ESC facility
- Background concentration in the stream
- Stream flow and pond inflow/outflow rates.

Two methods are used in a preliminary manner to assess the receiving water impacts without mixing and dilution in the receiving stream:

1. Risk on fish habitat due to increase in TSS concentration – relative changes in instream concentration (GOC, 1993) ;
2. Severity of impacts due to TSS concentration and duration of exposure (Ward, 1992, MNR).

The first method quantifies the risk to fish and fish habitat based on the increases in suspended solids concentration above the background levels. Observed pond effluent TSS concentrations are used to evaluate the risks. Table 10.1 summarizes the results and shows the number of events that would impact fish and fish habitat.

Table 10.1: Receiving water impacts due to increases in TSS concentration
(Source:GOC, 1993).

Sediment Concentration Increase (mg/L)	Risk to Fish and Fish Habitat	Number of events during 2002-03 monitoring period
0	No risk	
< 25	Very low risk	2 events
25 –100	Low risk	9 events
100 – 200	Moderate risk	2 events
200 – 400	High Risk	2 events
> 400	Unacceptable risk	1 event

The second impact assessment methodology considers both concentration and duration of exposure to the effluent from the pond. The concentration and duration of exposure curves for the Ballymore pond outlet during monitored events were estimated using the model. Figure 10.2 illustrates concentration and duration of exposure. Points of this curve represent the number of hours when the concentration is exceeded during each event.

Fig. 10.2: Preliminary evaluation of severity of impacts by suspended sediments (Modified from Ward, 1992).

It may be seen that the pond effluent concentration can induce minor to moderate impacts. This evaluation should be treated as preliminary because no mixing or dilution is considered in the analysis.

Although the design standard of Ballymore pond met the requirements of the MOE Stormwater Management Planning and Design Manual criteria, the effluent TSS concentration can impact on fish and fish habitat.

CHAPTER 11

DISCUSSION

This chapter covers a range of issues, which may influence the outcome of the study. The possibilities for water quality results being affected by different factors are investigated.

There are several issues concerning the monitoring program and modelling methodology that arise from this study. One of the critical factors that can alter the results is the methodology of monitoring stormwater events. For example, sampling time is a major concern. During the Fall 2002 sampling period samples were collected at the beginning of the event every 5 minutes, which mean that full sample collection of 24 bottles was completed in two hours. Analysis of hydrographs indicates that the collection of samples was completed before the flow reached its peak in the hydrograph. Looking at the event of September 14, 2002, for example (Figure 11.1): the hydrograph consisted of two peaks. The second flow peak followed the first one after 4.5 hours. However, collection was completed in two hours and the pollutograph depicts only the first flow peak. Thus, complete information on observed water quality was not available for further analysis and modelling. During the second monitoring period, which started in May 2003, the sampling time was changed to collect every 15 minutes instead of 5 minutes. It extended the collection time to 6 hours. This time extension allowed for a much better representation of events. Results for events with rainfall depth less than 10 mm were affected the most. For example, event of May 2, 2003 is characterized by rainfall of 6.8 mm (Figure 11.2). It produced pollutograph that extended almost to the end of hydrograph.

Issues involving interpretation of the events could also influence the study results. Mainly, this concerns determining the start and end time of events in case of back-to-back events. This is because the start/end times will alter the calculation of the total volume of the hydrograph. The value of total volume is essential due to certain reasons, such as: (i) total volumes are used to calculate the centroids of the hydrographs, which are used to determine the hydraulic detention time; (ii) total volumes are used to calculate the mass loads and performance data. In some events it is difficult to determine the real proper timing.

September 14th, 2002

Fig.11.1: Hydrograph and pollutograph for September 14, 2002 event.

Fig.11.2: Hydrograph and pollutograph for Mayv2, 2003 event.

In this case, when observed data is critical for proper model calibration, it is important to maintain a standard method of determining start/end time of an event. To identify inter-event time for individual events 12 hours was selected. For example, event of May 11-12, 2003 (Figure 11.3): the inter-event time of 14 hours is observed between rainfalls. Thus, the event of May 11-12 was separated on two events: May 11th and May 12th.

May 11-12, 2003

Fig. 11.3: Hydrographs and rainfall for May 11-12, 2003 event.

Suspended solids load from an event may also be influenced by the presence of bulkheads at the inlets prior to the construction sediment ponds. During the study water quality samples were collected downstream from the bulkhead. At the end of the fall sampling period visual observations revealed that a significant amount of sediment had accumulated at the bulkhead, almost reaching the top. Therefore, it is possible for the sediment accumulated behind the bulkhead to be stirred up by the incoming runoff from a new event and be carried into the pond.

13 out of 21 analyzed samples from the construction catchment exhibited initial SS concentration (the very beginning of sampling) significantly higher than those at the end of sampling. For example, at the beginning of the September 20, 2002 event, SS concentration was 34000 mg/L and by the end of the 2-hours sampling period it decreased to 166 mg/L. The June 4, 2003 event experienced a decrease in SS concentration from

3380 mg/L to 59 mg/L. The concentration of SS in the August 11 and September 15, 2003 events went down from 4190 mg/L and 3030 mg/L to 18 mg/L and 39.4 mg/L, respectively. The higher initial SS concentration could have been influenced by presence of a bulkhead. During intense storm events, sediments behind the bulkhead could have been stirred up. Thus, initial samples collected within the first hour showed a much higher SS concentration. The rainfall intensity at the beginning of a storm could also be an important factor affecting stormwater mixing with sediments collected behind the bulkhead. This possibility was investigated. A scatter plot between average rainfall intensity during the first 2 hours of a storm and first hour average SS concentration is illustrated in Fig. 11.4. It is obvious from the graph that correlation between the two variables is very small. It was calculated as 0.11, indicating that high initial inflow concentration of SS was not influenced by presence of a bulkhead during storms with high rainfall intensity.

Fig. 11.4: Relationship between rainfall intensity and SS concentration

Other factors that may have influenced the water quality results include rainfall depth, intensity, duration, and interevent dry periods. According to results from a study in Maryland (Schueler and Lugbill, 1990), median SS concentration increases with the increase in rainfall depth. Table 11.1 contains data to calculate the correlation between median SS concentration and rainfall depth, rainfall duration, average intensity and interevent days.

Table 11.1: Rainfall characteristics vs. median concentration.

Event	Rainfall Depth (mm)	Rainfall Duration (hr)	Average intensity (mm/hr)	Interevent Period (days)	Median SS Concentration (mg/L)
14-Sep-02	28.8	8.4	3.5	23.3	3602.1
20-Sep-02	13.3	5.3	2.6	0.5	2295.8
27-Sep-02	18.4	8.9	2.1	4.5	5085.5
2-Oct-02	10.0	13.8	0.7	5	8499.5
19-Oct-02	13.0	23.5	0.6	0.1	1278.8
25-Oct-02	9.4	6.3	1.5	1.9	12457.0
2-May-03	6.8	9.5	0.7	0.6	406.7
5-May-03	17.4	14.5	1.2	3.4	313.4
11-May-	17.8	13.8	1.2	4.8	1451.0
20-May-	10.8	4.5	2.2	3.5	682.5
11-Aug-03	14	5.8	2.2	2.0	250.6
15-Sep-03	15.0	9.8	1.5	0.7	103.3
19-Sep-03	38.0	23.8	1.6	2.4	108.1
22-Sep-03	25	8.5	2.8	2.2	246.6
14-Oct-03	30.7	19.0	1.6	10.6	265.4
2-Nov-03	32.2	49.3	0.7	2.6	156
R²	0.13	0.07	0.001	0.01	

There is no correlation found between median SS concentration and rainfall characteristics.

Logically, longer detention/drawdown time results in more opportunity for sediments to settle followed by increase in removal efficiency of the management facility. An attempt to establish the relationship between detention/drawdown time and removal efficiency based on simulated results and instantaneous removal efficiency was undertaken. Table 11.2 contains data for detention/drawdown times and removal efficiencies. The obtained results are shown in Figures 11.5-11.8 and are as follows: there is no evidence of a correlation between detention/drawdown time and removal efficiency found in this study.

Table 11.2: Relation between detention/drawdown times and removal efficiency.

Event Date	Removal Efficiency	Detention Time (hr)	Drawdown Time (hr)
14-Sep	53.5%	11.4	25.8
20-Sep	47.7%	10.1	51.5
27-Sep	95.7%	13.4	107.8
2-Oct	99.7%	8.1	36.5
19-Oct	81.9%	9.9	39
25-Oct	99.3%	15.4	94.3
2-May	92.9%	7.8	24.3
5-May	99.4%	19.9	27.3
20-May	94.3%	16.6	16
15-Sep	95.1%	9.8	86.5
19-Sep	96.5%	15.3	179
2-Nov	82.2%	39.5	-

Fig. 11.5: Relation between detention time and RE based on simulation data.

Fig. 11.6: Relation between drawdown time and RE based on simulated data.

Fig. 11.7: Relation between detention time and instantaneous RE.

Fig. 11.8: Relation between drawdown time and instantaneous RE.

CHAPTER 12

SUMMARY OF RESULTS.

CONCLUSIONS AND RECOMMENDATIONS

12.1 Summary of Results

12.1.1 Water Quantity

A total of 27 storm events were monitored during the study period. Due to the fact that not all rain or flow data was available, only some of the sample events were included in this analysis. A total of 21 storms were characterized hydrologically: (i) 6 large storms (greater than 20 mm); (ii) 8 medium sized storms (between 10 and 20 mm); 3 small storms (less than 10 mm). Storms less than 6 mm of rainfall produced a negligible amount of runoff, probably due to the initial abstraction losses and high infiltration resulting from soil exposure and construction conditions. Therefore, they were not included in the analysis.

As expected, runoff coefficients gradually increase as development proceeded. On average 25%, 41%, and 58% of rainfall appeared as surface runoff during storm events over the three monitoring period (i.e., September – October 2002, May – July 2003, and August – November 2003).

Outflow hydrographs from the pond show that this SWM facility significantly shaved the peak flow rates of the inlet hydrograph during storm events. Peak flow rates were substantially attenuated as stormwater passed through the facility. The average difference between inflow and outflow peak values was found to be 82%.

The drawdown times, defined as the time between maximum and minimum active storage volumes during a storm, were also estimated from the observed hydrographs. On average, the drawdown time was estimated at about 46 hours with a range from 14 to 107 hours. Longer drawdown times occurred during larger events as a result of hydrograph recession. Shorter times occurred because of smaller inflow volumes.

12.1.2 Water Quality

Water quality summary analysis was based on observed data obtained from the field measurements throughout the study period and simulated data obtained through modeling exercise.

Suspended Solids (SS) is the most critical constituent in construction site runoff in terms of concentration and loading. Furthermore, suspended sediments act as carriers for other constituents (phosphorus, metals and organics). Hence, SS serves as a direct and indirect measure of overall performance of the sediment control pond.

The following summarizes the water quality findings based on discrete sampling:

- The average observed event mean concentration (EMC) of suspended solids at the inlet of construction watershed was 3,620 mg/L, ranging from 238 to 16,550 mg/L;
- The instantaneous suspended solids concentration was recorded as high as 34,000 mg/L in one of the events.
- The average simulated inflow SS EMC was 2,254 mg/L, within a range of 385 mg/L to 7,813 mg/L.
- The average observed EMC of suspended solids at the outlet was 120 mg/L. The range was from 7 mg/L to 670 mg/L.
- The average simulated outflow EMC was 93 mg/L, ranging from 16 mg/L to 278 mg/L.
- The average observed SS load removal efficiency during the sampling period was estimated to be 94%.
- The average SS load removal efficiency was estimated from the simulation model using the entire pollutographs as 87%.

The following summarizes findings from composite samples analysis:

- Turbidity levels for the outlet were found to experience a significant increase throughout the study period: 81 NTU in the Fall 2002 period changed to 166 NTU in the May-July 2003 and to 605 NTU in the last sampling period indicating that fine particles are gradually accumulating in the pond. Average turbidity level for the outlet is 284 NTU that is harmful to receiving fish habitat.

- Nutrients varied in their removal efficiencies: average removal efficiency for TKN was 60% and for total phosphorus (TP) reached as high as 83%. Although TP experienced quite high removal efficiencies throughout the study period, outflow average EMC is estimated as 0.24 mg/L, which is significantly higher than the recommended value of 0.03 mg/L.
- Metals also varied in their removal efficiencies: metals with average removal efficiencies above 50% in the Fall 2002 include barium, calcium and strontium; in May-July 2003: aluminum, barium, calcium, cobalt, manganese, nickel, lead, vanadium, and zinc. This indicates that the pond performed better in the second sampling period. In the last period of August-November 2003 only metals such as cadmium, manganese and zinc experienced removal efficiency higher than 50%. During all three monitoring periods, average effluent concentration of copper and iron exceeded Ontario's PWQO's. Cobalt's effluent concentration exceeded provincial objectives only during August-November 2003 period.
- The particle size distribution from the construction site was skewed towards the finer particles. The particle size distribution of incoming sediments was composed of extremely fine-grained particles, primarily consisting of fine silts, clays, and colloidal materials particles. 90% of particles entering the pond from both inlets were found to be finer than 30 microns. 90% of particles exiting the pond were smaller than 15 microns in diameter.
- The clay fraction (smaller than 4 μm) contributed 40.8-45% of the weight to the suspended solids material in the influent. The silt-size fraction contributed more (50.0-53.6%), with the remaining sand-size fraction contributing only 5.0-5.6%. Effluent characteristics are: content of clay fraction is 56.5%, silt and sand-size are 40.7% and 2.8, respectively.

12.1.3 Continuous Simulation and Receiving Water Analysis

In order to estimate the sediment loads and pond performance during the study period from September 2002 to November 2003, and also for the model's verification, long-term simulation PCSWMM was conducted.

For the study period average SS concentration for the inflow is found to be 2033 mg/L and for the outflow 99 mg/L. These values are closely matched with average EMC's simulated on event basis.

Also, load-based pond performance during the period of 2002-2003 using continuous simulation was estimated as 95% compare to load-based removal efficiency of 87% simulated on event basis and 96% of instantaneous RE calculated from field data.

It was estimated that 0.11m of sediments were accumulated at the bottom of the pond with a rate of 5.1 m³/ha during August 2002-November 2003 period.

Long-term continuous simulation was also conducted to estimate the cumulative construction sediment loads leaving the site. Two sets of three-year hourly rainfall data corresponding to average and extreme wet year conditions were considered.

The annual sediment-loading rate from the construction site was estimated to be 3.2 and 3.4 m³/ha for average and wet year conditions, respectively. This compares to U.S. EPA data of 1.9 m³/ha for stable watersheds with similar imperviousness.

The long-term SS removal efficiency for the pond was estimated as 91.0% and 90.0% for average and extreme wet year conditions respectively.

May 2003 rainfall events were used for verification of the model, which showed a good comparison with observed data.

12.2 Conclusions and Recommendations

The primary objective of this study was to assess the performance of storm water management facilities designed according to the MOE SWMP manual for treating urban construction storm runoff prior to discharging in receiving water bodies. The scope included assessment of typical hydrologic conditions of a construction site, sediment characteristics and performance of sediment control pond in terms of water quantity and quality.

Construction site runoff differs significantly from stormwater runoff over developed areas. Large loads entering the ESC facility mean a significant amount of sediments leave the facility, even with high removal effectiveness. From this study, concentration of suspended solids in construction runoff was on average 200 times higher than in urban runoff from developed areas.

This study demonstrates that significant water quality improvement can be achieved through implementation of SWM facility such as sediment control pond during the construction activities. The field data collection and analysis show that the Ballymore pond meets the target in terms of suspended solids removal efficiency ($> 80\%$). However, despite the high removal efficiency, effluent concentration of suspended solids remains elevated and receiving water impacts to fish and fish habitats can be expected. Also, outflow concentrations of total phosphorus and several metals, such as copper, iron and cobalt, exceeded the Province Water Quality Objectives. These results suggest that: (i) stormwater basins designed to prevent downstream pollution associated with sediments may not be as effective in removing chemical pollutants and elevated turbidity as they are in removing sediments; (ii) the concentrations exiting the pond should serve as the determining factor of the pond's performance rather than the removal efficiencies.

The stage of construction influenced the event mean concentration of SS showing a greater concentration of suspended solids during the most active housing development stage. Sediment inflow was rapid for the entire construction period (including time required for the building sodding and landscaping of individual lots). Once a catchment area was completely developed and vegetation was established, sediment inflow dropped significantly. Study showed that outflow turbidity levels were increasing throughout the monitoring period and reached as high as 600 NTU on average at the end of the study period. These values significantly exceed 'safe' levels for receiving waters.

Based on model verification results, the study indicated that modelling of pollution from a construction site is a useful tool, which can support monitoring programs for effective decision-making.

Overall, the performance of the construction site sediment control pond was found to be unsatisfactory. The elevated levels of suspended solids have the potential of producing

adverse effects on the receiving watercourses depending on the relationship between suspended solids concentration and duration. The following recommendations to improve the pond's effectiveness are made:

- Sediment control pond should be constructed at the start of the construction process to ensure the capture of sediment from all phases of construction.
- The sizing criteria for sediment control ponds should be consistent with the ultimate SWM facility (MOEE, 2003). This includes "Enhanced Level of Protection". This would bring the level of protection during construction to the highest standard presently practiced. Also, the outflow concentration of suspended solids should be identified and an approximate level of (e.g., 25 mg/L) (Ward, 1992) maintained.
- The permanent pool for the sediment control pond should be cleaned when it is half full of sediment (i.e., $125 \text{ m}^3/\text{ha} * 50\% = 63 \text{ m}^3/\text{ha}$) to ensure its proper performance.
- The banks of the sediment control ponds suspected to be significant sources of soil erosion and sediment contributions to the storage facility. Slope stabilization should be a high priority in pond construction.
- To provide temporary soil stabilization and prevent soil erosion chemical stabilizers, or soil binders, may be used: materials such as vinyl, asphalt, or rubber can be sprayed onto the surface of exposed soils to hold the soil in place.
- Particle size distribution analysis shows that construction sediment is comprised primarily of smaller particles. The low settling velocity of smaller particles yield lower treatment effectiveness as compared with stable urban sites and highlight the need for enhanced source controls. Other measures, such as outflow polishing through vegetation filtering or sand trenches could be considered. The introduction of devices such as microfilters at stormwater pipe outlet should be considered to capture the small sediments from the outflow.
- To decrease turbidity levels, alternative methods such as chemical flocculation may be used.

- Receiving water impacts would best be determined from site-specific monitoring. This should include a comprehensive baseline monitoring before construction. Conditions at the outlet of the pond and downstream within the receiving stream should be included.
- The overall ESC effectiveness could be improved by reducing the amount of sediments reaching the ESC pond. Other 'at-source' ESC practices should continue to be implemented and other practices such as earlier re-vegetation could be enhanced. Effective use of ESC measures at the source, upstream of the pond, will reduce the incoming sediment load and improve the overall removal efficiency.
- The ESC controls should be inspected frequently to verify their effectiveness, particularly after runoff events. Inspection records should be created to document the inspection and repairs.
- Further study is recommended to investigate the potential harm to fish and the organisms by increased suspended sediment concentrations and duration of exposure.

References

- Akan, A.O., Houghlalen, R.J. *Urban Hydrology, Hydraulics and Stormwater Quality*. John. Wiley & Sons, Inc. Hoboken, New Jersey, 2003.
- Baffaut, C. and Delleur, J.W. "Calibration of SWMM Runoff Quality Model with Expert System". *Journal of Water Resources Planning and Management*, vol. 116(2), pp. 247-261, 1990.
- Bannerman, R., Owens, D., Dodds, R. and Hornewer, N. "Sources of Pollutants in Wisconsin Stormwater". *Water Science and Technology*, vol. 28(3-5), pp. 241-259, 1993.
- Bhadury, B., Harbor, J. Maurice, P. "Chemical trap Efficiency of a Construction Site Stormwater Retention Basin". *Physical Geography*, vol. 16(5), pp. 389-401, 1995.
- Chapra, S.C. *Surface Water Quality Modeling*. McGraw-Hill, 1997.
- Charbeneau, R.J., Barrett, M.E. "Evaluation of Methods for Estimating Stormwater Pollutant Loads". *Water Environment Research*, vol. 70, pp. 1295-1302, 1998.
- Choi, K., Ball, J.L. "Parameter Estimation for Urban Runoff Modelling". *Urban Water*, vol. 4, pp. 31-41, 2002.
- Chorley, R.J., Schumm, S.A. and Sugden, D.E. *Geomorphology*. Cambridge, United Kingdom, 1984.
- Chui, T.W., Mar, B. W. and Horner, R.R. "A Pollutant Loading Model for Highway Runoff". *Journal of Environmental Engineering, ASCE*, vol. 108(6), pp.1193-1210, 1982.
- Clarifica Inc. "Investigation to Develop an Improved Sizing Approach for Construction Sediment Control Facilities". Prepared for: Department of Fisheries and Oceans Canada. File Number: DF01-0001, March 2002.

Clarifica Inc. "Preliminary Assessment for Improved Design Criteria for Construction Sediment Control Ponds". Prepared for Toronto and Region Conservation Authority and Fisheries and Oceans Canada. File: IR01 – 0001, March 2003.

Clarifica Inc., 2003. "Preliminary Assessment for Improved Design Criteria for Construction Sediment Control Ponds". Prepared for Toronto and Region Conservation Authority and Fisheries and Oceans Canada, March 2003. File: IR01 – 0001.

Delleur, J.W. "Modeling Quality of Urban Runoff". *Hydroinformatic Tools fro Planning, Design, Operation and Rehabilitation of Sewer Systems*. Marsalek, J. et al. (Eds). Kluwer Academic Publishers, Netherlands, pp. 242-285, 1998.

Dent, S. "Automated Calibration using Optimization Techniques with SWMM RUNOFF". SWMM Users Conference, Toronto, Canada, February 20-21, 2003.

Dodson, R. D., *Storm Water Pollution Control*, McGraw-Hill, 2000.

Elliot, William J. and Andy D. Ward. *Environmental Hydrology*. Lewis Publishers. New York, 1995.

Ellis, J.B. "The Management and Control of Urban Runoff". *Journal of Water Resources Planning and Management*, vol. 3(2), pp.116-124, 1989.

Environmental protection Agency (EPA). Handbook. *Urban Runoff Pollution Prevention and Control Planning*. Office of R & D. Center for Environmental Research Information. Cincinnati, Ohio, 1993.

Fennesey, L.A.J., Hamlett, J.M., Aron, G. and LaSota, D. "Changes in Runoff due to Stormwater Management Pond Regulations. *Journal of Hydraulic Engineering*, vol. 6(4), pp. 317-327, 2001.

Ferrara, R.A. and Witkowski, P. "Stormwater Quality Characteristics in Detention Basins". *Journal of Environmental Engineering, ASCE*, vol. 109(2), pp. 428-447, 1983.

Fifield, J. S. *Designing for Effective Sediment and Erosion Control On Construction Sites*. Forester Press, 2002.

GOC. "The Yukon Placer Authorization". Government of Canada. Authorization and supporting documents applicable to placer mining in the Yukon Territory. Ottawa, 1993.

Goldman, S., Jackson, K., and Butskynsny, T., *Erosion and Sediment Control Handbook*. McGraw-Hill, New York, 1986.

Greb, S.R., Bannerman, R.T. "Influence of Particle Size on Wet Pond Effectiveness". *Water Environment Research*, vol. 69, pp. 1134-1138, 1997.

Greenland International Consulting Inc., and Toronto and Region Conservation Authority (TRCA). "Urban Construction Sediment Control Study". April 2001. File Number: 00-G-1320, 2001.

Gupta, H.V. and Sorooshian, S. Yapo, P.O. "Toward Improved Calibration of Hydrologic Models: Multiple and Noncommensurable Measures of Information". *Water Resources Research*, vol. 34(4), pp. 751-763, 1998.

Harbor, J. "Engineering Geomorphology at the Cutting Edge of Land Disturbance: Erosion and Sediment Control on Construction Sites". *Geomorphology*, vol. 31, pp.247-263, 1999.

Harbor, J.M., Snyder, J., Storer, J. "Reducing Nonpoint Source Pollution from Construction Sites Using Rapid Seeding and Mulching". *Physical Geography*, vol. 16(5), pp. 371-388, 1995.

Hoffman. D.W. and Richards, N.R. *Soil Survey of York County*. Report No. 19 of the Ontario Soil Survey. Ministry of Agriculture and Food. Reprinted February 1990. Guelph, ON, 1955.

Horner, R.R., Guedry, J. and Kortenhoff, M.N. *Improving the Cost Effectiveness of Highway Construction Site Erosion and Pollution Control*. Washington State Transportation Center and the Federal Highway Administration. Seattle, WA, 1990.

Huber, W.C. "Contaminant Transport in Surface Water". In *Handbook of Hydrology*. McGraw-Hill, Inc., New York, 1993.

Huber, Wayne C. and Robert E. Dickinson (USEPA). *Storm Water Management Model Version 4: User's Manual*. Environmental Research.

Ibrahim, Y. "A Method of Estimating Optimal Catchment Model Parameters". *Water Resources Research*, vol. 29(9), 3049-3058, 1993.

ISCO Inc. 1997a. *6700 Portable Samplers Instruction Manual*. 60-9004-021. Revision, I 60-9003-411 D 7-98. Lincoln, Nebraska, July 1997.

ISCO Inc. 1997b. *4150 Flow Logger Instruction Manual*. 60-3244-074. Revision I, 60-3243-143, July 1997.

James, W. and James, W.R.C. *Water Systems Models [1,2]*. User's guide to SWMM4 RUNOFF and supporting modules, University of Guelph and CHI, 2000.

James, W. *Hydrology & Hydraulics Vocabulary for Engineers*. Computational Hydraulic International, Guelph, Ontario, Canada, 1995.

James, W. *Rules for Responsible Modeling*. 4th edition. CHI, Guelph, Ontario, 2003.

Jewell, T.K. and Adrian, D.D. "SWMM Stormwater Pollutant Washoff Functions". *Journal of Environmental Engineering Division, ASCE*, vol. 104(5), pp. 1036–1039, 1978.

Jewell, T.K., Nunno, T.J. and Adrian, D.D. "Methodology for Calibrating Stormwater Models". *Journal of Environmental Engineering Div., ASCE*, vol. 104(3), 485-501, 1978.

Laboratory Office of Research and Development U.S. Environmental Protection Agency Athens, Georgia 30613. EPA/600/3-88/001a, 1992.

Lei, J., Li, J. and Schilling, W. "Stepwise Hypothesis Test Model Calibration Procedure of Urban Runoff Design Model and an Alternative of Monte-Carlo Simulation".

- Li, James. *Erosion and Sediment Control Training Manual*. Prepared for the Ministry of the Environment, Ryerson Polytechnic University, 1998.
- Linsley, R.K. Jr., Kohler, M.A., Paulhus, J.L.H. *Applied Hydrology*. Mc Graw-Hill Book Company, Inc., 1949.
- Marsalek, J, Watt, W.E., Anderson, B.C., and Jaskot, C. "Physical and Chemical Characteristics of Sediments from a Stormwater Management Pond". *Water Quality Research Journal of Canada*, vol. 32(1), pp. 89-100, 1997.
- Maryland Department of Environment. Maryland Stormwater Manual (Vol.1), 2000 <http://www.mde.state.md.us/assets/document/chapter1.pdf>.
- Ministry of Environment SWAMP Report. TRCA. Performance Assessment of a Stormwater Retrofit Pond-Harding Park, Richmond Hill, Ontario, 2002.
- Ministry of the Environment (MOE). *Stormwater Management Planning and Design Manual*, March 2003.
- Newman, T.L. II, Omer, T.A. and Droskoll, E.D. "SWMM Storage-Treatment for Analysis/Design of Extended-Detention Ponds". *Applied Modeling of Urban Water Systems. Monograph 8*. Edited by W.James. CHI, Guelph, Ontario, 2000.
- Nix, Stephan J. *Urban Stormwater Modelling and Simulation*. Lewis Publishers, London, 1994.
- Norman, C.G. "Urban Runoff Effects on Ohio River Water Quality". *Water Environment & Technology*, vol. 3, pp. 44-46, 1991.
- Novotny, V. and Chesters, G. "Delivery of Sediment and Pollutants from Nonpoint Sources: A Water Quality Perspective". *Journal of Soil and Water Conservation*, vol. 67, pp. 443-446, 1989.

Oliver, L.J. and Grigoropoulos, S.G. "Control of Storm-Generated Pollution Using a Small Urban Lake". *Journal (Water Pollution Control Federation), ASCE*, vol. 53(5), pp. 594-603, 1981.

Papa, F., Adams, B.J., and Guo, G. "Detention Time Selection for Stormwater Quality Control Ponds". *Canadian Journal of Civil Engineering*, vol. 26, pp. 72-82, 1999.

Przepiora, A., Hesterberg, D., Parsons, J.E., Gilliam, J.W., Cassel, D.K., and Faircloth, W. "Field Evaluation of Calcium Sulfate as a Chemical Flocculant for Sedimentation Basins". *Journal of Environmental Quality*, vol. 27, pp. 669-678, 1998.

Przepiora, A., Hesterberg, D., Parsons, J.E., Gilliam, J.W., Cassel, D.K., and Faircloth, W. "Calcium Sulfate as a Flocculant to Reduce Sedimentation Basin Water Turbidity". *Journal of Environmental Quality*, vol. 26, pp. 1605-1611, 1997.

Pyatt, L. "Performance Evaluation of a Sediment Control Pond". M.A.Sc. Thesis. Environmental Applied Science and Management Program. Ryerson University, Toronto, Ontario, 2003.

Randall, W. "Stormwater Detention Ponds for Water Quality Control". Proceedings, Edited by W DeGroot, Engineering Foundation, *Urban Water Resources Research Council of ASCE*, 1982.

Robbins, C.W. and Brokway, "Irrigation Water Salt Concentration Influences on Sediment Removal by Ponds". *Soil Science Society of America Journal*, vol. 42, pp. 478-481, 1978.

Sabourin Kimble and Associates Ltd. 2000. "Stormwater Management Facility 4ab, Design Brief, Ballymore on Bayview Development, OPA 129 – 19T-86100, Town of Richmond Hill". Project No. 99:905:D1#3649. June 16, 2000. Revised September 8, 2000.

Sansalone, J.J. and Buchberger, S.G. "Partitioning and First Flush of Metals in Urban Roadway Stormwater". *Journal of Environmental Engineering*, vol. 123(2), 134-143, 1997.

Schueler, T. R., and J.Lugbill. *Performance of Current Sediment Control Measures at Maryland Construction Sites*. Report. Department of Environmental Programs, Metropolitan Washington Council of Governments, Washington DC, 1990.

Schuler, T.R. and Holland, H.K. *The Practice of Watershed Protection*. Center for Watershed Protection. Ellicott City, USA, 2000.

Town of Richmond Hill. 2004. "Lake Wilcox".

http://www.town.richmond-hill.on.ca/subpage.asp?pageid=parks_lake_wilcox.

TRCA. Performance Assessment of an Off-Line Stormwater Management Pond. Heritage Estates Stormwater Management Pond. Richmond Hill, Ontario, 1996.

Tsihrintzis, V.A. and Hamid, R. "Modeling and Management of Urban Stormwater Runoff Quality: A Review". *Water Resources Management*, vol. 11, pp. 137-164, 1997.

Tsihrintzis, V.A., Hamid, R. "Runoff Quality Prediction from Small Urban Catchments Using SWMM". *Hydrological Processes*, vol.12, pp. 311-329, 1998.

Viessman, W. Jr., Lewis, G.L. *Introduction to Hydrology*. Prentice Hall, Pearson Education, Inc., New York, 2002.

Viessman, Warren Jr., Gary L. Lewis, and John W. Knapp. *Introduction to Hydrology* - 3rd edition. Harper Collins Publishers, New York, 1989.

Wanielista, M. P. and Yousef, Y.A. *Stormwater Management*. John Wiley & Sons, Inc., New York, 1993.

Ward, N. "The Problem of Sediment in Water for Fish". Northwestern Ontario Boreal Forest Management Technical Notes. Ontario Ministry of Natural Resources, 1992.

Warwick, J.J. and Tadepalli, P. "Efficacy of SWMM Application". *Journal of Water Resources Planning and Management*, vol. 117(3), pp. 352-366, 1991.

Water Quality Guidelines (criteria) for Turbidity, Suspended and Benthic Sediments, 1988. Updated 2001.

<http://wlapwww.gov.bc.ca/wat/wq/BCguidelines/turbidity.html>.

Whipple, W. Jr. "Dual-Purpose Detention Basins". *Journal of the Water Resources Planning and Management Division*, vol. 105(WR2), pp. 403-412, 1979.

Whipple, W., Grigg, S., Gizzard, T., Randall, C.W., Shubinski, R.R., and Tucker, L.S. *Stormwater Management in Urbanizing Areas*. Prentice Hall, New Jersey, 1983.

Wu, J.S., Holman, R.E. and Dorney, J.R. "Systematic Evaluation of Pollutant Removal by Urban Wet Detention Ponds". *Journal of Environmental Engineering*, vol. 122(11), pp. 983-988, 1996.

Zaghloul, N. A. "Sensitivity Analysis of the SWMM Runoff-Transport Parameters and the Effects of Catchment Discretization". 1981 International Symposium on Urban Hydrology, Hydraulics, and Sediment Control. University of Kentucky, Lexington, Kentucky-July 27-30, 1981.

Zaghloul, N. and Al-Shurbaji, A. M. "A Storm Water Management Model for Urban Areas in Kuwait". *Water Resources Bulletin, AWRA*, vol. 26(4), pp.563–575, 1990.

Zoppou, C. "Review of Urban Storm Water Models". *Environmental Modelling & Software*, vol. 16, pp. 195-231, 2001.

APPENDICES

- A. Analytical Procedures, Ontario Ministry of the Environment, Laboratory Services.
- B. Summary of the collected data for the duration of study.
- C. Summary of Hydrologic Characteristics.
- D. Observed Hydrographs vs. Rainfall. (Data is available.)
- E. Pollutographs for Each Event. (Data is available.)
- F. Pond Performance for Composites. (Data is available.)
- G. Constituents Concentrations. (Data is available.)
- H. Particle Size Distributions on Event Basis. (Data is available.)
- I. Quantity and Quality Calibrated Input Parameters
- J. Examples of PCSWMM Input Files. (Data is available.)
- K. Comparison of Observed and Simulated Hydrographs. (Data is available.)
- L. Comparison of Observed and Simulated Pollutographs. (Data is available.)

Appendix A

Analytical Procedures, Ontario Ministry of the Environment, Laboratory Services

	Parameter	Method
General Chemistry	Chloride	Colorimetry following two-stage reaction with mercuric thiocyanite and ferric iron
	Conductivity, pH, Alkalinity	Automated system using electrodes in a constant temperature bath for conductivity, a calibrated potentiometric system for pH and titration for TFE alkalinity (to an end-point of pH 4.5).
	Silicon: reactive silicate; Dissolved organic carbon; and Dissolved inorganic carbon	<p>Molybdate reactive silicates: dissolved reactive silicate ions are measured through the formation of molybdenum heteropoly blue complex</p> <p>Dissolved inorganic carbon (+ carbon dioxide) are measured by acidifying the sample supernatant, extracting the CO₂ through a dialysis membrane and reacting it with phenolphthalein and colourimetric measurement</p> <p>Organic carbon is measured in the sample supernatant by acidification followed by nitrogen flushing to remove inorganic carbon and UV digestion in an acid-persulphate medium. The resulting CO₂ is analyzed as above</p>
	Solids: Suspended Dissolved Total	<p>Total Solids: refers to the material (residue) which remains after an aliquot of well-mixed sample is transferred into a tared dish and evaporated to dryness (20 hrs minimum) at 102 ± 2° C.</p> <p>Suspended Solids refers to all material (residue, particulate) which is removed from a sample when a well-mixed sample aliquot is filtered through a 1.5 to 2.0 µm glass fibre filter. The material on the filter is dried at 103 ± 2°C.</p> <p>Dissolved solids refer to the material (residue, filtrate) which remains in solution when a well-mixed sample is filtered through a 1.5 – 2.0 µm glass fibre filter. An aliquot of the filtrate (50 or 100 mL) is transferred, using a transfer pipette, into a tared dish and evaporated to dryness (20 hrs minimum), at 103 ± 2°C.</p>
	Chemical Oxygen Demand	Samples are mixed with an acidified Potassium Dichromate Solution that contains mercuric sulphate to suppress chloride interference. Concentrated sulphuric acid containing silver sulphate as a catalyst is added and the mixture is digested in a mechanical-convection oven for 3 hrs at 149 ± 1°C. Analysis is completed by automated colorimetric measurement of trivalent chromium.

	Particle Size	Optical – laser light diffraction (Coulter LS130 Particle Size Analyzer) This method is capable of analyzing from 0.1 to 900 μm in 27 size channels. However, it is reported as a percent distribution by volume (no count data).
	Turbidity	Measurement of light scattering at $90^\circ \pm 30^\circ$ by nephelometry calibrated to Formazin turbidity standards
Metals	<u>Total Metals:</u> Aluminum, Barium, Beryllium, Calcium, Cadmium, Cobalt, Chromium, Copper, Iron, Magnesium, Manganese, Molybdenum, Nickel, Lead, Strontium, Titanium, Vanadium, and Zinc	Inductively coupled plasma (ICP) following ultrasonic nebulizer
Nutrients	<u>Total Nutrients:</u>	
	Total P	Total P: digestion in sulphuric acid, potassium sulphate media followed by reduction with ascorbic acid – measured a orthophosphate
	TKN	Total Kjeldahl Nitrogen: digestion with Kjeldahl's reagent, neutralization and analysis for ammonia species by colorimetry
	<u>Dissolved Nutrients:</u> Ammonia+ Ammonium Nitrite Nitrate+nitrite Phosphate	Simultaneous, automated analysis of one aliquot of sample: <ul style="list-style-type: none"> – Ammonia by conversion to indophenol blue with sodium nitroprusside as a catalyst – Nitrite by colourimetric method after reaction with sulphanilamide and N (1-naphthyl) ethylenediamine dihydrochloride – Nitrate + nitrite by colorimetric method following conversion of nitrate to nitrite – Phosphorus, as orthophosphate, by colorimetric method following reaction with ascorbic acid

Appendix B

Summary of the collected data for the duration of study

Date			Data									
			Flow			Discrete (TSS)			Composite (TSS)			Rain
			1070	510	Outlet	1070	510	Outlet	1070	510	Outlet	
2002	1	14-Sep	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
	2	20-Sep	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
	3	27-Sep	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
	4	2-Oct	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
	5	19-Oct	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
	6	25-Oct	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
2003	7	2-May	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
	8	5-May	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
	9	11-May	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
	10	20-May	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
	11	4-Jun	Y	N	Y	Y*	N	Y	N	N	Y	Y
	12	8-Jun	Y	Y	Y	Y	N	Y	Y	N	N	Y
	13	13-Jun	Y	Y	Y	N	N	Y	N	Y	N	Y
	14	22-Jul	Y	Y	N	N	N	N	Y	Y	N	Y
	15	2-Aug	Y	Y	N	Y	Y	N	Y	Y	N	N
	16	9-Aug	Y	Y	N	Y	Y	N	Y	Y	N	Y
	17	11-Aug	Y	Y	N	Y	Y	N	Y	Y	N	Y
	18	26-Aug	N	Y	N	Y	Y	N	Y	Y	N	Y
	19	15-Sep	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
	20	19-Sep	Y	Y	Y	Y	Y*	Y	Y	N	Y	Y
	21	22-Sep	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
	22	27-Sep	N	Y	Y	N	Y	Y	N	Y	Y	Y
	23	14-Oct	Y	Y*	Y	Y	Y	Y	Y	Y	Y	Y
	24	18-Oct	Y	N	N	Y	N	N	Y	N	N	Y
	25	25-Oct	Y	N	Y*	Y	Y	Y	Y	N	Y	Y
	26	2-Nov	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
	27	12-Nov	N	Y*	Y*	N	Y	Y	N	Y	Y	N

Y=Yes, data is available

N=No, data is not available

* Data is not complete

Appendix C

Summary of Hydrologic Characteristics

Ballymore Pond
September 2002-November 2003 Events

Summary of Hydrologic Statistics

	Event Date		Rain					Inlet Combined				Outlet				Runoff Coefficient	Hydraulic Detention Time (hr)	Drawdown Time (hr)
			Total Rainfall (mm)	Duration (h)	Mean Intensity (mm/hr)	Maximum Intensity (mm/hr)	Interevent Period (days)	Total Runoff (mm)	Flow Duration (hr)	Average Flow (l/s)	Peak Flow (l/s)	Total Runoff (mm)	Flow Duration (hr)	Average Flow (l/s)	Peak Flow (l/s)			
1	2002	14-Sep	28.8	8.4	3.5	47.5	23.3	7.1	11.0	26.6	321	6.8	37	7.8	12.6	0.25	11.4	25.8
2		20-Sep	13.3	5.3	2.6	72.5	0.5	2.82	22	5.2	120.4	2.75	30	3.9	8.6	0.21	10.1	51.5
3		27-Sep	18.4	8.9	2.1	7.5	4.5	9.2	36	11.2	144.9	9.8	72	5.8	16.3	0.50	13.4	107.8
4		2-Oct	10	13.8	0.7	17.5	5	3.2	19.6	6.9	99.4	2.2	19.5	4.1	72.4	0.32	8.1	36.5
5		19-Oct	13	23.5	0.6	5	0.1	4.1	23.2	7.5	57.9	4	20	7.7	10.4	0.32	9.9	39
6		25-Oct	9.4	6.3	1.5	5	1.9	4.6	32	6.1	48.9	4.8	36	4.7	7.4	0.49	15.4	94.3
7	2003	2-May	6.8	9.5	0.7	2.4	0.6	3.4	34.8	3.9	24.9	3.3	37.3	3.8	8.4	0.50	7.8	24.3
8		5-May	17.4	14.5	1.2	6.4	3.4	8.5	21.5	16.6	151.4	8.1	70	4.1	16.8	0.49	19.9	27.3
9		11-May	17.8	13.8	1.2	11.2	4.8	7.5	28	10.9	100.1	7.1	40	7.7	16.6	0.42	5.66	29
10		20-May	10.8	4.5	2.2	8.8	3.5	5.5	34.5	6.6	94.7	5.1	48.5	4.5	17.9	0.51	16.6	16
11		4-Jun	13.8	17	0.8	5.6	3.5	5	26.8	7.8	49.5	4.7	54	3.7	10.6	0.36	10.6	14.5
12		8-Jun	23.6	21.3	1.1	19.2	3.4	18.7	40.25	19.7	385.7	26.2	65.5	17	54.1	0.79	14.4	21.8
13		15-Sep	15	9.8	1.5	12.8	0.7	6.3	33	7.6	136.5	6.2	58.3	4.5	14.4	0.42	9.8	86.5
14		19-Sep	38	23.8	1.6	10.4	2.4	25.6	80.5	19.1	243.1	12.1	79	6.5	16.3	0.67	15.3	179
15		2-Nov	32.2	49.3	0.7	5.6	2.6	19.2	75.8	10.8	85.3	10.7	129.5	3.5	7.5	0.60		

Appendix I

Quantity and Quality Calibrated Input Parameters

Quantity Input

Event Date	Phase	Calibrated Quantity Model Parameters				
		WW(3)	WW(1)	WSTORE1	WSLOPE	WW(5)
14-Sep-02	I	33	162	6.3	0.006	0.015
20-Sep-02		15	53	0.5	0.01	0.015
27-Sep-02		45	120	1.5	0.01	0.015
2-Oct-02		35	120	1.5	0.01	0.015
19-Oct-02		44	170	4	0.004	0.015
25-Oct-02		39	120	0.2	0.01	0.015
Average		35	124	2.3	0.008	0.015
2-May-03	II	68	72	0.5	0.01	0.015
5-May-03		56	190	3.55	0.005	0.01
11-May-03		43	130	5	0.02	0.012
20-May-03		76	250	3.65	0.02	0.01
4-Jun-03		52	39	0.9	0.01	0.015
8-Jun-03		88	150	4.5	0.01	0.015
Average		64	139	3.0	0.010	0.013
15-Sep-03	III	47	215	1.1	0.01	0.015
19-Sep-03		71	400	0.8	0.01	0.015
22-Sep-03		90	220	5	0.01	0.015
Average		69	278	2.3	0.010	0.015

Quality Input

Event Date	Phase	Calibrated Quality Model Parameters			
		QFACT(1)	WASHPO	RCOEFF	ERLEN
14-Sep-02	I	400	0.725	0.02	150
20-Sep-02		200	1.5	0.1	56.8
27-Sep-02		300	0.878	0.1	200
2-Oct-02		210	1.2	1	200
19-Oct-02		250	0.64	0.01	150
25-Oct-02		250	1.9	7	100
Average		268	1.141	1.372	143
2-May-03	II	200	2	0.246	20
5-May-03		430	3	0.05	150
11-May-03		210	2.43	0.1852	300
20-May-03		200	2	0.138	100
4-Jun-03		200	2	0.001	173
8-Jun-03		200	1.55	0.438	150
Average		240	2.163	0.176	149
15-Sep-03	III	200	1.217	0.313	300
19-Sep-03		200	1.09	0.059	150
22-Sep-03		265	1.06	0.027	300
Average		222	1.122	0.133	250